

Local Notice to Mariners for Northeast District 09/23/2026

Ambrose Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Ambrose Channel Lighted Buoy 12	34850	LT EXT	FD
Ambrose Channel Lighted Gong Buoy 17	34880	LT EXT	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector New York, Submerged Lands Act (SLA) - Ambrose Channel/General/Marine Construction (Excluding Bridges)/Survey Operations	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Survey Operations From: 2026-09-08 To: 2026-12-14 Location: 40-28-07.320N/074-15-20.268W 40-31-25.392N/073-51-43.092W S. T. Hudson Engineers, Inc. plans to conduct geophysical survey operations aboard the M/V BELLA MARIE in the Raritan Bay area from September 8 through December 13, 2026. The work will occur during daylight hours only, seven days per week, and will not be conducted during hazardous sea or weather conditions. Survey activity will extend from Cheesequake Creek across the Raritan, Chapel Hill, and Ambrose channels, with the survey area beginning near 40° 28' 07.352" N, 074° 15' 20.287" W and ending near 40° 31' 25.423002" N, 073° 51' 43.105434" W. The M/V BELLA MARIE is a 40-foot power catamaran survey vessel. During operations, the vessel will tow survey equipment behind and beneath it, including equipment that may extend up to 250 feet astern, which will restrict the vessel's maneuverability. Mariners operating near the survey vessel should use caution, maintain a safe distance, and proceed at reduced speed. The vessel will continuously monitor VHF Channels 13 and 16 and will check in daily with New York/New Jersey Vessel Traffic Service. The vessel will also maintain a listening watch on VHF Channel 12 or 14 as required by location. The designated shoreside point of contact is Joe Wozniak, HSE & Marine Compliance Manager, S. T. Hudson Engineers, Inc., at 609-412-1242 or jwozniak@sthe.com.	

Annisquam River

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector Boston, Submerged Land Act (SLA) - Annisquam River/ATON/ATON Changes	ATON Changes	ATON/ATON Changes From: 2026-09-15 To: 2026-11-14 Location: 42-38-08.160N/070-41-08.916W Aid Name: Annisquam River Channel Buoy 24 LLNR: 9690 Action: RELOCATE TO: 42-38-08.148N / 070-41-08.899 W.	Lat: 42° 38' 08" Lon: -070° 41' 09"
Portsmouth To Cape Ann - Annisquam River/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	Severe shoaling has been reported in the Annisquam River. Annisquam River channel buoy 24 (LLNR 9690) has been relocated due to recent shoaling in the area to mark best water. Mariners should proceed with caution while transiting the area	

Apponaganset Bay

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Buzzards Bay Main Channel - Apponaganset Bay/General/Marine Events/Regatta (Race)	Marine Events	RI – NARRAGANSETT BAY – SUNSET SERIES RACING – RACE/REGATTA Mariners are advised that the Sunset Series Racing is scheduled to be held in the vicinity of Apponagansett Harbor, South Dartmouth, MA. The event will take place on May 20, 2026, from 5:00 p.m. to 9:00 p.m. Expect up to 35 sailing vessels, 8-62 ft in length. Mariners are advised to transit the area with extreme caution. Mariners may contact the person in charge by phone at (508) 843-4426.	

Arthur Kill

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Raritan River Cutoff Channel - Arthur Kill/General/Bridges/Maintenance	Bridges	General/Bridges/Maintenance On February 16, 2026, between 7:00 am and 3:30 pm on weekdays, bridge maintenance will be performed on the New Jersey Turnpike (99.70ANI) IVO Interchange 13) over Elizabeth River, mile .61 to the mouth of Elizabeth Reach, in Elizabeth, Union County, New Jersey. This work will be completed in 5 non-consecutive days. A 15 ft skiff and a 60 ft X 160 ft platform will be in the waterway intermittently. Mariners requiring full horizontal clearance can contact Matt Becker at (201) 304-3045. The project is to be completed by December 31, 2026. Mariners are advised to exercise caution when transiting the area. From: 2026-02-12 To: 2027-01-01 Location: 40-38-44.052N/074-12-14.508W Bridge Name: 99 67 Interstate95 Expressway Southbound Bridge	Lat: 40° 38' 44" Lon: -074° 12' 15"
Raritan River Cutoff Channel - Arthur Kill/General/Bridges/Inspection	Bridges	General/Bridges/Inspection From: 2026-06-14 To: 2026-11-01 Location: 40-31-29.310N/074-14-49.110W Bridge Name: Outerbridge Crossing From June 15, 2026 – October 31, 2026, Monday-Friday, between 7:00 a.m. and 5:00 p.m., a biennial bridge inspection using a combination of a bucket truck, manlift, and tethered climbing will be conducted on the Outerbridge Crossing over Arthur Kill at mile 2.0. Vertical clearance will not be reduced by more than 5 feet below low steel due to this inspection. Additionally, there will be a dive inspection of the bridge piers periodically during this time period. Mariners requiring full vertical or horizontal clearance can contact VTS New York or contact the contractor via marine radio VHF-FM Ch. 13/16 or by calling Rudy Baliga (862) 345-4670. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 31' 29" Lon: -074° 14' 49"
Raritan River Cutoff Channel - Arthur Kill/General/Bridges/Inspection	Bridges	General/Bridges/Inspection From: 2026-07-01 To: 2026-10-01 Location: 40-38-09.060N/074-11-49.030W Bridge Name: Goethals Bridge From July 1-September 30, 2026, between 7:00 a.m. and 4:00 p.m., a bridge traveler will be operated under the Goethals Bridge over Arthur Kill Channel at mile 11.5 to perform bridge inspection. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or call 848-231-3359. The traveler platform will be moved out of the navigable channel after work hours or when not in use. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 38' 09" Lon: -074° 11' 49"

Raritan River Cutoff Channel - Arthur Kill/General/Bridges/Rehabilitation	Bridges	From July 27, 2026 to October 31, 2028, contractors will be conducting steel repairs and painting of the Outerbridge Crossing over Arthur Kill at mile 2.0. This work will be conducted from up to eight 20-foot-wide work platforms suspended no more than 2 feet 10 inches from the low structural steel of the bridge. Work platforms will be first deployed on August 3, 2026, on the eastern edge of the navigable channel, and will be repositioned across the channel as work is complete at each repair site. Work platforms will be lit with red lights on all four corners. Work shifts are 7:00 a.m. to 3:30 p.m. and 9:30 p.m. to 5:00 a.m. daily. Mariners can obtain information about specific work platform locations can be provided by contacting USCG VTS New York at (718) 354-4088, contacting the on-site contractor at (631) 704-4376, or by contacting the USCG Northeast District Bridge Branch at (571) 607-8154. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 31' 29" Lon: -074° 14' 49"
Raritan River Cutoff Channel - Arthur Kill/General/Bridges/Inspection	Bridges	General/Bridges/Inspection From: 2026-10-01 To: 2027-01-01 Location: 40-38-09.060N/074-11-49.030W Bridge Name: Goethals Bridge From October 1-December 31, 2026, between 7:00 a.m. and 4:00 p.m., a bridge traveler will be operated under the Goethals Bridge over Arthur Kill Channel at mile 11.5 to perform bridge inspection. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or call 848-231-3359. The traveler platform will be moved out of the navigable channel after work hours or when not in use. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 38' 09" Lon: -074° 11' 49"
Raritan River Cutoff Channel - Arthur Kill/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2024-09-13 To: 2039-11-29 Location: 40.59778° N / 74.19924° W 40.59752° N / 74.19868° W 40.59178° N / 74.20379° W 40.59178° N / 74.20452° W 40.59778° N / 74.19924° W NJ - ARTHUR KILL – TREMLEY POINT REACH Shoaling has been identified in the Arthur Kill, between Tremley Point Reach and Rahway River on the New Jersey side in the area between buoys Channel Lighted Buoy 34 and Channel Lighted Buoy 32. Mariners are urged to maintain a sharp lookout and transit the area with extreme caution.	

Barnstable Harbor

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Georges Bank And Nantucket Shoals - Barnstable Harbor/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	MA – BARNSTABLE HARBOR – SHOALING Mariners be advised that shoaling exists in the Barnstable Harbor Entrance channel. Shoaling extends approximately 200 feet into the channel north of Barnstable Harbor Entrance Lighted Buoy 6, in the vicinity of position 41-.43.5 N, 070-16.3W. Water depth is estimated to be 2 feet at low tide in this area. All mariners are requested to use caution while transiting the area.	

Barrington River

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Barrington River Buoy 8	18780	MISSING	PA

Bass Harbor

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Bass Harbor Head Gong Buoy WB	2345	OFF STATION	FD

Bass River

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Beverly Channel - Bass River/General/Bridges/Temp Deviation	Bridges	Construction of a temporary Hall-Whitaker Bridge is ongoing and anticipated to be complete no later than May 29, 2030. Until construction is complete, the Hall-Whitaker Bridge over the Bass River in Beverly, MA at mile 0.6 will remain in the closed position. Smaller vessels with adequate clearance beneath the existing moveable bridge in the closed position will be able to pass. Mariners are advised to exercise caution when transiting the area. Any concerned traffic can contact the project manager (MAS Building & Bridge) at (508) 918-3133, or Mass DOT Highway Division at (857) 443-6594.	Lat: 42° 32' 59" Lon: -070° 53' 16"
Beverly Channel - Bass River/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	MA-SALEM AND LYNN HARBORS (CHART 13275)-BASS RIVER Severe shoaling has been reported between Bass River Channel Buoy 2 (LLNR 10325)-Bass River Channel Buoy 9 (LLNR 10355) and there is a severe decrease in the channel's width. Mariners should proceed with caution while transiting the area.	

Bay Ridge Channel

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Main Channel - Bay Ridge Channel/General/Other	Miscellaneous	General/Other NY-GOWANUS CANAL From: 2024-09-30 To: 2028-12-31 Location: 40.67208° N / 73.99839° W 40.67178° N / 73.99816° W The Gowanus Canal is closed to all recreational boating between 9th Street and Butler Street, including use of the 2nd Street public boat launch, at the direction of the U.S. Environmental Protection Agency (USEPA), the lead federal agency for the Gowanus Canal Superfund Site, due to the ongoing construction of the dredging and capping remedy of the canal until further notice unless specific advance written authorization is granted by USEPA. Contact: (212) 637-3639. For further information: https://gowanussuperfund.com .	

Beach Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Beach Channel Lighted Buoy 5	34405	MISSING	FD

Bellport Bay.

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Bellport Shellfish Regulatory Buoy A	null	MISSING	PA
Bellport Shellfish Regulatory Buoy B	null	MISSING	PA
Bellport Shellfish Regulatory Buoy C	null	MISSING	PA
Bellport Shellfish Regulatory Buoy D	null	MISSING	PA
Bellport Shellfish Regulatory Buoy E	null	MISSING	PA

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Great South Bay - Bellport Bay/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2026-03-06 To: 2027-03-06 Location: 40-44-09.096N/072-52-27.444W Shoaling has been reported of 3.0 feet at mean low low water in the vicinity of position 40-44-9.115N, 072-52-27.447W. Mariners are advised to transit the area with extreme caution.	Lat: 40° 44' 09" Lon: -072° 52' 27"

Beverly Channel

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Salem Channel - Beverly Channel/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-09-28 To: 2026-11-16 Location: 42-32-17.952N/070-52-53.796W Marine construction operations will be conducted in Salem Harbor, MA, in the vicinity of Lobster Rock Daybeacon from approximately September 28, 2026, through November 15, 2026. AGM Marine Contractors, Inc. will remove the Lobster Rock Daybeacon for the U.S. Coast Guard using the dredge PRONCKAI, deck barge THING, and tug SITKA. Work is expected to occur during a single daylight shift, approximately 6:00 a.m. to 8:00 p.m., seven days per week, weather permitting. Mariners are advised to transit the area with caution, reduce wake as necessary, and remain alert for construction vessels and equipment operating on scene. The dredge and tug will monitor VHF-FM Channels 13 and 16 and will use Channel 68 as the working channel.	Lat: 42° 32' 18" Lon: -070° 52' 54"
Salem Channel - Beverly Channel/General/Marine Events/Other	Marine Events	MA – BEVERLY HARBOR – INDEPENDENCE PARK – BEVERLY 400th BATTLE REENACTMENT The Beverly 400 is hosting the Beverly 400 – Battle of the Hannah and Nautilus Reenactment on October 10th, 2026, from 9:00 AM to 11:00 AM in Beverly Harbor off Independence Park. The event will consist of two sailing vessels approximately 38.5' and 50' in length. The person responsible for on scene safety can be reached at 347-424-3173. For more information, please contact Scott White at 347-424-3173. Chart 13276	

Black Rock Harbor

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Black Rock Harbor Channel Buoy 11	24710	SINKING	FD

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Ash Creek Lighted Buoy 5	24755	OFF STA	PA

Block Island Sound And Approaches

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Block Island Sound And Approaches/General/Miscellaneous	Miscellaneous	The United States Coast Guard will be conducting Search and Rescue Exercises in the waters of Block Island Sound approximately 4-10 nautical Miles North-Northeast of Montauk, NY. The exercise will take place daily from September 8th until September 30th, 2026, between the hours of 7:00am and 4:00pm. It will involve vessel assets. Multiple orange/rectangular 6-person life rafts, multiple Oscar rescue mannikins donning lifejackets, and several vessels will be anchored within the test area. Mariners are advised to keep a sharp lookout and stay clear of the test area and deployed objects. Mariners may contact the on-scene vessels via VHF channels 083 or 21A to coordinate transit. POC for this exercise: Mr. James Spilsbury, james.d.spilsbury@uscg.mil. Sector Command Center 866-819-9128	

Block Island Sound And Gardiners Bay.

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Approaches To New York Nantucket Shoals To Five Fathom Bank - Block Island Sound And Gardiners Bay/General/Hazards To Navigation/Hazards	Hazards To Navigation	General/Hazards To Navigation/Hazards From: 2024-10-01 To: 2039-12-31 Location: 40.97581° N / 71.1889° W	Lat: 40° 58' 33" Lon: -071° 11' 20"

Booth Bay

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
McFarland Island Daybeacon	5545	STRUCT DMGD	PA

Boston North Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Boston North Channel VAIS NC	10680	AIS INOP	FD
Boston North Channel Lighted Buoy 5	10700	LT EXT	FD

Bridgeport Harbor

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Long Island Sound Eastern Part - Bridgeport Harbor/General/Bridges/Closure (Scheduled Or Emergency)	Bridges	General/Bridges/Closure (Scheduled Or Emergency) From: 2026-07-30 To: 2026-09-29 Location: 41-10-45.370N/073-11-08.860W Bridge Name: Stratford Ave Bridge CONNECTICUT – PEQUONNOCK RIVER – Temporary Deviation – The Coast Guard has issued a temporary deviation from the regulation governing the operation of the Stratford Avenue Bridge across Pequonnock River at mile 0.1. Under this temporary deviation the Stratford Ave (Route 130) Bridge may remain closed to mariners beginning August 10, 2026 through October 5, 2026. Questions may be directed to Brian Brinsmade at (203) 389-3173. Mariners are advised to exercise caution when transiting the area.	Lat: 41° 10' 45" Lon: -073° 11' 09"

Bristol Harbor

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Bristol Harbor East Channel Buoy 9	18194.2	OFF STA/HAZ NAV	PA
Bristol Harbor West Channel Buoy 3	18196.2	OFF STA	PA

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Providence River Approach - Bristol Harbor/General/Miscellaneous	Miscellaneous	General/Miscellaneous From: 2025-11-14 To: 2026-12-31 Location: 41-39-45.216N/071-16-29.964W Jaia Robotics will be conducting autonomous underwater vehicle testing, in Narragansett Bay, Monday through Friday, between 8:00am to 7:00pm. The autonomous, underwater, vehicles are around 36 inches in length, and the vehicles come in red/yellow configurations.	Lat: 41° 39' 45" Lon: -071° 16' 30"

Burlington Bay

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Burlington Breakwater Light	39625	LT EXT	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Main Passage - Burlington Bay/General/Marine Events/Regatta (Race)	Marine Events	VT – LAKE CHAMPLAIN – BURLINGTON – Lake Champlain Yacht Club Weekend Racing Mariners are advised that the LCYC Weekend Racing will take place in Shelburne Bay to Wilsboro Point near Burlington, VT. The event will be held every weekend from May 23, May 30, June 13, June 20, July 25, August 1, August 22, September 24, 2026 at 10:00 a.m. to 3:00 p.m., approximately 25 vessels will be participating. For event information: Kevin Hawko, (802) 373-8576.	

Buzzards Bay Main Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Cleveland East Ledge Light	16080	SS IMCH	FD

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
West Island Channel Lighted Buoy 1	17046	OFF STATION	PA
EOM Lighted Research Buoy A	16043	MISSING	PA

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION

Sector Southeastern New England, Submerged Lands Act (SLA) - Buzzards Bay Main Channel/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2024-09-12 To: 2039-08-23 MA – CUTTYHUNK HARBOR – ENTRY CHANNEL Mariners are advised that the navigable width of the entry channel into Cuttyhunk Harbor has decreased to approximately 15 feet wide. This may cause navigability issues and restrict movement for two-way traffic. Mariners are urged to maintain a proper lookout and use extreme caution while transiting the area. You may contact the local harbormaster by phone at (508) 990-7578.	
Sector Southeastern New England, Submerged Lands Act (SLA) - Buzzards Bay Main Channel/General/Marine Events/Regatta (Race)	Marine Events	RI – BUZZARDS BAY, VINEYARD SOUND – HORATIO BREWSTER PERSUIT RACE – RACE/REGATTA Mariners are advised that the Horatio Brewster Pursuit Race is scheduled to be held from Padanaram Harbor, MA to Menemsha, MA. The event will take place on Saturday June 20, 2026, from 9:00 a.m. to 4:00 p.m. Expect up to 10 sailing vessels, 20-40 ft in length. Mariners are advised to transit the area with extreme caution. Mariners may contact the person in charge by phone at (508) 843-4426.	

Canapitsit Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Canapitsit Channel Buoy 5	15945	SINKING	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Main Channel - Canapitsit Channel/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	Mariners are advised of shoaling in the Cuttyhunk Inner Harbor Entrance Channel. The shoaling is reported to extend across the entirety of the entrance channel with an approximate depth at mean low water of 5 feet. Mariners are urged to exercise extreme caution while transiting this area.	

Cape Cod Canal Eastern Entrance

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Cape Cod Canal Eastern Entrance Range Front Light	13080	LT EXT	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Hog Island Channel - Cape Cod Canal Eastern Entrance/General/Bridges/Maintenance	Bridges	Atlas Painting and Sheeting Corp. will be conducting bridge sandblasting and painting operations on the Buzzards Bay Railroad Bridge over the Cape Cod Canal beginning 9 March 2026 through 31 December 2026. Scaffolding will reduce the vertical clearance from 135 feet to 130 feet MHW. Questions concerning the project should be directed to the Duty Marine Traffic Controller, US Army Corps of Engineers, Cape Cod Canal Field Office at 978-318-8500 or VHF Channel 14. Mariners should exercise caution while transiting the area.	Lat: 41° 44' 31" Lon: -070° 36' 49"
Hog Island Channel - Cape Cod Canal Eastern Entrance/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-03-09 To: 2027-02-17 Location: 41-44-30.948N/070-36-48.816W Atlas Painting and Sheeting Corp. will be conducting bridge sandblasting and painting operations on the Buzzards Bay Railroad Bridge over the Cape Cod Canal beginning 9 March 2026 through 31 December 2026. Scaffolding will reduce the vertical clearance from 135 feet to 130 feet MHW. Questions concerning the project should be directed to the Duty Marine Traffic Controller, US Army Corps of Engineers, Cape Cod Canal Field Office at 978-318-8500 or VHF Channel 14. Mariners should exercise caution while transiting the area.	Lat: 41° 44' 31" Lon: -070° 36' 49"

Castine Harbor

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
East Penobscot Bay - Castine Harbor/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2024-07-08 To: 2027-03-31 Location: 44.38878° N / 68.7951° W 44.38861° N / 68.79472° W 44.38587° N / 68.79678° W 44.38605° N / 68.79699° W 44.38878° N / 68.7951° W ME-PENOBSCOT BAY-CASTINE HARBOR Redd & Reed will be conducting marine construction and pier replacement and expansion operations at the Maine Maritime Academy, in Castine, in position 44-23-10.8N, 068-47-47.9W, from July 8, 2024, to the winter of 2027. Work will be conducted between 7:00am to 7:00pm, by deck barges, tugboats, push boats, and work skiffs, who will monitoring VHF-FM CH 11 for any concerned traffic. Mariners are urged to use extreme caution and transit the area at their slowest safe speed to create minimum wake after passing arrangements have been made.	

Chandler Bay.

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Middle Back Rock Daybeacon	1210	DAYMK MISSING	FD

Chelsea River

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Chelsea River Light 1	10965	LT EXT	FD
Chelsea River Light 5	10971	LT EXT	FD

Clinton Harbor

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
North Channel Saybrook To New Haven - Clinton Harbor/ATON/Advanced Notice of Change	Advanced Notice of Change	ATON/Advanced Notice of Change From: 2026-09-02 To: 2027-03-01 Location: 41-15-39.204N/072-31-35.868W Aid Name: Clinton Harbor Channel Buoy 6 LLNR: 23470 Action: CHANGE Action Type Change Light System Primary The U.S. Coast Guard will be making the following change to Aids to Navigation: CHANGE the following aids from unlighted aids to lighted aids as indicated; Add to the remarks section of Light List Vol 1 Aid removed when endangered by ice. Light removed from Nov 15 to May 1. Clinton Harbor Channel Buoy 6 (LLNR 23470) to Clinton Harbor Channel Lighted Buoy 6 (LLNR 23470) FI R 4s Clinton Harbor Channel Buoy 9 (LLNR 23485) to Clinton Harbor Channel Lighted Buoy 9 (LLNR 23485) FI G 2.5s Clinton Harbor Channel Buoy 11 (LLNR 23490) to Clinton Harbor Channel Lighted Buoy 11 (LLNR 23490) Q G Clinton Harbor Channel Buoy 11A (LLNR 23495) Clinton Harbor Channel Lighted Buoy 11A (LLNR 23495) FI G 2.5s Previously advertised as a proposal for Project 01-23-058 in LNM 01/26. E-mail can be sent to: D01-SMB-DPWPPublicComments@uscg.mil.	Lat: 41° 15' 39" Lon: -072° 31' 36"
North Channel Saybrook To New Haven - Clinton Harbor/ATON/Advanced Notice of Change	Advanced Notice of Change	ATON/Advanced Notice of Change From: 2026-09-02 To: 2027-03-01 Location: 41-15-47.304N/072-31-34.680W Aid Name: Clinton Harbor Channel Buoy 9 LLNR: 23485 Action: CHANGE Action Type Change Light System Primary The U.S. Coast Guard will be making the following change to Aids to Navigation: CHANGE the following aids from unlighted aids to lighted aids as indicated; Add to the remarks section of Light List Vol 1 Aid removed when endangered by ice. Light removed from Nov 15 to May 1. Clinton Harbor Channel Buoy 6 (LLNR 23470) to Clinton Harbor Channel Lighted Buoy 6 (LLNR 23470) FI R 4s Clinton Harbor Channel Buoy 9 (LLNR 23485) to Clinton Harbor Channel Lighted Buoy 9 (LLNR 23485) FI G 2.5s Clinton Harbor Channel Buoy 11 (LLNR 23490) to Clinton Harbor Channel Lighted Buoy 11 (LLNR 23490) Q G Clinton Harbor Channel Buoy 11A (LLNR 23495) Clinton Harbor Channel Lighted Buoy 11A (LLNR 23495) FI G 2.5s Previously advertised as a proposal for Project 01-23-058 in LNM 01/26. E-mail can be sent to: D01-SMB-DPWPPublicComments@uscg.mil.	Lat: 41° 15' 47" Lon: -072° 31' 35"
North Channel Saybrook To New Haven - Clinton Harbor/ATON/Advanced Notice of Change	Advanced Notice of Change	ATON/Advanced Notice of Change From: 2026-09-02 To: 2027-03-01 Location: 41-15-56.340N/072-31-23.808W Aid Name: Clinton Harbor Channel Buoy 11 LLNR: 23490 Action: CHANGE Action Type Change Light System Primary The U.S. Coast Guard will be making the following change to Aids to Navigation: CHANGE the following aids from unlighted aids to lighted aids as indicated; Add to the remarks section of Light List Vol 1 Aid removed when endangered by ice. Light removed from Nov 15 to May 1. Clinton Harbor Channel Buoy 6 (LLNR 23470) to Clinton Harbor Channel Lighted Buoy 6 (LLNR 23470) FI R 4s Clinton Harbor Channel Buoy 9 (LLNR 23485) to Clinton Harbor Channel Lighted Buoy 9 (LLNR 23485) FI G 2.5s Clinton Harbor Channel Buoy 11 (LLNR 23490) to Clinton Harbor Channel Lighted Buoy 11 (LLNR 23490) Q G Clinton Harbor Channel Buoy 11A (LLNR 23495) Clinton Harbor Channel Lighted Buoy 11A (LLNR 23495) FI G 2.5s Previously advertised as a proposal for Project 01-23-058 in LNM 01/26. E-mail can be sent to: D01-SMB-DPWPPublicComments@uscg.mil.	Lat: 41° 15' 56" Lon: -072° 31' 24"
North Channel Saybrook To New Haven - Clinton Harbor/ATON/Advanced Notice of Change	Advanced Notice of Change	ATON/Advanced Notice of Change From: 2026-09-02 To: 2027-03-01 Location: 41-16-01.524N/072-31-23.916W Aid Name: Clinton Harbor Channel Buoy 11A LLNR: 23495 Action: CHANGE Action Type Change Light System Primary The U.S. Coast Guard will be making the following change to Aids to Navigation: CHANGE the following aids from unlighted aids to lighted aids as indicated; Add to the remarks section of Light List Vol 1 Aid removed when endangered by ice. Light removed from Nov 15 to May 1. Clinton Harbor Channel Buoy 6 (LLNR 23470) to Clinton Harbor Channel Lighted Buoy 6 (LLNR 23470) FI R 4s Clinton Harbor Channel Buoy 9 (LLNR 23485) to Clinton Harbor Channel Lighted Buoy 9 (LLNR 23485) FI G 2.5s Clinton Harbor Channel Buoy 11 (LLNR 23490) to Clinton Harbor Channel Lighted Buoy 11 (LLNR 23490) Q G Clinton Harbor Channel Buoy 11A (LLNR 23495) Clinton Harbor Channel Lighted Buoy 11A (LLNR 23495) FI G 2.5s Previously advertised as a proposal for Project 01-23-058 in LNM 01/26. E-mail can be sent to: D01-SMB-DPWPPublicComments@uscg.mil.	Lat: 41° 16' 02" Lon: -072° 31' 24"
North Channel Saybrook To New Haven - Clinton Harbor/ATON/ATON Changes	ATON Changes	ATON/ATON Changes From: 2026-09-17 To: 2026-11-16 Location: 41-15-39.204N/072-31-35.868W Aid Name: Clinton Harbor Channel Lighted Buoy 6 LLNR: 23470 Action: RENAME: Clinton Harbor Channel Buoy 6, to Clinton Harbor Channel Lighted Buoy 6, FI R 4s. 3NM Nominal Range.	Lat: 41° 15' 39" Lon: -072° 31' 36"
North Channel Saybrook To New Haven - Clinton Harbor/ATON/ATON Changes	ATON Changes	ATON/ATON Changes From: 2026-09-17 To: 2026-11-16 Location: 41-15-47.304N/072-31-34.680W Aid Name: Clinton Harbor Channel Lighted Buoy 9 LLNR: 23485 Action: RENAME Clinton Harbor Channel Buoy 9, to Clinton Harbor Channel Lighted Buoy 9, FI G 2.5s, 3NM Nominal Range.	Lat: 41° 15' 47" Lon: -072° 31' 35"
North Channel Saybrook To New Haven - Clinton Harbor/ATON/ATON Changes	ATON Changes	ATON/ATON Changes From: 2026-09-17 To: 2026-11-16 Location: 41-15-56.340N/072-31-23.808W Aid Name: Clinton Harbor Channel Lighted Buoy 11 LLNR: 23490 Action: RENAME Clinton Harbor Channel Buoy 11, to Clinton Harbor Channel Lighted Buoy 11, QG, 3NM Nominal Range.	Lat: 41° 15' 56" Lon: -072° 31' 24"
North Channel Saybrook To New Haven - Clinton Harbor/ATON/ATON Changes	ATON Changes	ATON/ATON Changes From: 2026-09-17 To: 2026-11-16 Location: 41-16-01.524N/072-31-23.916W Aid Name: Clinton Harbor Channel Lighted Buoy 11A LLNR: 23495 Action: RENAME Clinton Harbor Channel Buoy 11A, to Clinton Harbor Channel Lighted Buoy 11A, FI G 2.5s, 3NM Nominal Range.	Lat: 41° 16' 02" Lon: -072° 31' 24"

Cobscook Bay

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Cobscook Bay Buoy 5	1005	SINKING	FD

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
ORPC Cobscook Bay Lighted Buoy A	1013	MISSING	PA

Cohasset Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE

Cohasset Harbor

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Cohasset Gangway Lighted Bell Buoy 1G	12220	OFF STATION	FD

Cohasset Western Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Cohasset Western Channel Daybeacon 5	12170	MISSING	FD

Coney Island Channel

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Ambrose Channel - Coney Island Channel/General/Marine Events/Fireworks	Marine Events	General/Marine Events/Fireworks From: 2026-06-17 To: 2026-09-26 Location: BROOKLYN, NY – LOWER BAY – CONEY ISLAND BEACH –Fireworks Display Mariners are advised that a reoccurring fireworks display is scheduled to be held on Coney Island Beach, Friday nights from June 19, 2026 through September 2026, from 9:15 p.m. until 10:45 p.m. The fireworks launch site will be near the waters of the Lower Bay of New York Harbor in approximate position 40° 34’ 20” N, 73° 58’ 43” W (NAD 83). Mariners are advised to keep a minimum safe distance of 450 feet from the shoreline to avoid pyrotechnic fallout.	

Connecticut River

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Connecticut River Light 25	22610	DAYMK DMGD	FD
Connecticut River Light 42	22915	DAYMK MISSING	FD
Connecticut River Light 42	22915	LT EXT	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
North Channel Saybrook To New Haven - Connecticut River/General/Bridges/Construction	Bridges	General/Bridges/Construction From: 2025-05-08 To: 2029-12-31 Location: 41.31087778° N / 72.34920833° W Bridge Name: Amtrak Railroad Bridge CONNECTICUT – CONNECTICUT RIVER – From July 7, 2025, through December 30, 2029, AMTRAK will have moored barges in place during the construction and demolition of the Amtrak Connecticut River Bridge. Due to the placement of a temporary fendering system, the horizontal clearance of the bridge in the navigation channel will be reduced to 115 feet. Similarly, the placement of temporary signal cables overhead of the navigation channel will reduce vertical clearance to 100 feet above MHW when the bridge is in the open position. From October 1, 2025 to November 15, 2025, contractors will be performing dive operations to remove submarine cables from 0630-1830 Monday through Friday. From October 30, 2025 through October 31, 2025, dive operations are scheduled to take place in the navigational channel. Barges will be placed along the bridge fenders blocking the channel. Mariners are encouraged to avoid the channel while dive operations are taking place. However, mariners requiring passage must contact Michael King at (617) 653-7987 with a 2 hour advance notice to arrange transit through the work area. Mariners are advised to exercise caution and reduce wake when transiting the area. Mariners with questions or concerns can contact the contractor via marine radio VHF-FM Ch 13/16 or call Patrick Finley at (860) 806-2365 or Bob Nardi at (203) 496-7353.	Lat: 41° 18' 39" Lon: -072° 20' 57"
North Channel Saybrook To New Haven - Connecticut River/General/Bridges/Construction	Bridges	Connecticut River/General/Bridges From: 2025-12-22 To: 2029-12-31 Location: 41.310878, -72.349208 Bridge Name: Amtrak Railroad Bridge CONNECTICUT – CONNECTICUT RIVER – Moored Barge – AMTRAK will have a moored barge placed during the construction and demolition of the Amtrak Connecticut River Bridge. Beginning August 1, 2025 through December 30, 2029. The crane barge 120' x 300' will be moored outside of the navigational channel used for stationary material barges to support the installation of new bridge components and removal of the existing structure towards the end of the project.. Beginning December 22, 2025, barges and platform will be placed in the navigational channel for the new bridge construction. During this time the navigational clearance will be reduced to 100' vertical clearance and 110' horizontal clearance. Mariners are advised to exercise caution and reduce wake when transiting the area. Mariners with questions or concerns can contact the contractor via marine radio VHF-FM Ch 13/16 or call Patrick Finley at (860) 806-2365 or Bob Nardi at (203) 496-7353.	Lat: 41° 18' 39" Lon: -072° 20' 57"
North Channel Saybrook To New Haven - Connecticut River/General/Bridges/Rehabilitation	Bridges	General/Bridges/Rehabilitation From: 2026-05-12 To: 2028-11-30 Location: 41-42-52.848N/072-38-26.268W Bridge Name: Putnam 3 Route Bridge CONNECTICUT – CONNECTICUT RIVER – Connecticut Department of Transportation will be rehabilitating the Putnam Bridge across Connecticut River, mile 47.4, between Glastonbury and Wethersfield, Connecticut. To perform this work the contractor will be installing a work platform beginning May 31, 2026. The platform will reduce the vertical clearance to 75'. This work platform will be installed until November 2028. The contractors work hours are as follows: Day Shift: • Monday – Friday 7:00AM – 5:30PM and Saturday 7:00AM – 3:30PM Night Shift: • Sunday – Friday 7:00PM – 6:00AM Mariners are advised to exercise caution and reduce wake when transiting the area. Mariners with questions or concerns can contact the contractor via marine radio VHF-FM Ch 13/16 or call Ryan Hawkins 860-515-9205.	Lat: 41° 42' 53" Lon: -072° 38' 26"
North Channel Saybrook To New Haven - Connecticut River/General/Bridges/Rehabilitation	Bridges	General/Bridges/Rehabilitation From: 2026-06-15 To: 2027-11-13 Location: 41-48-47.990N/072-38-42.230W Bridge Name: Bissell Bridge CONNECTICUT- CONNECTICUT RIVER – Bridge Rehabilitation – Beginning June 18, 2026 through November 12, 2027, Connecticut DOT is performing rehabilitation on the superstructure and substructure of the Bissell Bridge across Connecticut River across Connecticut River at mp 55.8, in Hartford, Connecticut. To perform this, work the contractor will be utilizing 2 barges in the waterway, 8'x40'. The barges will be moved to the west side of pier 2 or west side of pier 10 during non-working hours. Contractors will be working in two shifts, Day Shift 07:00 AM-03:30 PM, Night shift 06:00 PM-06:00 AM. For more information contact Roy Oemceke at (207) 952-4201. Mariners are advised to use caution and transit at slow speed to minimize wake.	Lat: 41° 48' 48" Lon: -072° 38' 42"

Connecticut River/General/Bridges	Bridges	Connecticut River/General/Bridges From: 2026-09-01 To: 2026-11-01 Location: 41.769475, -72.665333 Bridge Name: Bulkeley Memorial Bridge From September 8, 2026 to October 31, 2026 between 9:00 a.m. to 4:00 p.m., a contractor will be performing diving inspections at the Bulkeley Bridge across Connecticut River at mile 52, in Hartford, CT. The contractor will be utilizing diving equipment and a 21-foot parker boat for this inspection. Mariners requiring full horizontal or vertical clearance can contact the contractor via marine radio VHF-FM Ch 13/16 or call Keith Griswold 860-682-0666 or Bill Kristoff 860-471-0606. Mariners are advised to exercise caution and reduce wake when transiting the area.	Lat: 41° 46' 10" Lon: -072° 39' 55"
Connecticut River/General/Bridges/Inspection	Bridges	Connecticut River/General/Bridges/Inspection From: 2026-09-17 To: 2027-03-16 Location: 41.318913, -72.347429 Bridge Name: Raymond E Baldwin Bridge From October 1, 2026 to October 31, 2026 between 8:30 a.m. and 4 p.m., a 75' under bridge inspection unit (UBIU) will be operating at the I-95 across Connecticut River at mile 4. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch 13/16 or call Yaroslav Skoplyak (860) 780-8606. Mariners are advised to exercise caution and reduce wake when transiting the area.	Lat: 41° 19' 08" Lon: -072° 20' 51"

Damariscotta River

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Hypocrite Ledge Daybeacon H	5260	DAYMK DMGD	FD
Damariscotta River Buoy 12	5350	MISSING	FD
Glidden Ledge Daybeacon 16	5370	STRUCT DMGD	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector Northern New England, Submerged Lands Act (SLA) - Damariscotta River/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-06-02 To: 2027-06-02 Location: 43-57-20.952N/069-34-32.268W \Fuller Marine Services, Inc. submitted a Local Notice to Mariners (LNM) Information Form to the U.S. Coast Guard First District for the full removal and replacement of Merry Island Daybeacon 15 (LLNR 5365) in the Damariscotta River, Maine. The project, The project will replace the aid entirely, is scheduled to begin on June 15, 2026, and will continue until completion, with daily operations from 7:00 AM to 6:00 PM using the vessels Enzo Charles and Mary Louisa II. Vessels will monitor VHF-FM Channels 16 and 13 for navigational safety and passing arrangements, with secondary contact available on Channel 09 or USCG working channel 22A. The crew will maintain a clear fairway for all traffic and will reposition within 30 minutes if additional channel breadth is required, subject to weather and safety conditions.	Lat: 43° 57' 21" Lon: -069° 34' 32"

Danvers River

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Beverly Channel - Danvers River/General/Bridges/Repairs, Painting, Or Fender Replacement	Bridges	General/Bridges/Repairs, Painting, Or Fender Replacement From: 2026-06-20 To: 2026-10-03 Location: 42-32-35.304N/070-53-53.880W Bridge Name: Kernwood Ave Bridge MASSACHUSETTS- DANVERS RIVER- SALEM AND BEVERLY- KERNWOOD BRIDGE - Bridge Fender System Repairs and Full channel closures MassDOT and SPS New England Inc will be conducting emergency repairs to the fender system at the Kernwood Bridge located at mile 1 of the Danvers River between Salem and Beverly Massachusetts. Work will commence Sunday June 21st, 2026, and continue through Friday October 2nd, 2026. Sunday work hours will be 11:00 p.m. to 5:00 a.m. Monday through Thursday work hours will be 9:00 p.m. to 5:00 a.m. During this maintenance project a full channel closure will be in effect during the timeframes listed above. Vessels will be unable to transit through the bridge during the closure. On scene equipment will consist of a 30x60 tug and barge with associated dive equipment and one safety vessel. Mariners should contact the on-scene Harbormaster boat on VHF Channel 13/16 for guidance. Questions may be addressed to MassDOT Mr. Thomas Gallagher at (978) 886-3724 or SPS New England project manager Ms. Laura Hood at (978) 606-7673. Mariners are advised to plan accordingly and exercise caution. when transiting the area. Chart 13275	Lat: 42° 32' 35" Lon: -070° 53' 54"

East Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
East Channel Buoy 11	29265	MISSING/TRUB	FD
East Channel Buoy 23	29297	Status Unreported	FD

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Atlantique Entrance Buoy 2	29268	OFF STATION	PA

East Passage

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Coddington Cove Breakwater Light 18	18005	DAYMK MISSING	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION

Eastern Approach - East Passage/General/Marine Events/Regatta (Race)	Marine Events	RI – NARRAGANSETT BAY – M32 WORLD CHAMPIONSHIP – RACE/REGATTA Mariners are advised that the M32 World Championship is scheduled to be held in the vicinity of Halfway Rock, Narragansett Bay, RI. The event will take place from Monday September 28, through October 3, 2026 from 12:00 a.m. to 4:00 p.m. Expect up to 12 sailing vessels, 32 ft in length. Mariners are advised to transit the area with extreme caution. Mariners may contact the person in charge by phone at (413) 364-0067.	
Eastern Approach - East Passage/General/Marine Events/Regatta (Race)	Marine Events	RI – NARRAGANSETT BAY– RESOLUTE CUP – RACE/REGATTA Mariners are advised that the Resolute Cup is scheduled to be held in the vicinity of East Passage, Narragansett Bay, RI. The event will take place from Monday September 28, through October 3, 2026 from 9:00 a.m. to 5:00 p.m. each day. Expect up to 32 vessels, 18-50 ft in length. Mariners are advised to transit the area with extreme caution. Mariners may contact the person in charge by phone at (312) 402-2105.	
Eastern Approach - East Passage/General/Naval Activity/Naval Testing (Surface/Underwater)	Naval Activity	General/Naval Activity/Naval Testing (Surface/Underwater) From: 2026-03-05 To: 2027-03-06 RI-NARRAGANSETT BAY - NAVAL UNDERSEA WARFARE CENTER WILL BE CONDUCTING TESTING USING SURFACE AND SUBSURFACE DEVICES NORTH AND EAST OF GOULD ISLAND IN THE NAVY TEST RANGE RESTRICTED AREA MARKED ON NOAA CHART 13223 NORTH OF THE NEWPORT BRIDGE. OPERATIONS WILL BE CONDUCTED MONDAY THRU FRIDAY 0700-1700. MARINERS ARE REQUESTED TO COOPERATE WITH PARTICIPATING VESSELS FOR THE SAFETY OF ALL. ANY CONCERNED TRAFFIC CAN CONTACT NAVY SUPPORT CRAFT ON VHF CHANNELS 13,16. FOR MORE INFORMATION PLEASE CONTACT 401-832-6140.	

East River Main Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
East River Main Channel Lighted Buoy 13	27280	LT EXT	FD

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
East River Regulatory Light E	27246.4	OFF STA/HAZ NAV	PA
East River Regulatory Light C	27246.2	STRUCT DEST	PA

Temporary Changes

NAME	LLNR	STATUS	AID TYPE
United Nations Security Zone CG Mooring Buoy	27310	ESTABLISHED	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Main Channel - East River Main Channel/General/Bridges/Rehabilitation	Bridges	General/Bridges/Rehabilitation From: 2024-07-01 To: 2027-12-31 Location: 40.77988889° N / 73.92682778° W Bridge Name: Triboro Bridge Structural Rehabilitation –Construction at the RfK Bridge across East River at mile 7.8 will commence on July 1, 2024. Hours of operation are during daylight hours. A temporary platform will be installed under the entire length and width of suspended span. The platform will reduce the vertical clearance by 4 feet plus 2 feet sag allowance (6 feet total). There will hot work/welding during construction. Any questions regarding this project can contact Andre Markarian via marine radio VHF-FM Ch. 13/16 or 510-774-2198. This project is to be completed by December 31, 2027. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 46' 48" Lon: -073° 55' 37"
Main Channel - East River Main Channel/General/Bridges/Rehabilitation	Bridges	General/Bridges/Rehabilitation From: 2024-05-13 To: 2026-12-31 Location: 40.79931111° N / 73.79358889° W Bridge Name: Throgs Neck Bridge Pier Protection Fender System Replacement – Exploratory Indicator Pile Program/Design/construction of fender system to the Bronx and Queens Towers of the Throgs Neck Bridge across East River at mile 15.8 is in progress. Hours of operation are from 7 a.m. to 5:30 p.m. daily. Crane and material barges will be operating along the perimeter of the Bronx and Queens Towers. Any questions regarding this project can contact Steve Mejia via marine radio VHF-FM Ch. 13/16 or 732-522-1238. This project is to be completed by December 31, 2026. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 47' 58" Lon: -073° 47' 37"
Main Channel - East River Main Channel/General/Bridges/Closure (Scheduled Or Emergency)	Bridges	General/Bridges/Closure (Scheduled Or Emergency) From: 2024-11-06 To: 2026-12-25 Location: 40.73905278° N / 73.94273056° W Bridge Name: Borden Ave Bridge NEW YORK – EAST RIVER NEWTOWN CREEK – DUTCH KILLS – Bridge Closure – The Borden Ave Bridge, mile 1.2, is closed due to vandalism. Vessels able to pass under the bridge in the closed position may do so. Mariners with questions may contact Keith Burrows at (212) 839-3741, NYCDOT Director of Bridge & Tunnel Operations. Mariners are advised to plan their transits accordingly.	Lat: 40° 44' 21" Lon: -073° 56' 34"
Main Channel - East River Main Channel/General/Bridges/Rehabilitation	Bridges	From August 1, 2026, through October 9, 2026, between 6:00 a.m. and 2:30 p.m., underwater repairs to the Brooklyn pier and fender of the Brooklyn Bridge across the East River at mile 0.8 shall take place utilizing divers from a platform moored adjacent to the Brooklyn pier. Mariners can contact the contractor via marine radio VHF-FM Ch. 13/16 or call Tom McIntosh from JT Cleary at (201) 417-4115. Mariners are advised to transit at a slow bell and exercise caution through the area.	Lat: 40° 42' 22" Lon: -073° 59' 48"
Main Channel - East River Main Channel/General/Bridges/Inspection	Bridges	From May 1, 2026 – December 31, 2026, Monday-Friday, with occasional Saturdays and Sundays, between 8:00 a.m. and 4:00 p.m., a biennial bridge inspection using a traveler and rigging will be conducted on the Manhattan Bridge, mile 1.1 in the East River, New York City. The safety boat Kylie Anne (CT8893BM) will be on scene during inspection operations. Mariners requiring the traveler to move to provide full vertical clearance can contact VTS New York, or contact the contractor via marine radio VHF-FM Ch. 13/16 or by calling 631-891-9721. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 42' 26" Lon: -073° 59' 26"
Main Channel - East River Main Channel/General/Bridges/Inspection	Bridges	General/Bridges/Inspection From: 2026-06-15 To: 2026-12-01 Location: 40-46-55.480N/073-53-17.830W Bridge Name: Rikers Island Bridge From June 15, 2026, to November 30, 2026, between 8:00 a.m. and 4:00 p.m., Monday-Friday and Saturday/Sunday, a barge and rowboat will be operated under Rikers Island Bridge over East River at mile 10.7 to perform inspections. Mariners requiring full horizontal clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or call 646-460-3880 or 863-326-3750. Safety vessel NY8360GY will be on scene during the inspection. The barge and rowboat will be moved out of the navigable channel after work hours or when not in use. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 46' 55" Lon: -073° 53' 18"
Main Channel - East River Main Channel/General/Bridges/Inspection	Bridges	General/Bridges/Inspection From: 2026-06-15 To: 2027-01-01 Location: 40-48-01.710N/073-55-41.420W Bridge Name: 125th St Bridge From June 15, 2026, to December 31, 2026, between 7:00 a.m. and 4:00 p.m., a barge with manlift will be operated under 125th St. (RFK) Bridge over Harlem River at mile 1.3 to perform inspections. Mariners requiring full horizontal clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or call 347-489-2906. The barge with manlift will be moved out of the navigable channel after work hours or when not in use. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 48' 02" Lon: -073° 55' 41"

Main Channel - East River Main Channel/General/Bridges/Inspection	Bridges	General/Bridges/Inspection From: 2026-07-20 To: 2026-11-21 Location: 40-44-21.206N/073-57-09.241W Bridge Name: Pulaski Bridge NEW YORK-NEWTOWN CREEK- From July 27, 2026 through November 20, 2026 between 9:00 a.m. to 3:00 p.m., contractors will be inspecting the Pulaski Bridge across Newtown Creek at mile 0.6, in Queens, NY. The contractor will be utilizing a 60' Under Bridge Inspection Unit (UBIU) with 60' manlift. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch 13/16 or call Han Chen (917) 306-0152. Mariners are advised to exercise caution and reduce wake when transiting the area.	Lat: 40° 44' 21" Lon: -073° 57' 09"
Main Channel - East River Main Channel/General/Bridges/Inspection	Bridges	General/Bridges/Inspection From: 2026-08-24 To: 2026-10-17 Location: 40-42-49.490N/073-58-19.960W Bridge Name: Williamsburg Bridge From August 24, 2026 to October 16, 2026, between 8:00 am to 4:00 pm Monday through Friday, a bridge traveler will be operated under Williamsburg Bridge across East River at mile 2.3, in Brooklyn, NY to perform a bridge inspection. Safety boat CT8893BM will be on scene during inspection operations. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or by calling (860) 707-7337. The traveler platform will be moved out of the navigable channel after work hours or when not in use. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 42' 49" Lon: -073° 58' 20"
East River Main Channel/General/Bridges	Bridges	East River Main Channel/General/Bridges From: 2026-09-20T00:00:00.000Z To: 2026-09-27T00:00:00.000Z Location: 40.763469, -73.945833 Bridge Name: Roosevelt Island Bridge Roosevelt Island Bridge- East River Security Zone September 9, 2026 through September 20, 2026 The U.S. Coast Guard will enforce a Security Zone on the East River between East 36th Street and the Queensboro/59th Street Bridge near the United Nations Headquarters from September 20, 2026, through September 26, 2026. This action has been requested by the U. S. Secret Service to protect visiting dignitaries during the U. N. General Assembly session. The U. S. Coast Guard will be closing the main navigational channel of the East River (between Manhattan and Roosevelt Island) and will be diverting marine traffic to the Roosevelt Island Channel (channel between Roosevelt Island and Queens). It is therefore required that the New York City Department of Transportation crew the Roosevelt Island Bridge and operate it on signal, daily, from 6 a.m. through 8 p.m. beginning September 20, 2026, through September 26, 2026.	Lat: 40° 45' 48" Lon: -073° 56' 45"
Main Channel - East River Main Channel/General/Bridges/Inspection	Bridges	East River Main Channel/General/Bridges From: 2026-09-15 To: 2026-12-31 Location: 40.733216, -73.940405 Bridge Name: Greenpoint Ave Bridge On September 21, 2026 to December 30, 2026 between 9:00 a.m. and 3:00 p.m. NYCDOT will be utilizing a barge with 60' manlift to inspect the Greenpoint Ave Bridge over Newtown Creek at mile 1.3 for bridge inspections. Mariners requiring full horizontal clearance can contact the contractor via marine radio VHF-FM Ch 13/16 or call Jan Pawluczuk at (646) 872-2967. Mariners are advised to exercise caution and reduce wake when transiting the area.	Lat: 40° 43' 60" Lon: -073° 56' 25"
East River Main Channel/General/Bridges	Bridges	East River Main Channel/General/Bridges From: 2026-09-17 To: 2026-09-26 Location: 40.808333, -73.932222 Bridge Name: Third Ave Bridge From September 24, 2026 to September 25, 2026, between 8 am to 4 pm, a contractor will be performing a dive inspection of the Third Ave Bridge across Harlem River at mile 1.9, between the Bronx and Manhattan, NY. The contractor will be utilizing a 21-foot parker boat – Hull ID: CT 9803AY, for this inspection. Mariners requiring full horizontal clearance can contact the contractor via marine radio VHF-FM Ch 13/16 or by calling Joseph Solis at (203) 305-0729. Mariners are advised to exercise caution and reduce wake when transiting the area.	Lat: 40° 48' 30" Lon: -073° 55' 56"
Main Channel - East River Main Channel/General/Bridges/Inspection	Bridges	General/Bridges/Inspection From: 2026-09-21 To: 2026-09-26 Location: 40-42-49.490N/073-58-19.960W Bridge Name: Williamsburg Bridge From September 21-25, 2026, between 9:30 a.m. and 3:00 p.m., a bridge traveler will be operated under the Williamsburg Bridge over East River at mile 2.3 to perform bridge maintenance. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or call 917-295-1856 or 917-471-2257. The traveler platform will be moved out of the navigable channel after work hours or when not in use. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 42' 49" Lon: -073° 58' 20"
Main Channel - East River Main Channel/General/Bridges/Maintenance	Bridges	General/Bridges/Maintenance From: 2026-09-23 To: 2026-09-24 Location: 40-42-26.240N/073-59-26.350W Bridge Name: Manhattan Bridge On September 23, 2026, between 9:00 a.m. and 2:00 p.m., a bridge traveler will be operated under the Manhattan Bridge over East River at mile 1.1 to perform bridge inspection. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or call 917-295-1856 or 917-471-2257. The traveler platform will be moved out of the navigable channel after work hours or when not in use. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 42' 26" Lon: -073° 59' 26"
Main Channel - East River Main Channel/General/Bridges/Maintenance	Bridges	General/Bridges/Maintenance From: 2026-09-24 To: 2026-09-25 Location: 40-45-24.950N/073-57-16.550W Bridge Name: Queensboro Bridge On September 24, 2026, between 9:00 a.m. and 2:00 p.m., a bridge traveler will be operated under the Queensboro Bridge over East River at mile 5.5 to perform bridge inspection. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or call 917-295-1856 or 917-471-2257. The traveler platform will be moved out of the navigable channel after work hours or when not in use. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 45' 25" Lon: -073° 57' 17"
Main Channel - East River Main Channel/General/Bridges/Maintenance	Bridges	General/Bridges/Maintenance From: 2026-09-28 To: 2026-10-03 Location: 40-42-49.490N/073-58-19.960W Bridge Name: Williamsburg Bridge From September 28-October 2, 2026, between 9:30 a.m. and 3:00 p.m., a bridge traveler will be operated under the Williamsburg Bridge over East River at mile 2.3 to perform bridge maintenance. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or call 917-295-1856 or 917-471-2257. The traveler platform will be moved out of the navigable channel after work hours or when not in use. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 42' 49" Lon: -073° 58' 20"
Main Channel - East River Main Channel/General/Bridges/Maintenance	Bridges	General/Bridges/Maintenance From: 2026-09-28 To: 2026-10-03 Location: 40-45-24.950N/073-57-16.550W Bridge Name: Queensboro Bridge From September 28-October 2, 2026, between 8:00 a.m. and 2:00 p.m., a bridge traveler will be operated under the Queensboro Bridge over East River at mile 5.5 to perform bridge inspection. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or call 917-295-1856 or 917-471-2257. The traveler platform will be moved out of the navigable channel after work hours or when not in use. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 45' 25" Lon: -073° 57' 17"

Main Channel - East River Main Channel/General/LAA/RNA/Security Zone	LAA/RNA	General/LAA/RNA/Security Zone From: 2026-09-20 To: 2026-09-27 United Nations General Assembly 81: Security Zones 1. From September 20 – 26, 2026, the U.S. Coast Guard will enforce security zones on the East River near the United Nations Headquarters, and near the Wall Street Heliport. The East River security zones encompass all waters of the East River between East 36th Street and the Queensboro/59th Street Bridge and are portioned into three distinct zones (Zones 1- 3) as referenced in 33 CFR 165.164(a) (4,5, and 6). The Wall Street Heliport security zone encompasses a section of all navigable waters just south of Wall Street, Manhattan. More detailed descriptions and visual depictions are provided on pages 2 and 3 of this Marine Safety Information Bulletin (MSIB). 2. Enforcement times for security zones described in this MSIB may change. USCG Sector New York and Vessel Traffic Services (VTS) New York will broadcast exact closure periods daily to keep mariners informed. 3. Coast Guard Sector New York will monitor VHF-FM channel 16. If unable to reach the U.S. Coast Guard on VHF-FM channel 16, contact VTS New York on VHF-FM channel 12 or at (718) 354-4088 for updates. 4. Violation of a security zone can result in civil penalties up to \$117,608 per violation and/or other enforcement actions as per 46 U.S.C. 70036(a). 5. Roosevelt Island Bridge Openings: Vessels that require opening of the Roosevelt Island Bridge must contact the bridge tender at least 15 minutes in advance by phone (646) 899-0441, from 6:00 am to 8:00 pm or via VHF-FM CH 13. UNGA East River Security Zone Restrictions/Closures Zone 1: Manhattan Shoreline: Always in effect. Beginning 6:00 am on September 20th no vessels are allowed to transit within approximately 180 yards of Manhattan Shoreline at East 36th St to 125 yards from Manhattan Shoreline at the Queensboro/59th St Bridge. Commercial vessels must check in with VTS New York (VTSNY) on VHF-FM CH 12 prior to entering the West Channel. Zone 2: West Channel Closure: No commercial or recreational traffic in the west channel of the East River between East 36th Street and the Queensboro/59th Street Bridge. Please note commercial vessels must check in with VTS New York (VTSNY) on VHF-FM CH 12 prior to entering the West Channel. NYC DEP sludge vessels and NYC Department of Sanitation barges will not be allowed to transit without 24-hour advance coordination with the Sector New York Enforcement Division at (505)523-662. Zone 3: Full River Closure: No vessel traffic will be allowed in the East River between East 36th Street and the Queensboro/59th Street Bridge. No vessel transits will be permitted within the security zone while it is in effect without the U.S. Coast Guard's approval.	
Main Channel - East River Main Channel/General/LAA/RNA/Security Zone	LAA/RNA	General/LAA/RNA/Security Zone From: 2026-09-18 To: 2026-09-27 Wall Street Heliport East River Closures Wall Street Heliport: The potential exists for this security zone to be enforced per 33 CFR 165.164(a)(1) during mornings and evenings on dates and times that are as directed by Sector New York. No vessel transits will be permitted within the security zone while it is in effect without the U.S. Coast Guard's approval. The security zone includes all waters of the East River off the Wall Street Heliport within the following boundaries: East of a line drawn between approximate position 40°42'01"N, 074°00'39"W (east of The Battery) to 40°41'36"N, 074°00'52"W (NAD 1983) (point north of Governors Island) and north of a line drawn from the point north of Governors Island to the southwest corner of Pier 7, Brooklyn; and south of a line drawn between Wall Street, Manhattan, and the northwest corner of Pier 2, Brooklyn.	
Main Channel - East River Main Channel/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-03-06 To: 2026-10-31 Location: 40-43-12.792N/073-55-32.268W Trevcon Construction Company, LLC. Will be Removing an Existing Seawall; Removal of Timber Decking and Piles; Dredging, Installation of Scour Protection, in Newton Creek, NY, in position 40-43-12.8N, 073-55-32.3W, between March 6, 2026, to October 30, 2026, between 5:00am, to 7:00pm. Equipment on scene will be Two Barge mounted cranes (180' x 60'), Two Barges (140' x 50'), One Barge (195' x 35').	Lat: 40° 43' 13" Lon: -073° 55' 32"
Main Channel - East River Main Channel/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-03-20 To: 2027-08-31 Location: 40-48-15.084N/073-55-49.980W Trevcon Construction Company will be conducting demolition and reconstruction operations on the Harlem River, west shoreline from RFK Bridge(125th St.) to Metro North Rail Bridge (132nd St.)in position 40-48-15.1N, 073-55-50W, through August 2027, Monday through Friday, between 5:00am to 6:00pm. Equipment on scene will be multiple crane barges, and material barges, monitoring VHF-FM CH 13, 16, 65, & 75. Floating Equipment will be positioned along the West shoreline of the Harlem River, vessel traffic will not be impeded.	Lat: 40° 48' 15" Lon: -073° 55' 50"
Main Channel - East River Main Channel/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-03-23 To: 2028-11-04 Location: 40-42-34.272N/073-59-05.388W Reicon will be conducting pile repair and rehabilitation operations at Pier 36, East River, New York, NY, in position 40-42-34.3N, 073-59-05.4W, from February 23, 2026, to November 3, 2028, Monday through Friday, between 6:00am to 2:00pm, local time. Equipment on scene will be a dive barge, monitoring VHF-FM Ch 13 and is requesting mariners to minimize their wake, while operations are being conducted.	Lat: 40° 42' 34" Lon: -073° 59' 05"
Main Channel - East River Main Channel/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-07-20 To: 2026-12-31 Location: 40-42-20.880N/073-58-57.288W This Local Notice to Mariners (LNM) report, submitted to the U.S. Coast Guard First District, announces upcoming waterborne crane operations in support of building construction on the East River, New York. The project, managed by Grace Industries LLC, will take place at coordinates 40° 42.348'N, 073° 58.955'W, from July 20, 2026, through December 31, 2026. Operations are scheduled Monday through Saturday, 6:00 AM to 6:00 PM, with cranes and material barges present at the site. Mariners in the area are advised to use slow speed ("slowbell") near the crane operations and may contact the operation via marine radio channels 16, 13, and 61A for coordination.	Lat: 40° 42' 21" Lon: -073° 58' 57"
Main Channel - East River Main Channel/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-09-09 To: 2026-12-01 Location: 40-41-48.840N/073-59-58.920W Trevcon Construction Company LLC submitted a Local Notice to Mariners (LNM) Information Form to the U.S. Coast Guard First District for a marine construction project in New York's East River/New York Bay. The project, scheduled from September 28 to November 30, 2026, involves the removal of the BBP Pier 4 Marine Transfer Bridge, including steel structure removal, timber pile removal, and diver operations. Work will occur daily from 5:00 AM to 6:00 PM at the coordinates 40°41'49" N, 73°59'59" W. Equipment on site will include a crane barge, material barge, and diving equipment.	Lat: 40° 41' 49" Lon: -073° 59' 59"
Main Channel - East River Main Channel/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-08-03 To: 2026-10-05 Location: 40-41-49.128N/073-59-59.892W Trevcon Construction Company LLC submitted a Local Notice to Mariners (LNM) Information Form to the U.S. Coast Guard First District for a marine construction project in New York's East River/New York Bay. The project, scheduled from August 3 to October 5, 2026, involves the removal of the BBP Pier 4 Marine Transfer Bridge, including steel structure removal, timber pile removal, and diver operations. Work will take place daily from 5:00 AM to 6:00 PM at the coordinates 40.6969° N, -73.9997° W. Equipment on site will include a crane barge, material barge, and diving equipment.	Lat: 40° 41' 49" Lon: -073° 59' 60"
Main Channel - East River Main Channel/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-08-24 To: 2026-11-30 Location: 40-41-31.416N/074-00-46.368W M&J LLC will be conducting rehabilitation work at the Governors Island Pedestrian Bridge and Fender Wharf in New York. The work is scheduled to occur from August 24, 2026, through November 29, 2027, Monday through Friday from 7:30 a.m. to 3:00 p.m. The project location is listed at latitude 40° 41'31.4232" N and longitude 74° 0'46.3896" W. Equipment on scene will include an equipment barge supporting a Caterpillar 320 excavator fitted with a stone-handling attachment. The form does not list vessel radio frequencies, passing arrangements, chart numbers, or vessel movement times.	Lat: 40° 41' 31" Lon: -074° 00' 46"

Main Channel - East River Main Channel/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-09-08 To: 2027-06-30 Location: 40-48-05.976N/073-53-22.992W Mariners are advised that Trevcon Construction Company LLC will conduct existing fender system replacement work with diving operations at the Hunts Point WRRF in the East River/New York Bay, New York, from July 27, 2026, through June 30, 2027. Operations are scheduled daily from 0500 to 1800 in the vicinity of 40°48'06"N, 073°53'23"W. Applicable chart number is USSNYCFH. Equipment on scene will include a crane barge, material barge, and diving equipment. Mariners transiting the area are requested to exercise caution, proceed at safe speed, and avoid interfering with construction and diving operations. No passing arrangements or vessel movement times were provided. For additional information, contact Dan Seligmann, Trevcon Construction Company LLC, at 631-923-8530 or Dseligmann@Trevcon.com.	Lat: 40° 48' 06" Lon: -073° 53' 23"
Main Channel - East River Main Channel/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes NY-NYC-EAST RIVER-MONGOMERY STREET TO E 14 STREET From: 2022-01-03 To: 2026-12-30 Location: 40.72676° N / 73.97142° W 40.72541° N / 73.97174° W 40.7188° N / 73.97335° W 40.71435° N / 73.97513° W 40.71142° N / 73.97659° W 40.71049° N / 73.97783° W 40.71014° N / 73.98107° W 40.70978° N / 73.98106° W 40.70947° N / 73.98421° W 40.70955° N / 73.98423° W 40.70981° N / 73.98122° W 40.71022° N / 73.98129° W 40.71057° N / 73.97787° W 40.71144° N / 73.97672° W 40.71435° N / 73.97526° W 40.7188° N / 73.97348° W 40.72541° N / 73.97187° W 40.72676° N / 73.97157° W 40.72676° N / 73.97142° W IPCP will be conducting esplanade, bulkhead, and park reconstruction, on the East River, Montgomery St to East 14th Street, from January 2022 to December 2026, 5-7 days a week, between 6:00am to 6:00pm. Equipment on scene will be Tugboat DEBRA QUINN, Inspection Boat, 290 x 40 Mooring Barges, 250 x 62 Gantry Crane Barge, Crawler Crane Barge, 150 x 60 Deck Barges, 140 x 40 Hopper Barges All moving of vessels to occur by tugboat; vessels will be moved at all times of day and night and will be monitoring VHF-CH 13 and 66. Mariners are urged to transit at their slowest safe speed to minimize wake and proceed with caution after passing arrangements have been made.	
Main Channel - East River Main Channel/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2025-09-01 To: 2027-07-05 Location: 40.7427° N / 73.97198° W 40.74265° N / 73.97148° W 40.73988° N / 73.97216° W 40.73999° N / 73.97258° W 40.7427° N / 73.97198° W Phoenix Marine Co. will be conducting diver\ operations in the East River at the Marginal Wharf Platforms at The Water Club and E. 34th St. Heliport, in position 40°44'36"N-73°58'16" W through 40°44'22"N-73°58'20"W. Work will be conducted between 6:00am-2:00pm, from September 15, 2025 to July 5, 2027. Equipment on scene will be (1) crane barge, (1) material barge and (1) work platform barge monitoring VHF-CH 9. Mariners transiting the work area are urged to exercise extreme caution, travel at the slowest safe speed to minimize wake, and proceed with caution	
Main Channel - East River Main Channel/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-05-26 To: 2026-09-30 This Local Notice to Mariners (LNM) Information Form, submitted to the U.S. Coast Guard District Northeast, details a marine construction project by C.A.C. Industries, managed by Michal Mludzik. The project involves timber pile repair, dive work, and concrete infill under the esplanade at Bobby Wagner Walk, New York, NY (just north of the E 90th Street ferry and south of DSNY 91st Street MTS), with precise coordinates at 40°46'41.2"N, 73°56'33.4"W. Operations are scheduled to begin May 27, 2026, and continue through September 2028, taking place Monday through Friday from 0600 to 1600 hours, dependent on tidal conditions. The site will utilize a 120x55 deck barge equipped with an MLC-150 crane, and marine radio communications will be available via channel 16 (hail) and channel 78 (monitor). The barge will be stationed along the bulkhead to minimize navigation impact.	

Edgartown Harbor

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Edgartown Harbor/General/Marine Events/Regatta (Race)	Marine Events	MA – EDGARTOWN OUTER HARBOR – 103rd ANNUAL JUNIOR ONE-DESIGN – RACE/REGATTA Mariners are advised that the 103rd Annual Regatta Junior One-Design is scheduled to be held in the vicinity of Edgartown Outer Harbor. The event will take place from Tuesday July 14 through Wednesday July 15, 2026, from 8:00 a.m. to 3:30 p.m. each day. Expect up to 96 sailing vessels, 8-14 ft in length. Mariners are advised to transit the area with extreme caution. Mariners may contact the person in charge by phone at (732) 245-3443 or by Channel 72 VHF.	

Erie Basin

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Erie Basin Entrance Light 2	36895	LT EXT	FD

Essex Bay

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Essex Bay Entrance Lighted Bell Buoy 1	9480	RBN IMCH/BUOY DMGD	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector Boston, Submerged Land Act (SLA) - Essex Bay/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	Essex Bay entrance has experienced increased shoaling from Essex Bay Buoy 3 in approximate position 42-40.4N 070-42.7W to Essex Bay Buoy 3A in approximate position 42-40.3N 070-43.3W. Mariners are advised that shoaling has been identified and extends the entire width of the channel to a least depth of 2 feet mean low water (MLW). Mariners without local knowledge are advised to transit with extreme caution and only during plus tides. Essex Bay Channel Buoy 16 has been reported having increased shoaling. Mariners are urged to use caution while transiting the area.	

Fire Island Inlet

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE

Fire Island Inlet Lighted Buoy 3	29130	LT EXT	FD
Fire Island Inlet Lighted Buoy 18	29195	LT EXT	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Approaches To New York Nantucket Shoals To Five Fathom Bank - Fire Island Inlet/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2024-09-12 To: 2039-11-14 Location: 40.63186° N / 73.3053° W 40.63094° N / 73.29678° W 40.62873° N / 73.29154° W 40.6278° N / 73.27761° W 40.62674° N / 73.27757° W 40.62762° N / 73.29276° W 40.62948° N / 73.29692° W 40.63016° N / 73.30538° W 40.62915° N / 73.3204° W 40.62306° N / 73.3237° W 40.62391° N / 73.33134° W 40.63165° N / 73.32152° W 40.63186° N / 73.3053° W NY-FIRE ISLAND INLET Shoaling has been identified in Fire Island Inlet in the area between buoys 3, 7, 13, and 15. Mariners are urged to use caution while transiting the area.	
Fire Island Inlet/General/Marine Construction (Excluding Bridges)/Dredging	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Dredging From: 2026-09-08 To: 2027-03-31 Great Lakes Dredge & Dock Company, LLC will be conducting dredging operations covering the Fire Island Inlet and Shores Westerly to Jones Inlet, New York Beach Erosion Control and Navigation Project. The project involves placing approximately 1.5 million cubic yards of beach fill along the Gilgo Beach shoreline, with material dredged from Fire Island Inlet and deposition basins. Work is scheduled to begin September 8, 2026, and continue through March 2027, operating 24 hours per day, seven days per week. The contractor will use the cutter suction dredge Illinois, three booster pump plants, including two on land, and submerged pipeline to hydraulically pump dredged material to the placement area. Supporting waterside equipment includes the Booster Plant Jack, Survey Vessel Cooper River, Crew Boat Saginaw River, Derrick 184, Anchor Barges 114 and 115, Fuel Barge 1003, and several tug vessels. All vessels and pipelines will be lighted in accordance with U.S. Coast Guard regulations. Marine VHF Channels 13 and 16 will be monitored continuously during operations. The submission includes coordinates for the staging area, submerged pipeline route, and borrow area associated with the dredging and beach fill work. The contractor notes that a booster is located between pipeline points ML-2 and ML-3. Mariners transiting the area are urged to exercise extreme caution due to ongoing dredging activity, submerged pipeline, vessel operations, and related construction equipment. Project contacts identified in the request are Project Manager Mike Hungerford and Site Manager Cameron Scheid. The document is marked confidential and proprietary by Great Lakes Dredge & Dock Company.	

Flanders Bay.

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Peconic River Lighted Buoy 4	28980	LT EXT	PA

Fox Island Thorofare

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Fox Ears Daybeacon 22	3955	OFF STATION	FD

Frenchman Bay.

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Egg Rock Light	1865	SS IMCH	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector Northern New England, Submerged Lands Act (SLA) - Frenchman Bay/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-05-18 To: 2028-03-31 L Beginning May 18, 2026, and continuing until March 02, 2028, a Crane Barge along with an attendant plant will be operating at various locations in and around the Bar Harbor Breakwater located adjacent to Bald Porcupine Island and the Porcupine Dry Ledge. Materials will be delivered to this Crane Barge via Tug transit. The work zone in general extends approximately 300 feet on either the north or south sides of the existing breakwater rock structure. Mariners are urged to transit at their slowest safe speed to minimize wake and proceed with caution when travelling near the work area. When construction vessels are to navigate to the Bar Harbor breakwater they shall follow a designated haul route to minimize any disruptions to local marine traffic or fishermen. Vessels shall enter the harbor on a course of 343°. Upon reaching vertex of N 264340.78, E 1069401.28 (northeast of Bald Porcupine Island) they shall alter course to a heading of 270°. They will then continue at this heading until reaching a vertex of N264340.78, E 1067401.28 where they shall set a heading of 210° and maintain this heading to enter the work zone. The work zone in general extends approximately 300 feet on either the north or south sides of the existing breakwater rock structure. Its vertices are: Northeast corner: N 262830.48, E 1066588.92, Southeast corner: N 262354.34, E 1066858.96, Northwest corner: N 261413.24, E 1064383.15, Southwest corner: N 260917.96, E 1064721.87. When leaving the work zone any vessels shall navigate the course described above with opposite headings. Should any construction vessels need to leave the work zone for safe harbor they shall exit the work zone at its northeast corner (N 262830.48, E 1066588.92) on a course heading of 0° until reaching a vertex of N 268623.87, E 1066472.54 and start a heading of 45°. A safe harbor point shall be N 269679.20, E 1067527.92 which is west of Burnt Porcupine Island. An alternate safe harbor spot shall continue on the same course until reaching vertex N 270669.19, E 1068517.87 and then alter course to heading 148° until reaching safe harbor at N 269494.97, E 1070376.68. This safer harbor location is between Burnt Porcupine Island and Long Porcupine Island, east of Rum Key. Vessels may leave this safe harbor location on a heading of 210° back into the work zone. The above described safe harbor locations may be reached in the opposite direction if chosen. The Crane Barge will not be sitting in the federally marked navigation channel while repairing the breakwater. Should any construction vessels need to leave the work zone for safe harbor they shall exit the work zone and travel across the navigation channel to a designated safe harbor point that is located west of Burnt Porcupine Island. An alternate designated safe harbor point is located between Burnt Porcupine Island and Long Porcupine Island, east of Rum Key. The crew will be working Monday through Friday during daylight hours. The Crane and attendant plant will both monitor marine VHF Channel 16. Mariners are urged to use extreme caution and transit the area at a safe speed. If you have any questions or require additional information, please contact me via e-mail at mlayton@agatenj.com or via telephone at (609) 364-2078.	

Gardiners Bay South Entrance

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Block Island Sound And Gardiners Bay - Gardiners Bay South Entrance/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2024-09-12 To: 2039-12-27 NY-BLOCK ISLAND SOUND AND GARDINERS BAY-GARDINERS BAY SOUTH ENRANCE-ACABONACK HARBOR Mariners are advised that dangerous shoaling conditions exist in Acabonack Harbor and vicinity which cause dangerous conditions when transiting the channel. Acabonack Harbor Buoys 1-4 (Private aids have been temporarily discontinued until the harbor is dredged. Mariners should exercise extreme caution when navigating the channel.	

Gerritsen Inlet

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Rockaway Inlet - Gerritsen Inlet/General/Bridges/Inspection	Bridges	General/Bridges/Inspection From: 2026-07-23 To: 2026-12-01 Location: 40-35-09.520N/073-54-44.320W Bridge Name: Belt Pkwy Bridge From August 3, 2026 to November 30, 2026, between 9 am to 3 pm, a barge with 60' manlift will be utilized to inspect the Belt Parkway across Hendrix Creek at mile 0. Mariners requiring full vertical and horizontal clearance can contact the contractor via marine radio VHF-FM Ch 13/16 or by calling Jaw Pawluczuk at (646) 872-2967. Mariners are advised to exercise caution and reduce wake when transiting the area.	Lat: 40° 35' 10" Lon: -073° 54' 44"
Rockaway Inlet - Gerritsen Inlet/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-04-07 To: 2026-10-04 Location: 40-35-12.084N/073-54-50.364W A sunken sailboat has been identified in position 40°35'12.6"N 73°54'49.4"W. Hull is submerged with the mast visible above the water. Vessel is not marked. Mariners urged to use caution and maintain sharp lookout in area.	Lat: 40° 35' 12" Lon: -073° 54' 50"

Gloucester Harbor

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Mayflower Ledge Buoy 8	9890	SINKING	FD

Goodwives River Approach

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Goodwives River Mid-Channel Buoy A	25121	LT EXT	PA

Great Kills Harbor

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Raritan Bay - Great Kills Harbor/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2024-09-12 To: 2039-10-27 Location: 40.53315° N / 74.14062° W 40.52984° N / 74.13963° W 40.52957° N / 74.1409° W 40.53297° N / 74.14193° W 40.53315° N / 74.14062° W NY-GREAT KILLS HARBOR Shoaling has been reported in in the vicinity of Great Kills Harbor, between buoys 6 and 8. Mariners are advised to proceed with caution while transiting the area.	

Great South Bay

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Great South Bay Buoy 30	29340	OFF STATION	FD

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Mud Creek Buoy 4	29797	OFF STA	PA
Fox Creek Channel Lighted Buoy 9	29640	OFF STA	PA
Barrett Beach Lighted Buoy 4	29925	OFF STA/HAZ NAV	PA
Watch Hill Channel Range Front Light	30050	MISSING	PA
Watch Hill Channel Range Rear Light	30055	MISSING	PA

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION

West Channel - Great South Bay/General/Bridges/Maintenance	Bridges	General/Bridges/Maintenance From: 2026-09-08 To: 2026-09-26 Location: 40-40-33.950N/073-16-26.690W Bridge Name: Robert Moses Causeway Bridge From September 8-25, 2026, Monday-Friday, 9:00 a.m.-3:00 p.m., NYCDOT will be performing bridge washing on the following bridges: - Meadowbrook State Parkway Bridge over False Channel at mile 0.7 - Meadowbrook State Parkway Bridge over Fundy Channel at mile 2.7 - Meadowbrook State Parkway Bridge over Sloop Channel at mile 12.8 - Loop Parkway Bridge over Swift Creek at mile 11.9 - Loop Parkway Bridge over Long Creek at mile 0.7 - Wantagh State Parkway Bridge over Seamans Island Creek at mile 0.5 - Wantagh State Parkway Bridge over Goose Creek at mile 16.1 - Wantagh Parkway Bridge over Sloop Channel at mile 15.4 - Robert Moses Causeway over Fire Island Inlet at mile 4 A Snooper Truck with a safety boat in the water will be utilized. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or call 631-339-4810. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 40' 34" Lon: -073° 16' 27"
Great South Bay/General/Bridges	Bridges	Great South Bay/General/Bridges From: 2026-08-31 To: 2026-10-17 Location: 40.676097, -73.274081 Bridge Name: Robert Moses Causeway Bridge From September 8, 2026 to October 16, 2026, an under-bridge inspection unit (UBIU) and safety boat will be operating at the Robert Moses Causeway across Great South Bay at mile 7.3, in Babylon, New York. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch 13/16 or call Seth Medwick at 917-821-9130. Mariners are advised to exercise caution and reduce wake when transiting the area.	Lat: 40° 40' 34" Lon: -073° 16' 27"

Greenwich Bay Approach

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Patience Island Lighted Bell Buoy 8	19340	OFF STATION	FD

Guilford Harbor

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
West River Entrance Buoy 1W	23770	MISSING	PA

Hackensack River

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Newark Bay - Hackensack River/General/Bridges/Rehabilitation	Bridges	General/Bridges/Rehabilitation From: 2024-09-25 To: 2028-01-20 Location: 40.82286667° N / 74.03445556° W Bridge Name: Westerly Hackensack River Bridge Replacement of Two Waterway Piers and Bridge Washing – Installation of temporary trestle at the New Jersey Turnpike Bridge across the Hackensack River at mile 11.8 will commence on July 1, 2024. Hours of operation are from 6 am to 4 pm. 6 Shugart sectional barges will be installed at piers 15 and 18 outside navigation channel. A barge will be operating in the navigation channel for bridge washing during month of January in 2026, 2027 and 2028 (tentative). Mariners requiring full horizontal clearance can contact Albert Parker via marine radio VHF-FM Ch 13/16 or 215-495-2140. Mariners are advised to exercise caution when transiting the area. This project is to be completed by January 20, 2028.	Lat: 40° 49' 22" Lon: -074° 02' 04"
Newark Bay - Hackensack River/General/Bridges/Modification	Bridges	General/Bridges/Modification From: 2024-12-10 To: 2027-02-08 Location: 40.79992778° N / 74.07591389° W Bridge Name: Berry's Creek Canal New Jersey Turnpike Bridge Bridge Replacement – Installation of temporary trestle to the New Jersey Turnpike Bridge (W112.72B) over Berry's Creek Canal at mile .05 will commence on or about December 16, 2024. Hours of operation are from 6 a.m. to 4 p.m. weekdays. There will be a safety boat operating IVO the bridge. A 84ft navigation channel free of obstruction will be maintained at all times. For construction details please contact Jed Fitz, superintendent at 267-907-5932 or via marine radio VHF-FM 13/16. This project is to be completed by February 8, 2027. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 47' 60" Lon: -074° 04' 33"
Newark Bay - Hackensack River/General/Bridges/Construction	Bridges	General/Bridges/Construction From: 2024-05-24 To: 2027-10-22 Location: 40.75346° N / 74.095153° W Bridge Name: Portal (N) Bridge Portal (N) Bridge Bridge replacement to the Portal Bridge North, across Hackensack River at mile 5.04 is in progress. Hours of operations are from Monday to Friday between 6:30 a.m. to midnight. There will be waterborne equipment blocking one draw of a swing bridge at a time and the other draw will be free and clear of any equipment for the passage of vessels. Mariners can contact one of the three (3) provided telephone numbers/emails or via marine radio VHF-FM CH 13/16 advising of travel through the channel (including possible return trips): 1. Martir Ortezt – Main Span Project Manager – (562) 307- 4916, mortez@taylor.com 2. Jack Phillips – Main Span Superintendent – (347) 924- 5635, john.h.phillips@skanska.com 3. Jim Hummel – Main Span Area Lead - (917) 417- 4885, Jim.Hummel@skanska.com Skanska Traylor PNB JV has been awarded the construction of the New Portal North Bridge Project (NJT Contract No. 20-083X, WBS No. GC.02) with a Notice to Proceed of April 7, 2022. Specific to the Hackensack River work, mile 5.0, the project consists of constructing two bridge piers, demolition of the existing center pier north fender, erecting three tied-arch spans of approximately 400 LF (1,200 LF overall), and demolition of the existing bridge once railroad traffic is switched to the new bridge. The current status of the channels: East Channel – Open West Channel – Close The Coast Guard is modifying the operating schedule that governs the Amtrak Portal Bridge across the Hackensack River, mile 5.0, at Little Snake Hill, New Jersey. This action is necessary to facilitate the construction of the new replacement Portal Bridge North, as designed by Amtrak as the owner of the bridge, adjacent to the current Amtrak Portal Bridge. This final rulemaking limits the extent of the opening of the Amtrak Portal Bridge in the horizontal position to prevent the swing span from striking the new Portal Bridge North during construction as follows: The draw shall only open to 55 feet horizontal clearance in the east channel and the west channel will be closed to all navigation while the draw is open. Whenever any bridge opening is needed, contact one of the three (3) provided telephone numbers/emails above with 24-hour advance notice to allow the removal of any waterborne equipment from the East Channel that restricts the horizontal clearance to less than 55 feet. The draw need not open for the passage of vessel traffic from 5 a.m. to 10 a.m. and from 3 p.m. to 8 p.m. Additional bridge openings shall be provided for tide restricted commercial vessels between 7 a.m. and 8 a.m. and between 5 p.m. and 6 p.m., if at least a two-hour advance notice is given by calling the number posted at the bridge. At all other times the bridge shall open on signal if at least a 2-hour advance notice is given. Please be advised that the existing Portal Bridge east channel horizontal clearance (temporary fender) will be maintained at approx. 55ft and west channel horizontal clearance at 91ft until it's demolished, both with a closed swing bridge vertical clearance of 23ft. With a swing bridge opening, the vertical clearance increases to 50ft with the existing Portal Bridge east channel horizontal clearance (temporary fender) being maintained at approx. 55ft and west channel being closed. Mariners are advised to exercise caution when transiting the area. This project will be completed by October 22, 2027.	Lat: 40° 45' 12" Lon: -074° 05' 43"

Newark Bay - Hackensack River/General/Bridges/Maintenance	Bridges	General/Bridges From: 2026-01-30 To: 2027-01-02 Location: 40.83963, -74.01879 Bridge Name: New Jersey Interstate 95 Turnpike Northbound Bridge On February 16, 2026, between 7:00 am and 3:30 pm on weekdays, in-water bridge maintenance will be performed on the New Jersey Turnpike (117.6 NO) IVO Pier One Overpeck Creek, mile .73 in Ridgefield, Bergen County, New Jersey. This work will be completed in three non-consecutive weeks. A 15 ft skiff and a 60 ft X 160 ft platform will be in the waterway intermittently. Mariners requiring full horizontal clearance can contact Matt Becker at (201) 304-3045. The project is to be completed by December 31, 2026. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 50' 23" Lon: -074° 01' 08"
Newark Bay - Hackensack River/General/Bridges/Maintenance	Bridges	General/Bridges From: 2026-02-12 To: 2027-01-01 Location: 40-47-15.684N/074-05-24.504W On February 16, 2026, between 7:00 am and 3:30 pm on weekdays and weekends, bridge maintenance will be performed on the New Jersey Turnpike (W111.48) over Berry Creek Canal, mile .1 in Lyndhurst, Bergen County, New Jersey. This work will be completed in 3 stages in approximately 3 non-consecutive weeks. A 15 ft skiff and a 60 ft X 160 ft platform will be in the water intermittently. Mariners requiring full horizontal clearance can contact Matt Becker at (201) 304-3045. The project is to be completed by December 31, 2026. Mariners are advised to exercise caution when transiting the area. Bridge Name: W111.48 NJ Interstate 95 Turnpike Bridge	Lat: 40° 47' 16" Lon: -074° 05' 25"
Newark Bay - Hackensack River/General/Bridges/Maintenance	Bridges	General/Bridges/Maintenance From: 2026-02-12 To: 2027-01-01 Location: 40-50-22.956N/074-01-07.536W On February 16, 2026, between 7:00 am and 3:30 pm on weekdays, in-water bridge maintenance will be performed on the New Jersey Turnpike (117.6) IVO Piers three and six over Overpeck Creek, mile .68 in Ridgefield, Bergen County, New Jersey. This work will be completed in three non-consecutive weeks. A 15 ft skiff and a 60 ft X 160 ft platform will be in the waterway intermittently. Mariners requiring full horizontal clearance can contact Matt Becker at (201) 304-3045. The project is to be completed by December 31, 2026. Mariners are advised to exercise caution when transiting the area. Bridge Name: 117 16 Interstate 95 Expressway Northbound Bridge	Lat: 40° 50' 23" Lon: -074° 01' 08"
Newark Bay - Hackensack River/General/Bridges/Maintenance	Bridges	General/Bridges/Maintenance From: 2026-02-13 To: 2027-01-01 Location: 40-49-23.160N/074-02-03.552W Bridge Name: Structure W115 36 Interstate 95 Highway Northbound Bridge On February 16, 2026, between 7:00 a.m. and 3:30 p.m. on weekdays, bridge maintenance will be performed on the deck, parapet, sidewalk and curb on Structure W115.36 Interstate 95 highway Southbound Bridge New Jersey Turnpike over the Hackensack River, mile 11.8 in Ridgefield, Bergen County, New Jersey. This work will be completed in 5 non-consecutive days. A 15 ft skiff and a 60 ft X 160 ft platform will be in the waterway intermittently. Mariners requiring full horizontal clearance can contact Matt Becker at (201) 304-3045. The project is to be completed by December 31, 2026. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 49' 23" Lon: -074° 02' 04"
Hackensack River/General/Bridges/Removal	Bridges	General/Bridges From: Tentative 2026-09-01 through 2026-12-28 (to start) To: Project will take approximately 8 weeks Location: 40.75343, -74.09542 Bridge Name: Amtrak Portal Bridge This is a preliminary notice. STJV is tentatively scheduled to start demolition of the existing Portal North bridge as early as September 1, 2026, but could start as late as end of December 28, 2026. The actual start date will be provided in future updates and is dependent on moving remaining existing rail traffic onto the new bridge. Upon making the rail traffic switch, the power to the swing bridge will be cut, making the existing bridge inoperable and commencing demolition activities. The demolition of the existing bridge will require eight (8) continuous weeks of full channel closures (Both Channels) for the safety of the public and for the successful completion of the work. The bridge demolition will NOT use explosives, instead sections of steel well be cut and removed with a crane on a barge. Once the steel beams are removed, cofferdams will be installed, the concrete piers will be demolished along with the timber fendering. Mariners are advised to plan accordingly and exercise caution when transiting the area.	Lat: 40° 45' 12" Lon: -074° 05' 44"
Hackensack River/General/Bridges	Bridges	Hackensack River/General/Bridges From: 2026-10-08 To: 2027-01-22 Location: 40.75343, -74.09542 Bridge Name: Amtrak Portal Bridge Demolition of the Amtrak Portal Drawbridge across Hackensack River at mile 5.0 will commence on October 9, 2026. To accommodate the demolition of the drawbridge superstructure, the Coast Guard has issued a temporary deviation from the regulation governing the operation of the moveable bridge. Under this temporary deviation, the bridge may remain in the closed position from October 9, 2026, until superstructure demolition over the navigable channel is complete on or about January 6, 2027. Mariners are also advised that a full channel closure in the vicinity of the bridge will take effect from approximately November 2, 2026, through January 6, 2027. Channel closure dates will be updated as demolition activities progress. Vessels that can make passage without a bridge opening request may do so until channel closures take effect. Mariners are advised to exercise caution and reduce wake when transiting the area.	Lat: 40° 45' 12" Lon: -074° 05' 44"

Hamburg Cove

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Hamburg Cove Entrance Buoy 4	22710	OFF STA	PA
Hamburg Cove Entrance Buoy 6	22720	OFF STA	PA
Hamburg Cove Buoy 15	22745	OFF STA	PA
Hamburg Cove Buoy 17	22750	OFF STA	PA
Hamburg Cove Buoy 19	22755	OFF STA	PA

Hampton Harbor

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Hampton Harbor Channel Buoy 7	8940	MISSING	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Hampton Harbor/General/Bridges	Bridges	Construction of the replacement State Route 1A Bridge across Hampton Harbor NH is ongoing. Vessel traffic continues to be restricted to the center span of the bridge due to work trestles placed in both side channels. Demolition of the existing bascule structure is scheduled to commence in October 2026. As part of the demolition activities, nighttime full-channel closures are expected over a three-week period in late October and early November. Specific dates and times for these channel closures will be published once the demolition schedule has been finalized. Mariners are reminded to exercise caution when transiting this area.	Lat: 42° 53' 46" Lon: -070° 49' 01"

Sector Northern New England, Submerged Lands Act (SLA) - Hampton Harbor/General/LAA/RNA/Temporary Regulated Navigation Zone	LAA/RNA	General/LAA/RNA/Temporary Regulated Navigation Zone From: 2025-07-08 To: 2030-12-31 The Coast Guard is establishing a temporary regulated navigation area (RNA) and a safety zone on the Hampton River at the inlet to Hampton Harbor, Hampton, NH, in response to hazardous conditions created by construction activities for the Neil R. Underwood Seabrook-Hampton Harbor Bridge replacement project. This rule is necessary to provide for the safety of life in the areas undergoing demolition and construction. The RNA will be enforced from July 1, 2025, through December 31, 2030, and will establish the following operating restrictions on vessels: Nothing in this regulation relieves any vessel, owner, operator, charterer, master, or person directing the movement of a vessel, from the consequences of any neglect to comply with this part or any other applicable law or regulation (i.e. the International Regulations for Prevention of Collisions at Sea, 1972 (72 COLREGS) or 33 CFR part 84—Subchapter E, Inland Navigation Rules) or of the neglect of any precaution which may be required by the ordinary practice of seamen, or by the special circumstances of the case. Entry and movement within the RNA is subject to a "Slow-No Wake" speed limit. All vessels may not produce a wake and may not attain speeds greater than five (5) knots unless a higher minimum speed is necessary to maintain bare steerageway. Any vessel transiting through the RNA must make a direct passage. No vessel may stop, fish, moor, anchor, or loiter within the RNA at any time. Vessels may not pass (overtake) another vessel within the RNA. Only one vessel is permitted to pass through the center span navigational channel at any given time. Except when transiting through the center span navigation channel, no vessel or craft may operate within 20 feet of the bridge(s). The operator of any vessel transiting in the RNA must comply with all lawful directions given to them by the COTP or the COTP's on-scene representative. viii) One-way traffic will flow northbound between the eastern side of the shallow waters and the Seabrook-Hampton Harbor Bridge. The northern side of the shallow area will accommodate one-way traffic moving west. The Safety Zone, includes all navigable waters within a 50-yard radius of the center point of the bridge, will be effective from July 1, 2025, through Decmber 31, 2030, but will only be enforced during active construction within the main span navigational channel or other instances which may cause a hazard to navigation as determined by the COTP. The COTP will make notification of the exact dates and times in advance of each closure period of the safety zone to the local maritime community through the Local Notice to Mariners and will issue a Broadcast Notice to Mariners via marine channel 16 (VHF-FM) as soon as practicable in response to an emergency. The complete rulemaking is available under Federal Register docket number USCG-2025-0389 and can be accessed through the federal portal at https://www.regulations.gov/document/USCG-2025-0389-0001 We invite your comments on this rulemaking. To submit your comment online, go to https://www.regulations.gov , and insert "USCG-2025-0389" in the "search box". Click "Search" and then click "Comment." We will consider all comments received on or before October 6, 2025. If the project is completed before December 31, 2030, enforcement of the safety zones will be suspended, and notice given via Local Notice to Mariners. The First Coast Guard District Local Notice to Mariners can be found at: https://www.navcen.uscg.gov/msi . For questions regarding this Marine Safety Information Bulletin contact Mr. Craig Lapiejko, Waterways Management at First Coast Guard District, telephone (571) 607-6314, e-mail: craig.d.lapiejko@uscg.mil . Matthew B. Stuck, First Coast Guard District Chief of Waterways Management, sends	
---	---------	--	--

Hingham Bay

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Weymouth Fore River - Hingham Bay/General/Marine Events/Regatta (Race)	Marine Events	MA – HINGHAM – HINGHAM BAY – HINGHAM BAY WEDNESDAY NIGHT RACES – REGATTA – The Hingham Bay Racing is hosting the Hingham Bay Wednesday Night Races every Wednesday night from 6:00 PM to 8:30 PM, from May 13, 2026, to September 30, 2026, in and around the vicinity of Hingham Bay. The event will consist of approximately 35 sailing vessels varying in length between 20'-50'. The person responsible for on scene safety can be reached on VHF CH 68. For more information, please contact Geoffrey Roth at 617-803-8344. Chart 13275	

Hingham Harbor Approach

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Hingham Harbor Approach Buoy 7	11995	SINKING	FD

Hog Island Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Hog Island Channel Lighted Buoy 19	16215	LT EXT	FD

Housatonic River

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Long Island Sound Eastern Part - Housatonic River/General/Bridges/Repairs, Painting, Or Fender Replacement	Bridges	General/Bridges/Repairs, Painting, Or Fender Replacement From: 2026-07-01 To: 2027-12-31 Location: 41-12-19.044N/073-06-34.776W Bridge Name: Devon Railroad Bridge CONNECTICUT – HOUSATONIC RIVER – Bridge Repairs – Beginning July 20, 2026, Connecticut Department of Transportation will be performing interim repairs on the Devon Bridge across Housatonic River at mile 3.9. Contractor will be utilizing a barge in the navigational channel that will reduce the horizontal clearance to 41'-6" as well as installing a platform under the bridge outside of the navigational channel that will reduce the vertical clearance. Work is expected to be completed in December 2027. Mariners with any questions can contact the contractor via marine radio VHF-FM Ch 13/16 or call CTDOT Environmental Coordinator Brian Brinsmade at (203) 389-3173. Mariners are advised to exercise caution and reduce wake when transiting the area.	Lat: 41° 12' 19" Lon: -073° 06' 35"

Hudson River

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
------	------	--------	----------

Haverstraw Bay North Reach Range Front Light	37900	LT EXT	FD
Hudson River Lighted Buoy 133	38585	OFF STATION	FD
Hudson River Buoy 173	38757	MISSING	FD
Hudson River Light 180	38785	LT EXT	FD

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Greens Cove Channel Lighted Buoy 1	37910	OFF STA/HAZ NAV	PA

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Main Channel - Hudson River/General/Bridges/Rehabilitation	Bridges	General/Bridges/Rehabilitation From: 2024-09-03 To: 2027-06-30 Location: 42-30-33.840N/073-46-23.340W Bridge Name: Castleton Highway Bridge Bridge Rehabilitation – Construction to the Castleton Highway Bridge across Hudson River at mile 135.7 is extended from June 30, 2026 to June 30, 2027. Hours of operation are from 7 a.m. and 7 p.m. Temporary safe span platforms will be installed under the tram rail steel (over navigation channel) which will reduce vertical clearance by approximately 6 feet. A minimum of 210 feet east side and the west side of the navigation channel will be cleared of obstruction at all times for safe passage of vessels. In addition, 25 feet of buffer will be maintained on each side of the channel marker. A safety boat will be operated IVO the bridge. Hot work will be performed during construction. Mariners requiring full horizontal clearance can contact the contractor/operator via marine radio VHF-FM CH 13 or call 518-857-9215. For all construction related questions, please contact Tim Mastro at 518-337-7231. This project is to be completed by June 30, 2027. Mariners are advised to exercise caution when transiting the area.	Lat: 42° 30' 34" Lon: -073° 46' 23"
Main Channel - Hudson River/General/Bridges/Rehabilitation	Bridges	General/Bridges/Rehabilitation From: 2024-05-01 To: 2029-12-31 Location: 40.851559° N / 73.9522° W Bridge Name: George Washington Bridge Rehabilitation of Lower Level Structural Steel, Painting and Replacement of Maintenance Travelers – Construction to the rehabilitation at the George Washington Bridge across the Hudson River at mile 11.0 will commence on May 1, 2024. Temporary work platform will be installed under the entire length of the bridge. The temporary work platform will reduce the vertical clearance by 3ft 9in plus 2ft sag max. below the low steel. Welding (hot work) may be performed during working hours. A 26 ft safety boat will be operating in the vicinity of the bridge. Mariners requiring full horizontal clearance can contact Michael Androsiglio 914-447-7513 or via marine radio. The resident engineer or contractor will be equipped with a VHF-FM marine radio and will be monitoring Channel 13/16 during hours of operation. Mariners can contact Marc Helman at 212-435-6112 or 551-220-8853 or Henry Chiang at 201-346-8921 for construction details. This project is to be completed by December 31, 2029. Mariners are advised to exercise extreme caution when transiting the area.	Lat: 40° 51' 06" Lon: -073° 57' 08"
Main Channel - Hudson River/General/Bridges/Construction	Bridges	General/Bridges From: 2025-08-18 To: 2029-02-29 Location: 42.65434° N / 73.74177° W Bridge Name: Livingston Avenue Railroad Bridge Bridge Replacement – Construction and demolition of existing railroad structures and facilities of the Livingston Avenue Railroad Bridge over the Hudson River at mile 146.2 between Albany and Rensselaer commenced on 18 August 2025. Work hours are Monday through Saturday between 6a.m. and 6 p.m. through September 30, 2026. There will be a safety boat operating IVO the bridge. For construction details please contact Jack Phillips at 347 924-5635 or via marine radio VHF-FM 13/16. Mariners are advised to exercise caution when transiting the area.	Lat: 42° 39' 16" Lon: -073° 44' 30"
General/Bridges/Closure (Scheduled Or Emergency)	Bridges	The Broadway Bridge at mile 6.8 in the Harlem River is unable to open for marine traffic until further notice, due to ongoing rehabilitation of its electrical and mechanical systems. The vertical clearance of the bridge in the closed position is 24 feet above MHW. Vessels that under the bridge in the closed position may do so at any time. Mariners are advised to use caution when transiting the area.	Lat: 40° 52' 25" Lon: -073° 54' 40"
Main Channel - Hudson River/General/Bridges/Construction	Bridges	Cable anchorage retrofits of the Governor Mario M. Cuomo Bridge across the Hudson River at mile 27.0 will commence on March 15, 2026. Temporary work platform will be installed in four locations underneath the bridge. The temporary work platform will extend 6 feet beneath the deck girders but remain above the traveler handrails, not impacting the vertical clearance of the bridge. Welding (hot work) may be performed during working hours. Work hours are 7:00 a.m. to 5:30 p.m. Monday through Friday. A safety boat will be operating in the vicinity of the bridge. The resident engineer or contractor will be equipped with a VHF-FM marine radio and will be monitoring Channel 13/16 during hours of operation. Mariners can contact Phillip Mirabella at 732-306-4135 or Rafik Moawad at 848-235-1281 for construction details. This project is scheduled to be completed by September 27, 2027. Mariners are advised to exercise caution when transiting the area.	Lat: 41° 04' 13" Lon: -073° 54' 27"
Hudson River/General/Bridges	Bridges	Hudson River/General/Bridges From: 2026-09-13 To: 2026-09-26 Location: 42.5094, -73.77315 Bridge Name: Castleton Highway Bridge From September 14, 2026, to September 25, 2026, between 7:00 am to 3:00 pm, a contractor will be performing an inspection of the Castleton-On-Hudson Bridge across the Hudson at mile 135.7, between Albany and Rensselaer, New York. The contractor will be utilizing two (2) Under Bridge Inspection Units (UBIUs) in coordination with a safety boat for this inspection. Mariners requiring full horizontal or vertical clearance can contact the contractor via marine radio VHF-FM Ch 13/16 or by calling (914) 801-0968. Mariners are advised to exercise caution and reduce wake when transiting the area.	Lat: 42° 30' 34" Lon: -073° 46' 23"
Main Channel - Hudson River/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2024-09-12 To: 2039-12-01 Location: 42.07223° N / 73.92927° W 42.07103° N / 73.92916° W 42.07132° N / 73.93048° W 42.07204° N / 73.92998° W 42.07223° N / 73.92927° W NY-HUDSON RIVER-CATSKILL CREEK-ESOPUS CREEK-ROUNDOUT CREEK Significant shoaling has been reported at the mouth of Catskill Creek, that may impact commercial traffic, along the southern portion of the channel. In Esopus Creek, shoaling has occurred faster than anticipated at the mouth of the creek when passing between Saugerties Lighthouse and Hudson River Lighted Buoy 93. In Roundout Creek, there is shoaling at the mouth of the creek. Mariners should exercise caution when navigating these areas.	

Main Channel - Hudson River/General/LAA/RNA/Safety Zone	LAA/RNA	General/LAA/RNA/Safety Zone § 165.T01-0336 Safety Zone; Hudson River, Manhattan, NY (a) Location. The following area is a safety zone: All waters of the Hudson River from surface to bottom, encompassed by a line connecting the following points beginning at 40°45'20.32" N, 074°00'23.84" W; thence to 40°45'23.34" N, 074°00'30.60" W; thence to 40°45'24.03" N, 074°00'40.85" W; thence to 40°45'18.89" N, 074°00'48.18" W; thence to 40°45'13.80" N, 074°00'48.64" W; thence to 40°45'08.03" N, 074°00'46.44" W; thence to 40°45'07.51" N, 074°00'37.61"W; thence to 40°45'09.18" N, 074°00'36.37" W; thence to 40°45'06.70" N, 074°00'30.78"W; thence returning along the Manhattan shoreline to the beginning point. These coordinates are based on the World Geodetic System (WGS 84) / North American Datum 83 (NAD 83). (b) Definitions. As used in this section, designated representative means a Coast Guard Patrol Commander, including a Coast Guard coxswain, petty officer, or other officer operating a Coast Guard vessel and a Federal, State, and local officer with law enforcement authority designated by or assisting the Captain of the Port New York (COTP) in the enforcement of the safety zone. (c) Regulations. (1) Under the general safety zone regulations in subpart C of this part, you may not enter the safety zone described in paragraph (a) of this section unless authorized by the COTP or the COTP's designated representative. (2) To seek permission to enter, contact the COTP or the COTP's representative on VHF-FM channel 16 or by telephone at (718) 354-4353. Those in the safety zone must comply with all lawful orders or directions given to them by the COTP or the COTP's designated representative. (3) Hudson River Community Sailing Vessels and Human Powered Vessels transiting directly to or from the Pier 66 area may transit through the southern area of the safety zone to the east of the Hudson River Cofferdam Lighted Hazard Buoy D (LLNR 37663.3) unless otherwise directed by the COTP or the COTPs designated representative. (d) Enforcement period. This section will be subject to enforcement from 12:01 a.m. on May 1, 2026, to 11:59 p.m. on January 20, 2029. If the project is completed before January 20, 2029, enforcement of the safety zone will be suspended, and notice given via Local Notice to Mariners. The Coast Guard Northeast District Local Notice to Mariners can be found at: https://www.navcen.uscg.gov/maritime-safety-information .	
Main Channel - Hudson River/General/LAA/RNA/Safety Zone	LAA/RNA	General/LAA/RNA/Safety Zone From: 2026-09-07 To: 2026-09-07 Location: HYDE PARK, NY - HUDSON RIVER – FIREWORKS SAFETY ZONE Mariners are advised that a safety zone will be enforced for a barge-based fireworks display, scheduled to be held on the Hudson River near the Culinary Institute of America in Hyde Park, NY on September 7, 2026 from 8:00p.m. until 10:00p.m with a rain date of September 9, 2026. The fireworks barge will be in approximate position 41° 44' 39.49" N, 73° 56' 17.09" W and the Safety Zone encompass all waters within a 450-foot radius from the barge. Vessels may not enter, remain in, or transit through the Safety Zone during the enforcement period unless authorized by the Coast Guard Captain of the Port. Other Federal, State and local agencies may assist these personnel in the enforcement of the Safety Zone.	
Main Channel - Hudson River/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2025-06-16 To: 2027-06-25 Location: 40.77075° N / 73.99841° W Reicon Group, LLC will be conducting pile repairs at Pier 94 from June 16, 2025, to June 25, 2027, Monday through Friday, between 7:00am to 3:30pm. Equipment on scene will be the RTC 330, monitoring VHF-FM CH 13 and will require a 24-hour notice for all vessel movement requests.	Lat: 40° 46' 15" Lon: -073° 59' 54"
General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2025-11-03 To: 2026-10-31 Location: 40-42-06.984N/074-02-02.364W PKF-Mark III, Inc will be conducting marine construction operations on the Hudson River, at Liberty State Park, in position 40-42-7.000N, 074-02-02.370W, from November 3, 2025, to October 31, 2026, Monday through Friday from 6:00am to 5:00pm. Equipment on scene will be multiple floating barges, crane barges, and material barges.	Lat: 40° 42' 25" Lon: -074° 02' 01"
Main Channel - Hudson River/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-02-17 To: 2031-01-29 Location: 41-59-01.284N/073-57-06.408W Bank Stabilization operations will be conducted north of the Kingston Rhinecliff Bridge off the west side of the Hudson River in position 41-59-1.240N, 073-57-9.794W, from February 17, 2026, to January 28, 2031. Work will be conducted withing the Town of Ulster allowable work hours between 7:00 am to 10:00 pm. Equipment on scene will be, Long reach excavators from upland at first and possibly on a barge if necessary. All work will be within the existing cove. The work will be within the existing cove off the Hudson River and will not interfere with the channel. The installation of a 44-foot by 8-foot floating pier, attached to a bulkhead by a 36-foot by 4-foot gangway. Three (3) finger piers, approximately 36-feet by 6-feet each, will extend from the main floating pier. The entire pier assembly will be held in place by five (5) plastic, 16-inch-diameter piles, each installed by vibratory hammer. The dredging of a total of approximately 1,429 cubic yards of material, over an area of approximately 12,500 square feet. All dredged material will be disposed of within a contained upland disposal area on the property.	Lat: 41° 59' 01" Lon: -073° 57' 06"
Main Channel - Hudson River/General/Marine Construction (Excluding Bridges)/Dredging	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Dredging From: 2026-08-17 To: 2026-10-10 Location: 40-46-01.920N/074-00-05.832W Donjon Marine Co., Inc. submitted a Local Notice to Mariners information form for FY27 maintenance dredging at the Manhattan Cruise Terminal berths in New York. Work is scheduled to begin on September 14, 2026, with an estimated completion date of October 10, 2026, and will occur 24 hours per day, seven days per week. The operation will take place inside the Manhattan Cruise Terminal berths near latitude 40°45'57.9384"N and longitude 73°59'57.03"W. Equipment on scene is expected to include one dredge, either Oyster Bay or Delaware Bay, three dump scows, one tending tug, and two towing-to-sea tugs. The project will operate as a "move on demand" dredging operation, with a tending tug maintained on site at all times to move vessels as needed to avoid impeding navigation. Vessels may be contacted on working channel 78 and will monitor channels 13 and 16.	Lat: 40° 46' 02" Lon: -074° 00' 06"
Main Channel - Hudson River/General/Marine Construction (Excluding Bridges)/Dredging	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Dredging From: 2026-08-28 To: 2027-12-31 Location: 42-29-01.464N/073-47-14.784W Carver Companies will conduct maintenance dredging operations at the Port of Coeymans on the Hudson River, New York, at approximate position 42°29'01.45"N, 073°47'14.78"W (42.483737N, 73.787440W). Operations are scheduled to begin September 1, 2026, and continue through December 31, 2027, operating 24 hours per day, 7 days per week. Vessels may contact the operation on VHF-FM channels 13 and 81A. Mariners should contact the tending tug CMT PIKE via VHF for passing arrangements and coordination to avoid impeding navigation.	Lat: 42° 29' 01" Lon: -073° 47' 15"

Main Channel - Hudson River/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-01-06 To: 2027-01-21 From November 24, 2024, through January 20, 2027, Weeks Marine and Frontier-Kemper Tutor Perini JV will conduct marine construction in the Hudson River on behalf of the Hudson Tunnel Project. The construction area is bounded by the following positions off the Manhattan bulkhead: 40-45-20.32N 074-00-23.84W; 40-45-18.89N, 074-00-48.18W; 40-45-13.80N 074-00-48.64W; 40-45-12.40N. 074-00-28.47W. The USCG has established a Safety Zone, 33 CFR 165.T01-0336 Safety Zone; Hudson River, Manhattan, NY. Mariners transiting west of the safety zone should proceed at a speed to minimize potential wake or surge damage to the vessels working the construction area. There are two distinct jobsites within the construction area. The first jobsite, which is operated by Weeks Marine, is west of Pier 66. Within this jobsite, Weeks Marine is conducting soil mixing within a 110' wide x 600' long cofferdam for the Hudson River Ground Stabilization (HRGS) Project. Work hours are approximately 7AM – 12AM, Monday through Friday, and 7AM – 3PM, Saturday. The cofferdam is marked with FL W 4s lights at each corner and at 30 ft intervals, and with white retro-reflective tape 6" high and at least 4' long is installed above the MHHW mark every 50 feet on the cofferdam. The Weeks 61 barge (AIS - WEEKS 61 Barge) will move between the south and north sides of the cofferdam to excavate spoils within the cofferdam. The Weeks 61 barge monitors VHF-FM channels 13 / 16 / 82. The Weeks 263 barge (AIS- WEEKS 263) and material barges will be on the southern side outside of the cofferdam to support drilling operations within the cofferdam. The Weeks 263 barge monitors VHF-FM channels 13 / 16 / 67. The Weeks 283 barge (AIS - WEEKS 283) and material barges will be on the northern side, outside of the cofferdam, to support timber pile obstruction removal. The Weeks 283 barge will remove timber pile obstructions and place them onto a material barge. The Weeks 283 barge monitors VHF-FM channels 13 / 16 / 66. The second jobsite, which is north of Pier 66 in close proximity to the Manhattan bulkhead and near position 40-45-15.270N, 074-0-28.007W, is operated by Frontier-Kemper Tutor Perini JV. Within this jobsite, Posillico Civil has constructed a 200 ft x 150 ft temporary marine structure to facilitate grouting and freezing operations to stabilize the ground beneath the Manhattan bulkhead in preparation for tunnel boring. The 150 ft x 50 ft Joseph D barge with a 184 ft crane on deck will be moored along the west face of the temporary marine structure. The 150 ft x 150 ft scow Angela will be moored on west side of the Joseph D barge. All barges require tug assistance for a movement and a minimum notice of 24 hours via VHF radio is required for any barge relocation. All moored barges display fixed white lights in accordance with the Inland Navigation Rules. Four seasonal white lighted buoys have been reset. Two (LLNR 37663, 37663.1) are upriver of the construction area, and two (LLNR 37663.2, 37663.3) are downriver. All four lighted buoys exhibit FL W 2.5s characteristics. From September 1 to September 30, Normandeau Associates, Inc. will be on site within the Safety Zone	
Main Channel - Hudson River/General/Marine Events/Swim	Marine Events	LNМ NY - EAST RIVER - HARLEM RIVER - HUDSON RIVER – Swim Mariners are advised that multiple swim events are scheduled from June 13, 2026, through October 13, 2026, navigating counterclockwise around Manhattan, NY. Approximately two to five participating swimmers will be assisted by a lead safety vessel in addition to one escort vessel and one escort kayak per every one to two swimmers. The swim events will start at either Pier A in Battery Park or Mill Rock, near East 90th St., Manhattan. They will proceed up the East River, through the Harlem River, and down the Hudson River, concluding back at the start position. Interested mariners may contact the Principal Swim Safety Officer on VHF channel 6. See list of dates and times below: Date Start Time Finish Time Start Location A. 06/13/2026 6:36 PM 3:06 AM Pier A B. 06/15/2026 2:00 AM 8:00 AM Mill Rock C. 06/16/2026 8:56 AM 5:26 PM Pier A D. 06/17/2026 9:51 AM 6:21 PM Pier A E. 07/11/2026 5:23 PM 1:53 AM Pier A F. 07/12/2026 6:21 PM 2:51 AM Pier A G. 07/14/2026 7:52 AM 4:22 PM Pier A H. 07/15/2026 8:45 AM 5:15 PM Pier A I. 07/16/2026 9:38 AM 6:08 PM Pier A J. 07/17/2026 10:32 AM 7:02 PM Pier A K. 08/01/2026 9:53 AM 6:23 PM Pier A L. 08/02/2026 10:37 AM 7:07 PM Pier A M. 08/05/2026 1:01 PM 9:31 PM Pier A N. 08/06/2026 1:55 PM 10:25 PM Pier A O. 08/07/2026 2:56 PM 11:26 PM Pier A P. 08/08/2026 4:02 PM 12:32 AM Pier A Q. 08/11/2026 6:46 AM 3:16 PM Pier A R. 08/12/2026 7:40 AM 4:10 PM Pier A S. 08/13/2026 8:31 AM 5:01 PM Pier A T. 08/14/2026 9:22 AM 5:52 PM Pier A U. 08/15/2026 10:13 AM 6:43 PM Pier A V. 08/16/2026 11:04 AM 7:34 PM Pier A W. 08/28/2026 8:02 AM 4:32 PM Pier A X. 08/29/2026 8:42 AM 5:12 PM Pier A Y. 08/30/2026 9:23 AM 5:53 PM Pier A Z. 08/31/2026 10:07 AM 6:37 PM Pier A AA. 09/01/2026 10:53 AM 7:23 PM Pier A BB. 09/02/2026 11:42 AM 8:12 PM Pier A CC. 09/09/2026 6:32 AM 3:02 PM Pier A DD. 09/13/2026 9:51 AM 6:21 PM Pier A EE. 09/14/2026 10:40 AM 7:10 PM Pier A FF. 09/15/2026 11:30 AM 8:00 PM Pier A GG. 09/25/2026 6:50 AM 3:20 PM Pier A HH. 09/26/2026 7:31 AM 4:01 PM Pier A II. 09/28/2026 8:55 AM 5:25 PM Pier A JJ. 09/29/2026 9:40 AM 6:10 PM Pier A KK. 09/30/2026 10:27 AM 6:57 PM Pier A LL. 10/01/2026 11:19 AM 7:49 PM Pier A MM. 10/08/2026 6:14 AM 2:44 PM Pier A NN. 10/09/2026 7:05 AM 3:35 PM Pier A OO. 10/10/2026 7:54 AM 4:24 PM Pier A PP. 10/11/2026 8:41 AM 5:11 PM Pier A QQ. 10/12/2026 9:27 AM 5:57 PM Pier A RR. 10/13/2026 10:14 AM 6:44 PM Pier A	

Hudson River Above Troy Lock

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Troy Dam - Hudson River Above Troy Lock/General/Marine Construction (Excluding Bridges)/Dredging	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Dredging From: 2026-09-15 To: 2027-03-14 Location: 42-45-10.584N/073-41-04.596W Mariners are advised that LAND Remediation, Inc. will conduct maintenance dredging in the Hudson River Federal Navigation Channel, Reach N04, on the north side of the Troy Federal Lock and Dam in Troy, NY, from September 28 through November 30, 2026. Work will take place Monday through Friday from 7:00 a.m. to 8:00 p.m. in the vicinity of 42°45'10.6"N, 73°41'04.6"W. Operations will include removal of shoal sediment along the eastern side of the river near the USACE Albany Field Office bulkhead and shoreline. A turbidity curtain, supported by temporary driven piles and anchors and marked with lights and spar buoys, will enclose the in-water work area and associated vessels. Equipment on scene will include one sectional excavator-mounted spud barge, three sectional material barges, the 26-foot tug Sunfish, and three work boats/skiffs. Vessel traffic will be able to pass the work site through a clearly marked approximately 45- to 50-foot-wide corridor north of the lock doors along the western lock wall. Mariners should use caution when transiting the area and may contact the contractor on VHF-FM channels 13 or 16, or by phone at 518-260-3064	Lat: 42° 45' 11" Lon: -073° 41' 05"

Huntington Harbor

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Huntington Harbor Channel Lighted Buoy 9	26565	LT EXT	PA

Hutchinson River

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION

Hutchinson River/General/Bridges/Repairs, Painting, Or Fender Replacement	Bridges	NYCDOT is currently conducting emergency repairs to the Hutchinson River Parkway Bridge, mile 0.9, across the Hutchinson River in Bronx NY. During work hours (11:00 p.m. to 5:00 a.m.), a barge will reduce the horizontal clearance beneath the bridge by 30 feet. The barge will be relocated outside the navigable channel outside of work hours. A safety boat will be operating in the vicinity of the bridge. The resident engineer or contractor will be equipped with a VHF-FM marine radio and will be monitoring Channel 13/16 during hours of operation. Mariners can also contact 929-687-2807 for construction details. This project is scheduled to be completed by October 5, 2026.	Lat: 40° 52' 08" Lon: -073° 49' 16"
Hutchinson River/General/Bridges/Repairs, Painting, Or Fender Replacement	Bridges	General/Bridges/Repairs, Painting, Or Fender Replacement From: 2026-09-04 To: 2026-10-31 Location: 40-52-08.310N/073-49-15.930W Bridge Name: Hutchinson River Pkwy Bridge Beginning September 11, 2026 to October 30, 2026 , NYCDOT will be repairing the fender system at the Hutchinson River Parkway Bridge across Hutchinson River at mile 0.9. NYCDOT will be utilizing barges for the fender repairs, they will be in the waterway from 6am to 2:30pm. For any questions or concerns mariners may contact Eric Lun at (646) 532-1943 or John Broderick at (631) 572-2636. Mariners are advice to transit with caution.	Lat: 40° 52' 08" Lon: -073° 49' 16"
Hutchinson River/General/Bridges	Bridges	Hutchinson River/General/Bridges From: 2026-09-17 To: 2026-10-31 Location: 40.86214, -73.81576 Bridge Name: Pelham Bay Parkway Bridge Beginning September 17, 2026 to October 30, 2026 , NYCDOT will be mooring barges from 2:30pm to 6 am at the Pelham Bay Parkway Bridge across Hutchinson River at mile 0.4. For any questions or concerns mariners may contact Eric Lun at (646) 532-1943 or John Broderick at (631) 572-2636. Mariners are advice to transit with caution.	Lat: 40° 51' 44" Lon: -073° 48' 57"

Isle Au Haut Bay

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
The Washers Buoy 2	3320	SINKING/HAZ NAV	FD
Isle Au Haut Light	3360	LT EXT	FD

Jericho Bay

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Sunken Egg Rock Buoy 1	2780	SINKING	FD
Long Ledge Daybeacon LL	2790	MISSING	FD
Roaring Bull Lighted Bell Buoy 2	3190	MISSING	FD

Jones Inlet

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Jones Inlet Lighted Buoy 16	30975	MISSING	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Jones Inlet/General/Bridges/Rehabilitation	Bridges	From April 15, 2026, to December 15, 2027, NYSDOT will be conducting structural rehabilitation to the Loop Parkway Bridge across Reynolds Channel at mile 8.2. Work hours are 7:00 a.m. to 4:00 p.m. Monday through Friday. During work hours, a 20-foot by 40-foot work barge will be deployed in the navigable channel. Mariners requiring full horizontal clearance under the bridge may contact the contractor on VHF-FM channels 13/16 or call (516) 351-9251. Mariners are advised to exercise caution when transiting this area.	Lat: 40° 35' 38" Lon: -073° 35' 14"
Jones Inlet/General/Bridges/Rehabilitation	Bridges	From April 15, 2026, to December 15, 2027, NYSDOT will be conducting structural rehabilitation to the Meadowbrook Parkway Bridge across False Channel at mile 0.7. Work hours are 7:00 a.m. to 4:00 p.m. Monday through Friday. During work hours, a 20-foot by 40-foot work barge will be deployed in the navigable channel. Mariners requiring full horizontal clearance under the bridge may contact the contractor on VHF-FM channels 13/16 or call (516) 351-9251. Mariners are advised to exercise caution when transiting this area.	Lat: 40° 37' 48" Lon: -073° 33' 45"
Jones Inlet/General/Bridges/Maintenance	Bridges	General/Bridges/Maintenance From: 2026-09-08 To: 2026-09-26 Location: 40-36-15.984N/073-34-12.360W Bridge Name: Loop State Pkwy Bridge From September 8-25, 2026, Monday-Friday, 9:00 a.m.-3:00 p.m., NYCDOT will be performing bridge washing on the following bridges: - Meadowbrook State Parkway Bridge over False Channel at mile 0.7 - Meadowbrook State Parkway Bridge over Fundy Channel at mile 2.7 - Meadowbrook State Parkway Bridge over Sloop Channel at mile 12.8 - Loop Parkway Bridge over Swift Creek at mile 11.9 - Loop Parkway Bridge over Long Creek at mile 0.7 - Wantagh State Parkway Bridge over Seamans Island Creek at mile 0.5 - Wantagh State Parkway Bridge over Goose Creek at mile 16.1 - Wantagh Parkway Bridge over Sloop Channel at mile 15.4 - Robert Moses Causeway over Fire Island Inlet at mile 4 A Snooper Truck with a safety boat in the water will be utilized. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or call 631-339-4810. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 36' 16" Lon: -073° 34' 12"
Approaches To New York Nantucket Shoals To Five Fathom Bank - Jones Inlet/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	NY- JONES BEACH-Update 5/15/2024 Shoaling has been identified in between Jones Beach Inlet Lighted Buoy 3 (LLNR 30920) and Jones Beach Inlet Lighted Buoy 6 (LLNR 30935). Mariners are urged to maintain a sharp lookout and transit the area with extreme caution, when navigating this area.	
Jones Inlet/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	NY-EAST ROCKAWAY INLET-SLOOP CHANNEL Shoaling has been identified in East Rockaway Inlet between buoys 3 and buoy 9. Mariners are urged to maintain a sharp lookout and transit the area with extreme caution, when navigating this area.	

Kickamuit River

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Mount Hope Bay - Kickamuit River/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2024-09-12 To: 2039-11-07 RI-NARRAGANSETT BAT (CHART 13221)-MOUNT HOPE BAY-KICKAMUIT RIVER Shoaling has been reported in the Kickamuit River in the vicinity of Kickamuit River Buoy 2. Mariners are advised to proceed with caution while transiting the area.	

Kill Van Kull

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Main Channel - Kill Van Kull/General/Marine Construction (Excluding Bridges)/Boring and Core Samples	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Boring and Core Samples From: 2026-0-01 T8o: 2026-10-31 Location: 40-38-37.428N/074-08-45.132W Amy Ruta of Parsons submitted a Local Notice to Mariners (LNM) Information Form for sediment core boring operations scheduled from August 1, 2026, to October 31, 2026, in Newark Bay and Kill Van Kull, New Jersey, near the Bayonne Bridge at coordinates 40°38'37.435"N, 74°8'45.144"W. The work will be conducted using barge-mounted sediment drilling equipment and samplers, operating five days per week from 7 am to 5 pm. Vessels involved can be contacted on VHF Channel 16, and passing arrangements require a 30-minute notice to move vessels located within the side slopes of the navigation channel, though no work will occur within the channel itself.	Lat: 40° 38' 37" Lon: -074° 08' 45"
Main Channel - Kill Van Kull/General/Marine Construction (Excluding Bridges)/Dredging	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Dredging From: 2024-10-02 To: 2029-01-29 Trevcon Construction Company, LLC will be conducting dredging operations and wharf construction in Arthur Kill, Elizabeth, NJ, in position 40-38-37N, 074-11-24W, from October 2, 2024, to January 29, 2029, Monday through Friday, between 6:00am to 3:00pm. Equipment on scene will be a crane and material barges. Mariners are urged to use extreme caution and transit the area at their slowest safe speed to create minimum wake after passing arrangements have been made.	

Larchmont Harbor East Entrance

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Long Island Sound Western Part - Larchmont Harbor East Entrance/General/LAA/RNA/Safety Zone	LAA/RNA	General/Marine Events/Fireworks From: 2026-06-26 To: 2026-07-04 Location: LARCHMONT, NY – LARCHMONT HARBOR – LONG ISLAND SOUND - FIREWORKS SAFETY ZONE Details: Mariners are advised that a safety zone will be enforced for a barge-based fireworks display, scheduled to be held on Larchmont Harbor, July 3, 2026, from 9:00 p.m. until 10:30 p.m. The fireworks barge will be in approximate position 40°55'25.47"N 73°44'32.23"W (WGS84) and the Safety Zone encompasses all waters within a 400-foot radius from the barge. Vessels may not enter, remain in, or transit through the Safety Zone during the enforcement period unless authorized by the Coast Guard Captain of the Port. Other Federal, State and local agencies may assist these personnel in the enforcement of the Safety Zone.	

Larchmont Harbor South Entrance

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Hicks Ledge Junction Buoy HL	25735	OFF STATION	FD

Lewis Bay

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Lewis Bay Approach Channel Buoy 22	14645	OFF STATION	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector Southeastern New England, Submerged Lands Act (SLA) - Lewis Bay/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-04-09 To: 2027-04-09 Location: 41-37.177N/070-11.305W An old block/sinker for the #6 buoy near the Hyannis Channel has been identified in position 41°37.177"N 70°17.305"W. The buoy block and sinker are submerged with the chain swinging freely with about a 15yd swing radius. Buoy is not marked. Mariners urged to use caution and maintain sharp lookout in area.	

Lighthouse Channel

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Portland Harbor - Lighthouse Channel/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-10-19 To: 2026-10-21 Location: 43-38-57.192N/070-15-12.888W AGM Marine Contractors submitted a Local Notice to Mariners information form for obstruction removal work in Portland Harbor, Portland, Maine. The work is scheduled for October 19 through October 20, 2026, with operations planned Monday through Tuesday from 0600 to 1800. The work location is listed at 43°38'57.21"N, 70°15'12.89"W. Equipment on scene will include the dredge Pronckai and supporting tugs. Vessels may contact the project team on VHF radio channel 66, and passing arrangements require vessels to call on channel 66 and provide 15 minutes' notice so equipment can move as needed to avoid impeding navigation.	Lat: 43° 38' 57" Lon: -070° 15' 13"

Little Bay

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Piscataqua River - Little Bay/General/Bridges/Removal	Bridges	Demolition activities have commenced to the General Sullivan Bridge across Little Bay, mile 0.1, between Newington and Dover NH and will continue through March 31, 2027. Work trestles have been constructed adjacent to the bridge from both banks, reducing the navigable channel to a width of 160 feet. A temporary work platform will be suspended from the bridge over the navigable channel on or about April 1, 2026. This work platform will not reduce the vertical clearance of the General Sullivan Bridge further than the clearance of the adjacent Spaulding Turnpike Bridge. Between April 1, 2026, and August 28, 2026, there will be short duration navigable channel closures to facilitate the removal of the bridge deck and superstructure over the navigable channel. The Coast Guard will announce these closures via Broadcast Notice to Mariners and updates to the Local Notice Mariners. Work hours for this project are 6:00 a.m. to 6:00 p.m. Monday through Friday. Mariners can contact on-scene project managers via VHF-FM channels 13/16 or by calling (207) 841-1902. Mariners are advised to exercise caution when transiting this area.	Lat: 43° 07' 05" Lon: -070° 49' 35"
Piscataqua River - Little Bay/General/Bridges/Rehabilitation	Bridges	General/Bridges/Rehabilitation From: 2026-06-05 To: 2026-11-20 Location: 43-07-05.196N/070-49-34.608W Bridge Name: General Sullivan Bridge Reed & Reed Inc. will be conducting bridge removal and temporary trestle construction operations in Little Bay, between Dover and Newington, NH, in position 43-07-04.56N, 070-49-34.59W. Construction will run from June 5, 2026, to November 20, 2026, Monday through Saturday, between 6:30am to 6:30 pm, local time. Equipment on scene will be (2) 250-ton cranes, (1) 90-ton Rough Terrian Crane, (2) forklifts, (1) dump truck, (1) excavator, (1) loader, (2) safety boats, (2) work boats, (2) 90' manlifts, monitoring VHF-FM CH 13 & 16. Vessels will be directed through a temporarily reduced 160-foot-wide navigational channel marked by tow temporary red and two temporary green buoys. Navigation through the work zone will be maintained during normal operations whenever safe to do so. The channel is expected to be restricted from June 5, 2026, through November 20, 2026, due to construction of the final Newington trestle span. In addition, short-term channel closures of up to 4 hours will be required during Span 5 superstructure removal, currently scheduled between August 3, 2026, and August 31, 2026. Outside of active closure periods, passage through the work zone will be accommodated subject to site conditions and construction activity.	Lat: 43° 07' 05" Lon: -070° 49' 35"
Long Island Sound Western Part - Little Bay/General/Bridges/Maintenance	Bridges	General/Bridges/Maintenance From: 2026-04-17 To: 2026-11-01 Location: 40-47-57.520N/073-47-36.920W Bridge Name: Throgs Neck Bridge NEW YORK – EAST RIVER – Barge Placement –Beginning April 21, 2026 through October 31, 2026, contractors will be performing bridge painting at the Throgs Neck Bridge across East River at mile point 15.8. To perform this work contractors will be utilizing a barge 110'x 32'. At no time will the bridge be in the navigational channel. Mariners with any questions can contact Project Manager Steven V. D'Orazio at (646) 235-7518 or via marine radio VHF-FM CH 13/16. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 47' 58" Lon: -073° 47' 37"

Little Narragansett Bay

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Approaches To New York Nantucket Shoals To Five Fathom Bank - Little Narragansett Bay/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	CT-STONINGTON-SANDY POINT-Update 5/29/2023 Shoaling has been reported in the vicinity of the western tip of Sandy Point Island, Stonington, CT in vicinity of little Narragansett Bay Entrance Lighted Buoy 5 (LLNR 20210) and Buoy 7 (LLNR 20215). Stonington Police Department's Marine Unit have observed significant narrowing of the channel, which may impact vessels transiting the area. Mariners should exercise extreme caution when navigating the channel.	

Little Peconic Bay

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Corey Creek Entrance Buoy 6	28530	MISSING/HAZ NAV	PA

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Shelter Island Sound South Channel - Little Peconic Bay/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2024-09-13 To: 2039-12-28 NY-LONG ISLAND SOUND (Eastern Part) (Chart 12354)-SOUTH SIDE-MATTITUCK INLET Shoaling has been reported in the Mattituck Inlet. Mariners are advised to proceed with caution while transiting the area.	

Little River

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Little River Ledge Buoy 2	1085	HAZ NAV/SINKING/TRLB	FD

Logan Airport Security Zone

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Logan Airport Security Zone Buoy 16	11033	OFF STATION	PA
Logan Airport Security Zone Buoy 13	11099	OFF STATION	PA
Logan Airport Security Zone Buoy 9	11119	OFF STATION	PA
Logan Airport Security Zone Buoy 10	11116	OFF STATION	PA

Long Island Sound Eastern Part

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE

Mount Sinai Jetty Hazard Daybeacon A	null	LT EXT	PA
Mount Sinai Jetty Hazard Daybeacon B	null	LT EXT	PA
Mount Sinai Harbor Buoy 10	26110	OFF STATION	PA

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Block Island Sound And Gardiners Bay - Long Island Sound Eastern Part/General/Bridges/Rehabilitation	Bridges	General/Bridges/Rehabilitation From: 2025-04-16 To: 2026-12-01 Location: 41.176728° N / 73.176352° W Bridge Name: Stratford Ave Bridge CONNECTICUT – PEQUONNOCK RIVER – Bridge Rehab – From April 21, 2025 through November 30, 2026 contractors will be utilizing a under bridge work platform truck to access the Stratford Avenue Bridge across Pequonnock River at mile 0.1. This truck is required for rehabilitation of the bridge. The work platform will not be in the navigational channel. Questions may be directed to Superintendent Wesley Sousa Santos at (860) 622-8410. Mariners are advised to exercise caution when transiting the area.	Lat: 41° 10' 36" Lon: -073° 10' 35"

Long Island Sound Western Part

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Throgs Neck Light	21520	LT EXT	FD

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Nissequogue River Lighted Buoy 4	26325	MISSING	PA
Lilco Basin Lighted Buoy 3	26385	MISSING	PA

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Long Island Sound Eastern Part - Long Island Sound Western Part/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-07-06 To: 2026-10-30 Location: 40-53-02.220N/073-43-50.340W The University of Connecticut Marine Sciences will conduct scientific research in New York Long Island Sound from July 2 to October 30, 2026. The project involves the deployment of four autonomous respiration chambers at four specific stations: Station 1 at 40°53'02.219" N, 73°43'50.339" W; Station 2 at 40°53'04.020" N, 73°43'45.959" W; Station 3 at 40°57'23.999" N, 73°34'59.400" W; and Station 4 at 40°57'24.420" N, 73°34'57.960" W. Each station is marked by surface buoys and a PVC marker with a yellow flag and radar-reflective tape, and the chambers are anchored to the seafloor. Stations 1 and 2 are approximately 900 feet northwest of the EXRX research buoy PATON 21436.000, while Stations 3 and 4 are about 230 feet west of the WLIS research buoy PATON 21336.000.	Lat: 40° 53' 02" Lon: -073° 43' 50"
Long Island Sound Eastern Part - Long Island Sound Western Part/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-07-06 To: 2026-10-30 Location: 40-53-04.020N/073-43-45.948W The University of Connecticut Marine Sciences will conduct scientific research in New York Long Island Sound from July 2 to October 30, 2026. The project involves the deployment of four autonomous respiration chambers at four specific stations: Station 1 at 40°53'02.219" N, 73°43'50.339" W; Station 2 at 40°53'04.020" N, 73°43'45.959" W; Station 3 at 40°57'23.999" N, 73°34'59.400" W; and Station 4 at 40°57'24.420" N, 73°34'57.960" W. Each station is marked by surface buoys and a PVC marker with a yellow flag and radar-reflective tape, and the chambers are anchored to the seafloor. Stations 1 and 2 are approximately 900 feet northwest of the EXRX research buoy PATON 21436.000, while Stations 3 and 4 are about 230 feet west of the WLIS research buoy PATON 21336.000.	Lat: 40° 53' 04" Lon: -073° 43' 46"
Long Island Sound Eastern Part - Long Island Sound Western Part/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-07-06 To: 2026-10-30 Location: 40-57-24.012N/073-34-59.412W The University of Connecticut Marine Sciences will conduct scientific research in New York Long Island Sound from July 2 to October 30, 2026. The project involves the deployment of four autonomous respiration chambers at four specific stations: Station 1 at 40°53'02.219" N, 73°43'50.339" W; Station 2 at 40°53'04.020" N, 73°43'45.959" W; Station 3 at 40°57'23.999" N, 73°34'59.400" W; and Station 4 at 40°57'24.420" N, 73°34'57.960" W. Each station is marked by surface buoys and a PVC marker with a yellow flag and radar-reflective tape, and the chambers are anchored to the seafloor. Stations 1 and 2 are approximately 900 feet northwest of the EXRX research buoy PATON 21436.000, while Stations 3 and 4 are about 230 feet west of the WLIS research buoy PATON 21336.000.	Lat: 40° 57' 24" Lon: -073° 34' 59"
Long Island Sound Eastern Part - Long Island Sound Western Part/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-07-06 To: 2026-10-30 Location: 40-57-24.408N/073-34-57.972W The University of Connecticut Marine Sciences will conduct scientific research in New York Long Island Sound from July 2 to October 30, 2026. The project involves the deployment of four autonomous respiration chambers at four specific stations: Station 1 at 40°53'02.219" N, 73°43'50.339" W; Station 2 at 40°53'04.020" N, 73°43'45.959" W; Station 3 at 40°57'23.999" N, 73°34'59.400" W; and Station 4 at 40°57'24.420" N, 73°34'57.960" W. Each station is marked by surface buoys and a PVC marker with a yellow flag and radar-reflective tape, and the chambers are anchored to the seafloor. Stations 1 and 2 are approximately 900 feet northwest of the EXRX research buoy PATON 21436.000, while Stations 3 and 4 are about 230 feet west of the WLIS research buoy PATON 21336.000.	Lat: 40° 57' 24" Lon: -073° 34' 58"

Lynn Harbor

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Nahant Harbor - Lynn Harbor/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2024-08-30 To: 2039-12-31	

Main Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Nobska Point Lighted Bell Buoy 26	15555	MISSING	FD
Nobska Point Light	15560	LT EXT	FD
Watch Hill Lighted Bell Buoy 2	20025	LT EXT	FD
Napatree Point Ledge Lighted Bell Buoy 6	20045	LT EXT	FD

Napatree Point Ledge Lighted Bell Buoy 6	20045	LT EXT	FD
Seaflower Reef Light	20155	LT EXT	FD
Gowanus Flats Lighted Buoy 32	34990	OFF STATION	FD

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Pier 9 Northeast Lighted Hazard Buoy	null	MISSING	PA
Ellis Island Security Zone Buoy ELSZ1	35006	MISSING	PA
Ellis Island Security Zone Buoy ELSZ10	35006.9	MISSING	PA
Ellis Island Security Zone Buoy ELSZ7	35006.6	MISSING	PA
Ellis Island Security Zone Buoy ELSZ2	35006.1	MISSING	PA
Liberty Island Security Zone Buoy LISZ2	37247.1	MISSING	PA
Liberty Island Security Zone Buoy LISZ3	37247.200000000004	MISSING	PA
Liberty Island Security Zone Buoy LISZ1	37247	OFF STA	PA

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Ambrose Channel - Main Channel/General/Bridges/Rehabilitation	Bridges	From April 1, 2026, through September 30, 2026, contractors will be installing main cable access platforms above the roadways of the Verrazzano Narrows Bridge, mile 0.0 across New York Harbor. The safety boat RHIANNON will be stationed below active work on this project during the hours of 7:00 a.m. and 3:30 p.m., as well from 10:00 p.m. to 6:00 a.m. The safety boat will move upon request by contacting the vessel directly on VHF-FM Channels 13 or 16. For more information regarding this project contact Eric Dovak at (347) 860-2399.	Lat: 40° 36' 22" Lon: -074° 02' 44"
Ambrose Channel - Main Channel/General/Bridges/Construction	Bridges	General/Bridges/Construction From June 1, 2026 – October 31, 2026, daily between 7:00 a.m. and 5:00 p.m., a biennial bridge inspection using an UBIU and traveler will be conducted on the Verrazano Bridge. In August, main cable inspection using rappelled ropes will also be conducted. Mariners requiring the UBIU or traveler to move to provide full vertical clearance can contact VTS New York, or contact the contractor via marine radio VHF-FM Ch. 13/16 or by calling 646-996-0634 or 646-634-3390. Mariners are advised to exercise caution when transiting the area. From: 2026-06-01 To: 2026-10-31 Location: 40-36-22.500N/074-02-43.600W Bridge Name: Verrazano Narrows Bridge	Lat: 40° 36' 22" Lon: -074° 02' 44"
Main Channel/General/Bridges	Bridges	Main Channel/General/Bridges From: 2026-09-15 To: 2026-12-31 Location: 40.678189, -73.9892 Bridge Name: Carroll St Bridge On September 21, 2026 to December 30, 2026 between 9:00 a.m. and 3:00 p.m. NYCDOT will be utilizing a barge and manlift will be performing bridge inspections at the Carroll Street Bridge over Gowanus Canal at mile 2. Mariners requiring full vertical and horizontal clearance can contact the contractor via marine radio VHF-FM Ch 13/16 or call Jan Pawluczuk at (646) 872-2967. Mariners are advised to exercise caution and reduce wake when transiting the area.	Lat: 40° 40' 41" Lon: -073° 59' 21"
Main Channel/General/Bridges	Bridges	Main Channel/General/Bridges From: 2026-09-15 To: 2026-12-31 Location: 40.679475, -73.988358 Bridge Name: Union St Bridge On September 21, 2026 to December 30, 2026 between 9:00 a.m. and 3:00 p.m. NYCDOT will be utilizing a barge and manlift will be performing bridge inspections at the Union Street Bridge over Gowanus Canal at mile 2.1. Mariners requiring full vertical and horizontal clearance can contact the contractor via marine radio VHF-FM Ch 13/16 or call Jan Pawluczuk at (646) 872-2967. Mariners are advised to exercise caution and reduce wake when transiting the area.	Lat: 40° 40' 46" Lon: -073° 59' 18"
Ambrose Channel - Main Channel/General/Marine Events/Regatta (Race)	Marine Events	General/Marine Events/Regatta (Race) From: 2026-04-29 To: 2026-10-18 New York, NY – UPPER BAY – Sailing Regatta Mariners are advised that a sailing regatta is scheduled to be held in the Upper Bay south of Governors Island, near Bay Ridge Flats, beginning April 29, 2026 through October 18, 2026, on every Wednesday and Thursday between the hours of 6:00 p.m. to 9:00 p.m., on Saturdays between the hours of 12:00 p.m. to 5:00 p.m., and on Sunday October 18, 2026 between the hours of 12:00 p.m. to 5:00 p.m. Approximately 13 sailboats, 24-26 feet in length, with multiple motorized support vessels will participate. Interested mariners may contact the Executive Director on marine band radio channel 71 VHF-FM. The race schedule between June 17, 2026 and July 11, 2026 maybe be impacted by other activities and marine events associated with Sail 4th 250 and International Naval Review 250.	
Ambrose Channel - Main Channel/General/Marine Events/Regatta (Race)	Marine Events	General/Marine Events/Regatta (Race) From: 2026-05-26 To: 2026-10-14 Location: NY/NJ – UPPER BAY – Sailing Regatta Mariners are advised that a weekly reoccurring regatta is scheduled on the Upper Bay of New York Harbor, every Tuesday from May 26, 2026, until October 13, 2026, from 6:30 pm until 8:00 pm. Approximately 15 sailing vessels will maneuver on various courses on the Upper Bay, between Ellis Island and Governors Island. Interested mariners may contact the race coordinator on VHF-FM Channel 68 during the scheduled regattas for further information.	
Ambrose Channel - Main Channel/General/Marine Events/Regatta (Race)	Marine Events	General/Marine Events/Regatta (Race) From: 2026-05-27 To: 2026-10-15 Location: NY/NJ – UPPER BAY – Sailing Regatta Details: Mariners are advised that a weekly reoccurring regatta is scheduled on the Upper Bay of New York Harbor, every Wednesday from May 27, 2026 until October 14, 2026, from 6:30 pm until 8:00 pm. Approximately 15 sailing vessels will maneuver on various courses on the Upper Bay, between Ellis Island and Governors Island. Interested mariners may contact the race coordinator on VHF-FM Channel 68 during the scheduled regattas for further information.	
Ambrose Channel - Main Channel/General/Marine Events/Regatta (Race)	Marine Events	General/Marine Events/Regatta (Race) From: 2026-05-28 To: 2026-10-17 Location: NY/NJ – UPPER BAY – Sailing Regatta Details: Mariners are advised that a weekly reoccurring regatta is scheduled on the Upper Bay of New York Harbor, every Thursday from May 28, 2026 until October 15, 2026, at 6:30 pm until 8:00 pm. Approximately 15 sailing vessels will maneuver on various courses on the Upper Bay, between Ellis Island and Governors Island. Interested mariners may contact the race coordinator on VHF-FM Channel 68 during the scheduled regattas for further information.	

Main Passage

Federal Discrepancies Corrected

NAME	LLNR	STATUS	AID TYPE	CORRECTION DATE
Crab Island Buoy 24	39450	WATCHING PROPERLY	FD	2026-09-22

Mamaroneck Harbor

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Mamaroneck Harbor Channel Lighted Buoy 10	25620	MSLD SIG	FD

Marblehead Channel

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector Boston, Submerged Land Act (SLA) - Marblehead Channel/General/Marine Events/Regatta (Race)	Marine Events	MA – MARBLEHEAD - MARBLEHEAD HARBOR – CORINTHIAN BANDIT SH RACE – REGATTA – The Corinthian Yacht Club is hosting the Corinthian Bandit SH Race on October 3rd, 2026, from 12:30 PM to 4:30 PM in and around the area between Cape Ann and Tinkers Gong. The event will consist of approximately 15 sailing vessels all ranging from 30’ to 40’ in length. The person responsible for on scene safety can be reached at 781-277-1151. For more information, please contact Dan Himes at 781-277-1151. Chart 13275	
Sector Boston, Submerged Land Act (SLA) - Marblehead Channel/General/Marine Events/Regatta (Race)	Marine Events	MA – MARBLEHEAD - MARBLEHEAD HARBOR – NEISA NE MATCH RACING CHAMPIONSHIPS – REGATTA – The Corinthian Yacht Club is hosting the New England Intercollegiate Sailing Association’s New England Match Racing Championships September 26, 2026 to September 27, 2026, from 9:30 AM to 5:30PM in and around the area of Marblehead Harbor. The event will consist of approximately 16 sailing vessels 23’ in length. The person responsible for on scene safety can be reached at 617-880-9807. For more information, please contact Dan Himes at 781-277-1151. Chart 13275	
Sector Boston, Submerged Land Act (SLA) - Marblehead Channel/General/Marine Events/Regatta (Race)	Marine Events	MA – MARBLEHEAD - MARBLEHEAD HARBOR – NEISA NE MATCH RACING CHAMPIONSHIPS – REGATTA – The Corinthian Yacht Club is hosting the New England Intercollegiate Sailing Association’s New England Match Racing Championships September 26, 2026 to September 27, 2026, from 9:30 AM to 5:30PM in and around the area of Marblehead Harbor. The event will consist of approximately 16 sailing vessels 23’ in length. The person responsible for on scene safety can be reached at 617-880-9807. For more information, please contact Dan Himes at 781-277-1151. Chart 13275	

Marblehead Harbor

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Marblehead Channel - Marblehead Harbor/General/Marine Events/Regatta (Race)	Marine Events	MA – MARBLEHEAD – FALL LASER ILCA SERIES – REGATTA – The Eastern Yacht Club is hosting the Fall Laser ILCA Series Regatta Series every Sunday from September 13, 2026, to November 22, 2026, from 1:00 PM to 3:00 PM in the vicinity of Marblehead Harbor. The event will consist of approximately 15 vessels, all of which are 14’ in length. The person responsible for on scene safety can be reached at 781-475-4120. For more information, please contact Jud Smith at 781-475-2140. Chart 13275	
Marblehead Channel - Marblehead Harbor/General/Marine Events/Regatta (Race)	Marine Events	MA – MARBLEHEAD – MARBLEHEAD HARBOR – POT LUCK REGATTA – REGATTA The Eastern Yacht Club is hosting the Pot Luck Regatta on September 27, 2026, from 12:00 PM – 4:00 PM, in and around the area of Marblehead Harbor. The event will consist of approximately 20 sailing vessels varying in length from 30’-50’. The person responsible for on-scene safety can be reached at 781-475-2140. For more information, please contact Jud Smith at 781-475-2140. Chart 13275	
Marblehead Channel - Marblehead Harbor/General/Marine Events/Regatta (Race)	Marine Events	MA – MARBLEHEAD – EASTERN YACHT CLUB – HALLOWEEN TEAM RACE – REGATTA - The Eastern Yacht Club is hosting the Halloween Team Race from October 24 to October 25, 2026, from 9:00 AM – 4:00 PM, in and around the area of Marblehead Harbor. The event will consist of approximately 15 sailing vessels approximately 23’ in length. The person responsible for on-scene safety can be reached at 617-416-3677. For more information, please contact Katie Roger at 617-416-3677. Chart 13275	
Marblehead Channel - Marblehead Harbor/General/Marine Events/Regatta (Race)	Marine Events	MA – MARBLEHEAD – EASTERN YC HIGH SCHOOL CHAMPIONSHIP – REGATTA – The Eastern Yacht Club is hosting the Nessa Keelboat High School Championships from October 10, 2026 from 9:00 AM to 4:00 PM, and October 11, 2026 from 9:00 AM to 12:00 PM, in and around the vicinity of Marblehead Harbor. The event will consist of approximately 12 sailing vessels 23’ in length. The person responsible for on-scene safety can be reached at 617-791-1585. For more information, please contact Alan McKinnon at 617-791-1585. Chart 13275	
Marblehead Channel - Marblehead Harbor/General/Marine Events/Regatta (Race)	Marine Events	MA – MARBLEHEAD – MARBLEHEAD HARBOR – EASTERN YACHT CLUB PUMPKIN PURSUIT RACE 1 – REGATTA The Eastern Yacht Club is hosting the Pumpkin Pursuit Race 1 on Sunday October 3rd, 2026, from 12:00 PM to 4:00 PM in and around the area of Marblehead Harbor. The event will consist of approximately 15 sailing vessels varying in length between 30’-50’ in length. The person responsible for on-scene safety can be reached at 617-678-4174. For more information, please contact Jack Cochrane at 617-678-4174. Chart 13275	
Marblehead Channel - Marblehead Harbor/General/Marine Events/Regatta (Race)	Marine Events	MA – MARBLEHEAD – MARBLEHEAD HARBOR – EASTERN YACHT CLUB PUMPKIN PURSUIT RACE 2 – REGATTA The Eastern Yacht Club is hosting the Pumpkin Pursuit Race 2 on Sunday October 17, 2026, from 12:00 PM to 4:00 PM in and around the area of Marblehead Harbor. The event will consist of approximately 15 sailing vessels varying in length between 30’-50’ in length. The person responsible for on-scene safety can be reached at 617-678-4174. For more information, please contact Jack Cochrane at 617-678-4174. Chart 13275	
Marblehead Channel - Marblehead Harbor/General/Marine Events/Regatta (Race)	Marine Events	MA – MARBLEHEAD – MARBLEHEAD HARBOR – EASTERN YACHT CLUB PUMPKIN PURSUIT RACE 3 – REGATTA The Eastern Yacht Club is hosting the Pumpkin Pursuit Race 3 on Saturday October 24, 2026, from 12:00 PM to 4:00 PM in and around the area of Marblehead Harbor. The event will consist of approximately 15 sailing vessels varying in length between 30’-50’ in length. The person responsible for on-scene safety can be reached at 617-678-4174. For more information, please contact Jack Cochrane at 617-678-4174. Chart 13275	
Marblehead Channel - Marblehead Harbor/General/Marine Events/Regatta (Race)	Marine Events	MA – MARBLEHEAD – SALEM SOUND – ETCHells NEW ENGLAND CHAMPIONSHIPS – REGATTA – The Eastern Yacht Club is hosting the Etchells New England Championships from 11:00 AM – 4:00 PM on October 8th – 11th, 2026, in and around the vicinity of Salem Sound and Marblehead Harbor. The event will consist of approximately 30 sailing vessels 33’ in length. The person responsible for on-scene safety can be reached at 781-475-4120. For more information, please contact Jud Smith at 781-475-2140. Chart 13275	
Marblehead Channel - Marblehead Harbor/General/Marine Events/Regatta (Race)	Marine Events	MA – MARBLEHEAD – MARBLEHEAD HARBOR – BYC TECH DINGHY FROSTBITING SERIES – REGATTA – The Boston Yacht Club is hosting the BYC MIT Tech Dinghy Frostbiting Series every Sunday, from November 08, 2026, to April 4, 2027, from 12:00 PM to 2:00 PM in Marblehead Harbor. The event will consist of approximately 15 sailing vessels varying all 14’ in length. The person responsible for on-scene safety can be reached at 617-548-9333. For more information, please contact Karen Tenenbaum at 617-548-9333. Chart 13275	

Mattituck Inlet

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Mattituck Inlet Lighted Buoy 2	21655	MISSING	FD
Mattituck Inlet Lighted Buoy 2A	21657	MISSING	FD
Mattituck Inlet Buoy 3	21660	MISSING	FD

Megansett Harbor

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Megansett Harbor Buoy 7	16500	Status Unreported	FD

Menemsha Creek

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Main Channel - Menemsha Creek/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2025-04-25 To: 2028-01-19 Shoaling has been reported in Menemsha Creek, Massachusetts. Water depths in the vicinity of Menemsha Creek Buoy 4 (LLNR 15965) have been reported as low as 3.5 feet across the channel.	
Main Channel - Menemsha Creek/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2026-03-26 To: 2026-09-22 Location: 41-21-15.624N/070-46-01.488W 41-21-15.084N/070-46-00.552W 41-21-13.176N/070-46-04.008W 41-21-06.228N/070-45-57.852W 41-21-03.564N/070-45-57.168W 41-20-52.260N/070-46-03.252W 41-20-34.224N/070-46-06.204W 41-20-34.368N/070-46-07.824W 41-20-52.584N/070-46-04.728W 41-21-03.564N/070-45-58.608W 41-21-05.508N/070-45-58.788W 41-21-13.284N/070-46-05.412W 41-21-15.624N/070-46-01.488W Shoaling has been reported in Menemsha Creek, Massachusetts.	

Middle Bay

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Jones Inlet - Middle Bay/General/Bridges/Rehabilitation	Bridges	From April 15, 2026, to December 15, 2027, NYSDOT will be conducting structural rehabilitation to the Meadowbrook Parkway Bridge across Fundy Channel at mile 2.7. Work hours are 7:00 a.m. to 4:00 p.m. Monday through Friday. During work hours, a 20-foot by 40-foot work barge will be deployed in the navigable channel. Mariners requiring full horizontal clearance under the bridge may contact the contractor on VHF-FM channels 13/16 or call (516) 351-9251. Mariners are advised to exercise caution when transiting this area.	Lat: 40° 36' 56" Lon: -073° 33' 16"
Jones Inlet - Middle Bay/General/Bridges/Maintenance	Bridges	General/Bridges/Maintenance From: 2026-09-08 To: 2026-09-26 Location: 40-36-56.000N/073-33-16.000W Bridge Name: Meadowbrook State Pkwy Bridge From September 8-25, 2026, Monday-Friday, 9:00 a.m.-3:00 p.m., NYCDOT will be performing bridge washing on the following bridges: - Meadowbrook State Parkway Bridge over False Channel at mile 0.7 - Meadowbrook State Parkway Bridge over Fundy Channel at mile 2.7 - Meadowbrook State Parkway Bridge over Sloop Channel at mile 12.8 - Loop Parkway Bridge over Swift Creek at mile 11.9 - Loop Parkway Bridge over Long Creek at mile 0.7 - Wantagh State Parkway Bridge over Seamans Island Creek at mile 0.5 - Wantagh State Parkway Bridge over Goose Creek at mile 16.1 - Wantagh Parkway Bridge over Sloop Channel at mile 15.4 - Robert Moses Causeway over Fire Island Inlet at mile 4 A Snooper Truck with a safety boat in the water will be utilized. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or call 631-339-4810. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 36' 56" Lon: -073° 33' 16"

Middle Channel

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
New Rochelle Harbor North Approach - Middle Channel/General/LAA/RNA/Temporary Regulated Navigation Zone	LAA/RNA	New Rochelle, NY - Long Island Sound – Safety Zone – Bridge Construction Mariners are advised that a safety zone will be enforced for construction work on the Glen Island Approach Bridge. The safety zone will be enforced from 7 a.m. until 5 p.m. each day starting on midnight December 2, 2024, through May 27, 2027. The safety zone will only be enforced during periods when construction operations at the Glen Island Bridge rehabilitation project are in progress. The Safety Zone encompasses all waters within a line beginning at 40° 53' 18.58"N 73° 46' 56.26"W; thence to 40° 53' 22.08"N 73° 46' 59.39"W; thence north along the shore to 40° 53' 23.8"N 73°46' 57.51"W; thence to 40° 53' 19.15"N 73° 46' 52.54"W and thence south along the shore back to the point of origin (WGS 84). You may not enter, remain in, or transit through the Safety Zone during the enforcement period unless authorized by the Coast Guard Captain of the Port. Other Federal, State and local agencies may assist these personnel in the enforcement of the Safety Zone. Mariners are urged to exercise caution while in the area. The anticipated dates for the windows of full channel closures: Date December 2, 2024, through December 20, 2024 February 3, 2025, through May 22, 2025 October 2, 2025 through 12 p.m. on May 22, 2026; from 7 a.m. on May 26, 2026, through 5 p.m. on May 29, 2026; and from 7 a.m. on June 22, 2026, through 5 p.m. on June 26, 2026.	

9/23/26, 12:04 PM

Maritime Safety Information Products | Navigation Center

New Rochelle Harbor North Approach - Middle Channel/General/LAA/RNA/COTP Restriction	LAA/RNA	General/LAA/RNA/COTP Restriction From: 2024-12-16 To: 2027-05-31 The Coast Guard is establishing a temporary safety zone for certain waters of Long Island Sound in the vicinity of the Glen Island Approach Bridge, New Rochelle, NY, for construction vessels and machinery involved in the rehabilitation project of the bridge. The safety zone is needed to protect personnel, vessels, and the marine environment from potential hazards associated with the bridge construction between December 2, 2024, through May 27, 2027. When enforced, this regulation prohibits persons and vessels from being in the safety zone unless authorized by the Captain of the Port New York or a designated representative. DATES: This rule is effective without notice from December 3, 2024, through 5 p.m. on May 27, 2027. For the purposes of enforcement, actual notice will be used from midnight on December 2, 2024, until December 3, 2024. This rule will only be enforced during periods when construction operations at the bridge are in progress. Comments and related material must be received by the Coast Guard on or before March 3, 2025. ADDRESSES: To view documents mentioned in this preamble as being available in the docket, go to https://www.regulations.gov, type USCG-2024-0956 in the search box and click "Search." Next, in the Document Type column, select "Supporting & Related Material." FOR FURTHER INFORMATION CONTACT: If you have questions about this rule, call or email Jeffrey Yunker, Waterways Management Division, U.S. Coast Guard Sector New York; telephone 718-354-4195, email Jeffrey.M.Yunker@uscg.mil. IV. Discussion of the Rule This rule establishes a safety zone from 7 a.m. until 5 p.m. each day starting on midnight December 2, 2024, through May 27, 2027. The safety zone will only be enforced during periods when construction operations at the Glen Island Bridge rehabilitation project are in progress. The anticipated dates for the windows of full channel closures are from 7 a.m. on December 2, 2024, through 5 p.m. on December 20, 2024; from 7 a.m. on February 3, 2025, through 5 p.m. on May 22, 2025; and from 7 a.m. on October 2, 2025, through 5 p.m. on April 29, 2026. The Coast Guard will make notice of the safety zone via the Local Notice to Mariners and issue a Broadcast Notice to Mariners via marine channel 16 (VHF-FM) as soon as practicable in advance of these scheduled closures. All these dates are tentative and subject to change due to weather, supply chain delays, or other unforeseen circumstances. This rule remains effective through May 27, 2027, in case the project is delayed due to unforeseen circumstances. The area regulated by the safety zone will encompass the waters around the Glen Island Bridge and will cover all navigable waters, from surface to bottom, within the area formed by connecting the following latitude and longitude points in the following order: 40°53'18.58" N 73°46'56.26" W; thence to 40°53'22.08" N 73°46'59.39" W; thence north along the shore to 40°53'23.8" N 73°46'57.51" W; thence to 40°53'19.15" N 73°46'52.54" W and thence south along the shore back to the point of origin. This area is intended for the vessels and machinery being used by personnel for the Glen Island Bridge rehabilitation project. The duration of the zone is intended to ensure the safety of personnel, vessels, and these navigable waters during the bridge construction. No vessel or person will be permitted to enter the safety zone without obtaining permission from the COTP or a designated representative. The Coast Guard will make notice of the safety zone via the Local Notice to Mariners and issue a Broadcast Notice to Mariners via marine channel 16 (VHF-FM) as soon as practicable in response to an emergency or hazardous condition.	
--	---------	--	--

Milton Harbor

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Long Island Sound Western Part - Milton Harbor/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2024-09-13 To: 2039-12-22 Location: 40.95282° N / 73.69544° W 40.95061° N / 73.69569° W 40.94138° N / 73.69947° W 40.94138° N / 73.69994° W 40.95266° N / 73.69569° W 40.95282° N / 73.69544° W NY-LONG ISLAND SOUND –MILTON HARBOR Severe Shoaling has been reported in Milton Harbor. Mariners are advised to proceed with caution while transiting the area.	

Missisquoi Bay

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Missisquoi Bay Lighted Research Buoy	39347	MISSING	FD

Temporary Changes

NAME	LLNR	STATUS	AID TYPE
EAST MISSISQUOI BAY LIGHTED RESEARCH BUOY	39348	ESTABLISHED	FD

MontaukHarbor

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Lake Montauk Lighted Buoy 13	19975	MISSING	PA

Moosabec Reach

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Gilchrist Rock Daybeacon 3	1280	DAYMK MISSING	FD
Moosabec Bar Buoy 12	1320	MISSING	FD

Moriches Bay

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Seatuck Cove Buoy 6	30360	OFF STA	PA

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Quantuck Canal - Moriches Bay/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2024-09-13 To: 2039-12-28 NY-SHINNECOCK BAY TO EAST ROCKAWAY INLET (Chart 12352)-MORICHES BAY-Update 2/8/22 Severe shoaling is present in Moriches Bay along the Long Island Intracoastal Waterway in the vicinity of Moriches Bay Buoys 21, 24, 26, 27, 28, and 29 extending the entire width of the channel at nearly all tide levels. The area from Buoys 24 to 29 is only navigable at the operator's risk. The most severe area of shoaling can be found between buoys 26 and 28 and is less than half the charted channel depth in some areas. Mariners should be aware that the Aids to Navigation in these areas are unreliable due to shoaling and mariners are strongly advised to seek alternate routes. Moriches Bay dredging has been completed. Shoaling has been reported in Moriches Bay along the Long Island Intercoastal Waterway in the vicinity of Moriches Bay Buoy 17, 18, 21, 26, 27, 28 and 29 extending the entire width of the channel and at any tide level. The most severe area of shoaling can be found between buoys 26 and 27 and is less than 3 ft. Shoaling is also reported in Moriches Inlet in the vicinity of Moriches Inlet East Cut Buoys 3E and 5E. Mariners should be aware that the Aids to Navigation in these areas have been deemed unreliable due to shoaling and mariners are advised to seek alternate routes. If transiting these areas, do so only at high tide and proceed slowly and with extreme caution. In addition, shoaling exists west of Moriches Bay Buoy 23 and East of Moriches Bay Buoy 27. Location: 40.78839° N / 72.72455° W 40.78722° N / 72.72421° W 40.77877° N / 72.76189° W 40.77994° N / 72.76236° W 40.78839° N / 72.72455° W	

Moriches Inlet

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Moriches Inlet East Cut Rock Lighted Hazard Buoy	29109	OFF STA	PA

Mount Hope Bay

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Brayton Point Channel Lighted Buoy 3	18910	HAZ NAV/SINKING/LT EXT	PA
Brayton Point Channel Front Range Light	18915	LT EXT	PA

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Tiverton Channel - Mount Hope Bay/General/Bridges/Repairs, Painting, Or Fender Replacement	Bridges	General/Bridges/Repairs, Painting, Or Fender Replacement From: 2026-05-18 To: 2027-02-01 Location: 41-42-33.510N/071-10-13.650W Bridge Name: I 195 Bridge From May 18, 2026 -- January 31, 2027, daily between 7:00 a.m. and 5:00 p.m., fender repairs using barges will be conducted on the Braga (I-195) Bridge across the Taunton River, mile 0.4, between Fall River and Somerset, MA. While material barges are on site, the width of the channel will be reduced from 400 feet to approximately 335 feet. Mariners requiring additional information regarding this project can contact the contractor on-site via marine radio VHF-FM Ch. 13/16 or by calling 978-844-4768. Mariners are advised to exercise caution when transiting this area.	Lat: 41° 42' 34" Lon: -071° 10' 14"
Tiverton Channel - Mount Hope Bay/General/Marine Construction (Excluding Bridges)/Dredging	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Dredging From: 2026-12-21 To: 2026-12-24 Location: 41-43-04.296N/071-09-57.312W Mariners are advised that Gladding-Hearn Shipbuilding Duclos Corporation will conduct maintenance dredging of the existing marine railway on the Taunton River in Somerset, MA, from December 21, 2026, through December 23, 2026. Operations are scheduled Monday through Friday from 7:00 a.m. to 5:00 p.m. Equipment on scene will include a long arm excavator. The work location is in approximate position 41°43'04.30"N, 071°09'57.32"W, charted on NOAA ENC US5FAVCB. Mariners should use caution when transiting the area and proceed at a safe speed.	Lat: 41° 43' 04" Lon: -071° 09' 57"

Muscle Ridge Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Garden Island Ledge Daybeacon 9	4615	STRUCT DMGD	FD

Muscongus Bay

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Moser Ledge Isolated Danger Buoy DM	4960	MISSING	FD

Mystic River

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
President Roads - Mystic River/General/Bridges/Rehabilitation	Bridges	From May 1, 2026, to September 30, 2026, the Interstate-93 Bridge across the Mystic River, mile 4.3, in Medford MA will be undergoing substructure repairs. Repairs will be conducted Monday through Friday 6:00 a.m. to 2:00 p.m., with possible night shifts from 9:00 p.m. to 5:00 a.m. A temporary work platform will be suspended from the bridge adjacent to each bridge pier with a work barge underneath in the waterway. These work platforms will reduce the horizontal clearance of the bridge to 57 feet. Mariners requiring additional information may contact contractors on-scene via VHF-FM channel 13/16 or call (603) 365-9857. Mariners are advised to exercise caution when transiting this area.	Lat: 42° 24' 53" Lon: -071° 06' 14"

Nahant Bay Approach

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Roaring Bull Daybeacon 2	10495	DAYMK DMGD	FD

Nahant Harbor

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
ARII Broad Sound Wave Research Lighted Buoy	10563	MISSING	PA

Nantasket Roads Southern Approach

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Nantasket Roads DRC Lighted Hazard Buoy A	11411	MISSING	PA

Narrows Bay.

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Narrows Bay/General/Bridges	Bridges	Narrows Bay/General/Bridges From: 2026-09-03 To: 2027-08-01 Location: 40.7382, -72.8687 Bridge Name: Smith Point Bridge Suffolk County has begun the construction of the Smith Point Bridge replacement across Narrow Bay at mile point 6.1, between Mastic Beach and Smith Point, NY. A 20' x 50' Poseidon sectional barge is onsite and will be moored on the southern end of the north trestle initially. 20' x 8' Aluminum Work Skiff is onsite, moored in the marina and assisting around site during the day. Barges will be in the waterway until August 1, 2027. All barges will be positioned outside of the navigational channel. Mariners with any questions or concerns may contact Nicholas laboni at (516) 551-7879. Mariners that can pass without a bridge opening may do so and are advised to exercise caution when transiting the area.	Lat: 40° 44' 18" Lon: -072° 52' 07"
Moriches Bay - Narrows Bay/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2026-03-06 To: 2027-03-06 Location: 40-44-25.404N/072-51-43.272W Shoaling has been reported of 3.9 feet at mean low low water in the vicinity of position 40-44-25.404N/072-51-43.272W. Mariners are advised to transit the area with extreme caution.	Lat: 40° 44' 25" Lon: -072° 51' 43"
Moriches Bay - Narrows Bay/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2026-03-06 To: 2027-03-06 Location: 40-44-28.644N/072-51-28.944W Shoaling has been reported of 3.5 feet at mean low low water in the vicinity of position 40-44-28.644N/072-51-28.944W. Mariners are advised to transit the area with extreme caution.	Lat: 40° 44' 29" Lon: -072° 51' 29"
Moriches Bay - Narrows Bay/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-09-16 To: 2027-03-15 Location: 40-43-52.356N/072-50-57.552W Mariners are advised that a chain and anchor from a previously deployed buoy mooring are partially submerged on the ocean floor at this location. Ground fishing and anchoring in this area are not recommended due to the potential risk of entanglement.	Lat: 40° 43' 52" Lon: -072° 50' 58"
Moriches Bay - Narrows Bay/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	NY-SHINNECOCK BAY-NARROWS BAY Shoaling has been identified in East Rockaway Inlet in the area between buoys Narrows Bay Lighted Buoy 6 and Narrows Bay Buoy 7. Mariners are urged to maintain a sharp lookout and transit the area with extreme caution.	

National Dock Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
National Dock Channel Buoy 3	37215	MISSING	FD

NAVAREA IV

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
NOAA Data Lighted Buoy 44005 (ODAS)	820	ADRIFT	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION

NAVAREA IV/General/Bridges/Maintenance	Bridges	General/Bridges/Maintenance From: 2026-09-08 To: 2026-09-26 Location: 40-37-48.155N/073-33-44.993W Bridge Name: Meadowbrook State Pkwy Bridge From September 8-25, 2026, Monday-Friday, 9:00 a.m.-3:00 p.m., NYCDOT will be performing bridge washing on the following bridges: - Meadowbrook State Parkway Bridge over False Channel at mile 0.7 - Meadowbrook State Parkway Bridge over Fundy Channel at mile 2.7 - Meadowbrook State Parkway Bridge over Sloop Channel at mile 12.8 - Loop Parkway Bridge over Swift Creek at mile 11.9 - Loop Parkway Bridge over Long Creek at mile 0.7 - Wantagh State Parkway Bridge over Seamans Island Creek at mile 0.5 - Wantagh State Parkway Bridge over Goose Creek at mile 16.1 - Wantagh Parkway Bridge over Sloop Channel at mile 15.4 - Robert Moses Causeway over Fire Island Inlet at mile 4 A Snooper Truck with a safety boat in the water will be utilized. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or call 631-339-4810. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 37' 48" Lon: -073° 33' 45"
NAVAREA IV/General/Bridges/Maintenance	Bridges	General/Bridges/Maintenance From: 2026-09-08 To: 2026-09-26 Location: 40-38-24.317N/073-30-25.632W Bridge Name: Wantagh State Pkwy Bridge From September 8-25, 2026, Monday-Friday, 9:00 a.m.-3:00 p.m., NYCDOT will be performing bridge washing on the following bridges: - Meadowbrook State Parkway Bridge over False Channel at mile 0.7 - Meadowbrook State Parkway Bridge over Fundy Channel at mile 2.7 - Meadowbrook State Parkway Bridge over Sloop Channel at mile 12.8 - Loop Parkway Bridge over Swift Creek at mile 11.9 - Loop Parkway Bridge over Long Creek at mile 0.7 - Wantagh State Parkway Bridge over Seamans Island Creek at mile 0.5 - Wantagh State Parkway Bridge over Goose Creek at mile 16.1 - Wantagh Parkway Bridge over Sloop Channel at mile 15.4 - Robert Moses Causeway over Fire Island Inlet at mile 4 A Snooper Truck with a safety boat in the water will be utilized. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or call 631-339-4810. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 38' 24" Lon: -073° 30' 26"
NAVAREA IV/General/Bridges/Inspection	Bridges	General/Bridges/Inspection From: 2026-08-06 To: 2027-01-01 Location: 40-45-24.950N/073-57-16.550W Bridge Name: Queensboro Bridge From August 6, 2026, to December 31, 2026, a traveler and safety boat will periodically be operating between 8:30 am to 6:30 pm daily at the Queensboro Bridge across the East River at mile 5.5, in New York to conduct a bridge inspection. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch 13/16 or by calling the project manager at 860-338-4607, or by contacting USCG Vessel Traffic Service New York at 718-354-4088. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 45' 25" Lon: -073° 57' 17"
NAVAREA IV/General/Bridges/Inspection	Bridges	General/Bridges From: 2026-08-24 To: 2026-12-01 Location: 40-38-47.681N/073-52-25.277W Bridge Name: Belt Pkwy Bridge From August 24, 2026, to November 30, 2026, between 9:00 am to 3:00 pm, a barge with manlift and tug boat #NY8360GY will be utilized to inspect the Belt Parkway Bridge across Hendrix Creek at mile 0.1, in Brooklyn, NY. Mariners requiring full horizontal clearance can contact the contractor via marine radio VHF-FM Ch 13/16 or by calling (917) 306-0152. Mariners are advised to exercise caution and reduce wake when transiting the area.	Lat: 40° 38' 48" Lon: -073° 52' 25"
NAVAREA IV/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-08-24 To: 2026-11-30 Location: 39-44-52.008N/072-25-06.708W The Wildlife Conservation Society submitted a Notice to Mariners regarding planned acoustic monitoring work near the Hudson Canyon. The project involves deploying four small, fully submerged acoustic recorders at four sites near the northern end of Hudson Canyon to detect vocalizing cetacean species and characterize the ambient underwater noise environment. The equipment consists of compact acoustic recording units suspended approximately two meters above the seafloor between an anchor and a small sub-surface float. The design has no surface expression and uses an acoustic release system intended to leave no equipment or mooring on the seafloor after recovery. The listed monitoring sites are located at approximately 39°44'52.02" N, 072°25'6.72" W; 39°37'26.33" N, 072°28'26.67" W; 39°36'47.57" N, 072°17'9.68" W; and 39°28'44.31" N, 072°32'56.1" W. Initial deployment is planned for August 26, 2026, with retrieval and redeployment anticipated in October or November. Work will occur during daylight hours, generally between 7:00 a.m. and 7:00 p.m. Operations will use a small research vessel, approximately 6 to 10 meters in length, along with acoustic receivers, anchors, rope, sub-surface buoys, and related deployment equipment. The recorders and floats will be placed approximately 80 meters below the surface, with no surface equipment, which is intended to avoid interference with vessel traffic. Marine radio channel 16 is listed for communications, and no disposal site is associated with the activity.	Lat: 39° 44' 52" Lon: -072° 25' 07"
NAVAREA IV/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-08-24 To: 2026-11-30 Location: 39-37-26.328N/072-28-26.652W The Wildlife Conservation Society submitted a Notice to Mariners regarding planned acoustic monitoring work near the Hudson Canyon. The project involves deploying four small, fully submerged acoustic recorders at four sites near the northern end of Hudson Canyon to detect vocalizing cetacean species and characterize the ambient underwater noise environment. The equipment consists of compact acoustic recording units suspended approximately two meters above the seafloor between an anchor and a small sub-surface float. The design has no surface expression and uses an acoustic release system intended to leave no equipment or mooring on the seafloor after recovery. The listed monitoring sites are located at approximately 39°44'52.02" N, 072°25'6.72" W; 39°37'26.33" N, 072°28'26.67" W; 39°36'47.57" N, 072°17'9.68" W; and 39°28'44.31" N, 072°32'56.1" W. Initial deployment is planned for August 26, 2026, with retrieval and redeployment anticipated in October or November. Work will occur during daylight hours, generally between 7:00 a.m. and 7:00 p.m. Operations will use a small research vessel, approximately 6 to 10 meters in length, along with acoustic receivers, anchors, rope, sub-surface buoys, and related deployment equipment. The recorders and floats will be placed approximately 80 meters below the surface, with no surface equipment, which is intended to avoid interference with vessel traffic. Marine radio channel 16 is listed for communications, and no disposal site is associated with the activity.	Lat: 39° 37' 26" Lon: -072° 28' 27"
NAVAREA IV/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-08-24 To: 2026-11-30 Location: 39-36-47.556N/072-17-09.672W The Wildlife Conservation Society submitted a Notice to Mariners regarding planned acoustic monitoring work near the Hudson Canyon. The project involves deploying four small, fully submerged acoustic recorders at four sites near the northern end of Hudson Canyon to detect vocalizing cetacean species and characterize the ambient underwater noise environment. The equipment consists of compact acoustic recording units suspended approximately two meters above the seafloor between an anchor and a small sub-surface float. The design has no surface expression and uses an acoustic release system intended to leave no equipment or mooring on the seafloor after recovery. The listed monitoring sites are located at approximately 39°44'52.02" N, 072°25'6.72" W; 39°37'26.33" N, 072°28'26.67" W; 39°36'47.57" N, 072°17'9.68" W; and 39°28'44.31" N, 072°32'56.1" W. Initial deployment is planned for August 26, 2026, with retrieval and redeployment anticipated in October or November. Work will occur during daylight hours, generally between 7:00 a.m. and 7:00 p.m. Operations will use a small research vessel, approximately 6 to 10 meters in length, along with acoustic receivers, anchors, rope, sub-surface buoys, and related deployment equipment. The recorders and floats will be placed approximately 80 meters below the surface, with no surface equipment, which is intended to avoid interference with vessel traffic. Marine radio channel 16 is listed for communications, and no disposal site is associated with the activity.	Lat: 39° 36' 48" Lon: -072° 17' 10"

NAVAREA IV/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-08-24 To: 2026-11-30 Location: 39-28-44.292N/072-32-56.076W The Wildlife Conservation Society submitted a Notice to Mariners regarding planned acoustic monitoring work near the Hudson Canyon. The project involves deploying four small, fully submerged acoustic recorders at four sites near the northern end of Hudson Canyon to detect vocalizing cetacean species and characterize the ambient underwater noise environment. The equipment consists of compact acoustic recording units suspended approximately two meters above the seafloor between an anchor and a small sub-surface float. The design has no surface expression and uses an acoustic release system intended to leave no equipment or mooring on the seafloor after recovery. The listed monitoring sites are located at approximately 39°44'52.02" N, 072°25'6.72" W; 39°37'26.33" N, 072°28'26.67" W; 39°36'47.57" N, 072°17'9.68" W; and 39°28'44.31" N, 072°32'56.1" W. Initial deployment is planned for August 26, 2026, with retrieval and redeployment anticipated in October or November. Work will occur during daylight hours, generally between 7:00 a.m. and 7:00 p.m. Operations will use a small research vessel, approximately 6 to 10 meters in length, along with acoustic receivers, anchors, rope, sub-surface buoys, and related deployment equipment. The recorders and floats will be placed approximately 80 meters below the surface, with no surface equipment, which is intended to avoid interference with vessel traffic. Marine radio channel 16 is listed for communications, and no disposal site is associated with the activity.	Lat: 39° 28' 44" Lon: -072° 32' 56"
NAVAREA IV/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-08-24 To: 2026-12-01 Location: 40-59-12.480N/071-30-30.960W Commencing August, 2026 and continuing through November, 2026, the U.S. Naval Research Laboratory will be placing moorings on the New Jersey coastal shelf and southeastward of Block Island Rhode Island. Moorings will be temporarily established on the seafloor and extend 3 feet off the bottom. Three moorings will also have a surface expression and be lighted. Mariners are requested to not disturb these U.S. Naval experiments and to avoid dragging in the area.	Lat: 40° 59' 12" Lon: -071° 30' 31"
NAVAREA IV/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-08-24 To: 2026-12-01 Location: 40-11-16.440N/071-09-25.920W Commencing August, 2026 and continuing through November, 2026, the U.S. Naval Research Laboratory will be placing moorings on the New Jersey coastal shelf and southeastward of Block Island Rhode Island. Moorings will be temporarily established on the seafloor and extend 3 feet off the bottom. Three moorings will also have a surface expression and be lighted. Mariners are requested to not disturb these U.S. Naval experiments and to avoid dragging in the area.	Lat: 40° 11' 16" Lon: -071° 09' 26"
NAVAREA IV/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-08-24 To: 2026-12-01 Location: 39-05-38.760N/073-31-39.000W Commencing August, 2026 and continuing through November, 2026, the U.S. Naval Research Laboratory will be placing moorings on the New Jersey coastal shelf and southeastward of Block Island Rhode Island. Moorings will be temporarily established on the seafloor and extend 3 feet off the bottom. Three moorings will also have a surface expression and be lighted. Mariners are requested to not disturb these U.S. Naval experiments and to avoid dragging in the area.	Lat: 39° 05' 39" Lon: -073° 31' 39"
NAVAREA IV/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-08-24 To: 2026-12-01 Location: 40-03-49.320N/071-32-33.720W Commencing August, 2026 and continuing through November, 2026, the U.S. Naval Research Laboratory will be placing moorings on the New Jersey coastal shelf and southeastward of Block Island Rhode Island. Moorings will be temporarily established on the seafloor and extend 3 feet off the bottom. Three moorings will also have a surface expression and be lighted. Mariners are requested to not disturb these U.S. Naval experiments and to avoid dragging in the area.	Lat: 40° 03' 49" Lon: -071° 32' 34"
NAVAREA IV/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-08-24 To: 2026-12-01 Location: 40-43-34.320N/071-23-36.600W Commencing August, 2026 and continuing through November, 2026, the U.S. Naval Research Laboratory will be placing moorings on the New Jersey coastal shelf and southeastward of Block Island Rhode Island. Moorings will be temporarily established on the seafloor and extend 3 feet off the bottom. Three moorings will also have a surface expression and be lighted. Mariners are requested to not disturb these U.S. Naval experiments and to avoid dragging in the area.	Lat: 40° 43' 34" Lon: -071° 23' 37"
NAVAREA IV/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-08-24 To: 2026-12-01 Location: 40-28-11.640N/071-16-50.520W Commencing August, 2026 and continuing through November, 2026, the U.S. Naval Research Laboratory will be placing moorings on the New Jersey coastal shelf and southeastward of Block Island Rhode Island. Moorings will be temporarily established on the seafloor and extend 3 feet off the bottom. Three moorings will also have a surface expression and be lighted. Mariners are requested to not disturb these U.S. Naval experiments and to avoid dragging in the area.	Lat: 40° 28' 12" Lon: -071° 16' 51"
NAVAREA IV/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-08-24 To: 2026-12-01 Location: 40-14-51.720N/071-10-59.880W Commencing August, 2026 and continuing through November, 2026, the U.S. Naval Research Laboratory will be placing moorings on the New Jersey coastal shelf and southeastward of Block Island Rhode Island. Moorings will be temporarily established on the seafloor and extend 3 feet off the bottom. Three moorings will also have a surface expression and be lighted. Mariners are requested to not disturb these U.S. Naval experiments and to avoid dragging in the area.	Lat: 40° 14' 52" Lon: -071° 10' 60"
NAVAREA IV/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-08-24 To: 2026-12-01 Location: 40-07-13.080N/071-07-48.000W Commencing August, 2026 and continuing through November, 2026, the U.S. Naval Research Laboratory will be placing moorings on the New Jersey coastal shelf and southeastward of Block Island Rhode Island. Moorings will be temporarily established on the seafloor and extend 3 feet off the bottom. Three moorings will also have a surface expression and be lighted. Mariners are requested to not disturb these U.S. Naval experiments and to avoid dragging in the area.	Lat: 40° 07' 13" Lon: -071° 07' 48"
NAVAREA IV/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-08-24 To: 2026-12-01 Location: 39-20-07.080N/073-57-44.640W Commencing August, 2026 and continuing through November, 2026, the U.S. Naval Research Laboratory will be placing moorings on the New Jersey coastal shelf and southeastward of Block Island Rhode Island. Moorings will be temporarily established on the seafloor and extend 3 feet off the bottom. Three moorings will also have a surface expression and be lighted. Mariners are requested to not disturb these U.S. Naval experiments and to avoid dragging in the area.	Lat: 39° 20' 07" Lon: -073° 57' 45"
NAVAREA IV/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-08-24 To: 2026-12-01 Location: 39-12-52.920N/073-44-40.920W Commencing August, 2026 and continuing through November, 2026, the U.S. Naval Research Laboratory will be placing moorings on the New Jersey coastal shelf and southeastward of Block Island Rhode Island. Moorings will be temporarily established on the seafloor and extend 3 feet off the bottom. Three moorings will also have a surface expression and be lighted. Mariners are requested to not disturb these U.S. Naval experiments and to avoid dragging in the area.	Lat: 39° 12' 53" Lon: -073° 44' 41"
NAVAREA IV/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-08-24 To: 2026-12-01 Location: 38-57-28.080N/073-16-56.280W Commencing August, 2026 and continuing through November, 2026, the U.S. Naval Research Laboratory will be placing moorings on the New Jersey coastal shelf and southeastward of Block Island Rhode Island. Moorings will be temporarily established on the seafloor and extend 3 feet off the bottom. Three moorings will also have a surface expression and be lighted. Mariners are requested to not disturb these U.S. Naval experiments and to avoid dragging in the area.	Lat: 38° 57' 28" Lon: -073° 16' 56"
NAVAREA IV/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-08-24 To: 2026-12-01 Location: 38-50-51.720N/073-05-04.920W Commencing August, 2026 and continuing through November, 2026, the U.S. Naval Research Laboratory will be placing moorings on the New Jersey coastal shelf and southeastward of Block Island Rhode Island. Moorings will be temporarily established on the seafloor and extend 3 feet off the bottom. Three moorings will also have a surface expression and be lighted. Mariners are requested to not disturb these U.S. Naval experiments and to avoid dragging in the area.	Lat: 38° 50' 52" Lon: -073° 05' 05"

NAVAREA IV/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-08-24 To: 2026-12-01 Location: 38-50-49.920N/072-56-42.000W Commencing August, 2026 and continuing through November, 2026, the U.S. Naval Research Laboratory will be placing moorings on the New Jersey coastal shelf and southeastward of Block Island Rhode Island. Moorings will be temporarily established on the seafloor and extend 3 feet off the bottom. Three moorings will also have a surface expression and be lighted. Mariners are requested to not disturb these U.S. Naval experiments and to avoid dragging in the area.	Lat: 38° 50' 50" Lon: -072° 56' 42"
NAVAREA IV/General/Hazards To Navigation/Hazards	Hazards To Navigation	General/Hazards To Navigation/Hazards From: 2026-07-31 To: 2027-03-31 Location: 41-35-29.724N/070-28-00.696W 41-35-29.688N/070-27-58.320W 41-35-26.340N/070-27-57.312W 41-35-26.340N/070-27-58.824W 41-35-29.724N/070-28-00.696W South Cape Oyster Co. will be conducting shellfish aquaculture operation in Ockway Bay, Mashpee, Massachusetts, located on the eastern side of the entrance from Popponesset Bay, west of Daniels Island. The work is associated with existing oyster farm operations and a request for Nationwide Permit 48 verification. The operation is listed as year-round, with floating gear deployed approximately April 1 through November 30 and lowered for overwintering from December 1 through March 31 and during storms. Site visits occur several times per week during the operating season and as needed in winter, generally during daytime hours. Equipment on scene includes a 21-foot Carolina Skiff work boat, floating vinyl-coated wire mesh cages, grow bags, bottom trays, yellow 16-inch marker balls, line, and approximately 56 helical screw anchors. The vessel may monitor VHF Channel 16 while underway. The form states that the aquaculture grant is outside navigable channels and mooring fields, in shallow water of approximately 2 feet at mean low water and 6 feet at mean high water. The site is marked year-round with six yellow aquaculture marker balls, and the applicant states that the fixed gear does not impede navigation. No vessel relocation is anticipated, and the work skiff will yield to transiting traffic.	
NAVAREA IV/General/Marine Construction (Excluding Bridges)/Survey Operations	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Survey Operations From: 2026-08-03 To: 2026-10-20 Location: 44-21-08.640N/067-22-59.880W Woods Hole Oceanographic Institution submitted a Local Notice to Mariners (LNM) Information Form to the U.S. Coast Guard First District for a project focused on harmful algal bloom surveillance in the Gulf of Maine. The operation will deploy sensors aboard a SeaTrac SP-48 uncrewed surface vehicle (USV) at the coordinates 44.3524° N, -67.3833° W. The project is scheduled to run continuously, 24 hours a day, seven days a week, from August 3rd to October 20th. The USV will operate in the designated area, and vessels are requested to provide two hours' notice for passing arrangements to avoid navigation interference.	Lat: 44° 21' 09" Lon: -067° 22' 60"
NAVAREA IV/General/Marine Construction (Excluding Bridges)/Dredging	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Dredging From: 2026-08-18 To: 2026-11-16 Location: 40-40-05.376N/074-00-02.916W Cashman Dredging and Marine Contracting Co., will be conducting work associated with the EPA Superfund Gowanus Canal Environmental Remediation Project in Brooklyn, New York. The operation involves transferring sediment and debris from smaller hopper barges to larger hopper barges for delivery to the Clean Earth Claremont Processing Facility in Jersey City, New Jersey, or directly loading material into trucks for over-the-road transport to an offsite disposal facility. The work is planned for the Gowanus Canal approximately 100 feet south of the 659 Smith Street property, across the channel from the New York City Department of Sanitation facility. Operations are scheduled to begin August 31, 2026, and continue through November 15, 2027, with work hours from 0700 to 1800, Monday through Friday. Equipment expected on scene includes one 40-by-140-foot excavator deck barge, one 37-by-150-foot material barge, one 30-by-60-foot hopper barge, and one 600-horsepower tugboat. Vessels may be contacted on VHF channels 13 and 16. The applicant states that passing arrangements can be made within approximately 30 minutes and that the barges will have a full-time tender available to move them on demand to avoid impeding navigation. The form identifies NOAA Chart US5NYCDG/12334 for the area and includes a site layout showing the temporary dock, containment boom, hopper barges, transloader, spill tarp, gangway, and water treatment system	Lat: 40° 40' 05" Lon: -074° 00' 03"
NAVAREA IV/General/Marine Construction (Excluding Bridges)/Survey Operations	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Survey Operations From: 2026-09-02 To: 2026-09-26 Aqua Survey, Inc. submitted a Local Notice to Mariners information form for planned sediment sampling operations in the Gowanus Canal, Brooklyn, NY, between the 4th and 11th Street Turning Basins. Work is scheduled for September 2 through September 25, 2026, Monday through Friday, from 0800 to 1600. The vessels expected on scene are R/V Schuykill, R/V Packanack, and R/V Jon II. Vessels may be contacted on VHF Channels 13 and 16. The project team indicated that vessels can move on demand and will not impede navigation. The listed point of contact is Lisa Pipolo of Aqua Survey, Inc., reachable at 908-788-8700 or pipolo@aquasurvey.com. Location: 40-40-14.052N/073-59-56.544W	Lat: 40° 40' 14" Lon: -073° 59' 57"
NAVAREA IV/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-09-21 To: 2026-10-31 H & L Contracting details emergency repairs to underwater diffusers at the Cedar Creek Wastewater Treatment Plant's ocean outfall in Wantagh, New York, located in the Atlantic Ocean. The project, led by Jeffery Hawkins, will run from July 16 to October 31, 2026, operating Monday through Friday from 6:00 AM to 5:00 PM. Work will be conducted from a dive vessel, tug Manhasset Bay, and marker buoys, with vessel communications managed via VHF channels 16 and 65. The operation involves installing location buoys along the 84-inch outfall pipeline, which extends approximately two miles offshore and branches into an east-west diffuser field, each leg measuring about 1,225 feet. Commercial divers will mark the pipeline alignment to facilitate inspection and construction. The four key coordinates of the diffuser field are: 40.567939°N, 73.454662°W; 40.562960°N, 73.452567°W; 40.566250°N, 73.438921°W; and 40.571250°N, 73.441111°W. Vessels can be moved with 15 minutes' notice to avoid impeding navigation.	
NAVAREA IV/General/Marine Construction (Excluding Bridges)/Dredging	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Dredging From: 2026-08-01 To: 2026-10-01 Curtin Maritime Corporation will begin maintenance dredging operations in the New York and New Jersey Channels—specifically the Seguine, Ward, and Outerbridge reaches—on or about August 1, 2026, with completion expected by October 1, 2026. The project, conducted under USACE contract W912DS25CA011, involves 24/7 dredging within existing federal navigation channels to maintain safe passage for maritime traffic. Dredged material will be transported offshore and placed as remediation material at the Historic Area Remediation Site (HARS) in the Atlantic Ocean. The operation will utilize one mechanical dredge (DB Avalon) and three split hull scows, supported by four towing vessels. All manned equipment will monitor VHF-FM Channels 13 and 16 for maritime safety. Mariners are advised to proceed with caution and coordinate passing arrangements. The project site plan, coordinates, and operational notes are provided, with specific restrictions on dredging activities in certain shoaled areas from October 1 to November 30. The survey and mapping data meet US Army Corps of Engineers standards and are referenced to the US State Plane Coordinate System (NAD 1983). For further information, Project Manager Robert Collaro is the point of contact.	
NAVAREA IV/General/Marine Construction (Excluding Bridges)/Boring and Core Samples	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Boring and Core Samples From: 2026-08-10 To: 2026-09-30 Location: 42-22-09.408N/071-03-54.864W 42-22-07.968N/071-03-53.676W 42-22-07.392N/071-03-55.260W 42-22-09.120N/071-03-57.204W 42-22-09.408N/071-03-54.864W MASSACHUSETTS – BOSTON INNER HARBOR – CHARLES RIVER – Boring Operations Mariners are advised that Skanska Civil Northeast/Koch JV (Skanska) will be conducting boring operations in the vicinity of the MBTA Draw One Bridge over the Charles River. Operations will commence on August 10, 2026, and continue through October 3rd, 2026. Work will be conducted between 7:00 a.m. and 4:00 p.m. daily for the duration of the project. On-scene equipment will consist of a 22' x 40' steel pontoon barge and one assist vessel. All boring operations will occur outside the navigational channel. For additional information, mariners may contact Skanska representative Mr. Edward Breed at (617) 981-0215. The on-scene support vessel will monitor VHF-FM Channels 13 and 16. Mariners are advised to exercise caution and proceed at a slow speed to minimize wake while transiting the area.	

NAVAREA IV/General/Marine Construction (Excluding Bridges)/Dredging	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Dredging From: 2026-09-20 To: 2026-11-01 Mariners are advised that the National Oceanic and Atmospheric Administration will conduct hydrographic survey operations offshore of the New York Traffic Separation Scheme from September 20, 2026, through October 31, 2026. Operations are scheduled to occur 24 hours per day within an area bounded by approximate positions 39.9584°N, 073.5035°W; 40.2864°N, 073.6958°W; 40.5565°N, 073.4719°W; and 40.4162°N, 072.9241°W. Applicable chart numbers include US3NY1AE and US3NY1AF. Survey operations will involve the use of a Moving Vessel Profiler, an underwater towfish deployed approximately 30 to 50 meters astern of the survey vessel. Mariners transiting the area are requested to exercise caution, maintain a safe passing distance, and avoid impeding survey operations. Vessels involved in the operation may be contacted on VHF-FM channels 16 and 13. For additional information, contact LT Abby Letts, National Oceanic and Atmospheric Administration, at 626-660-8744 or ops.ferdinand.hassler@noaa.gov.	
NAVAREA IV/General/Marine Events/Fireworks	Marine Events	General/Marine Events/Fireworks From: 2026-09-25 To: 2026-09-26 Location: 43-44-59.424N/070-07-29.964W 43-44-56.580N/070-07-20.388W 43-44-47.724N/070-07-28.560W 43-44-50.316N/070-07-35.580W 43-44-54.924N/070-07-38.064W 43-44-59.424N/070-07-29.964W ME – CASCO BAY – Chebeague Island – Fireworks Mariners are advised that the Chebeague Island Fireworks display is scheduled to be held offshore North of the ferry terminal on the North side of Chebeague Island in Casco Bay, ME. The fireworks display will be held on September 26, 2026 from 10:15 p.m. to 10:30 p.m. Mariners are advised to transit the area, 43.752722 N, 70.106389 W, with caution. For event information: (207) 242-9013.	
NAVAREA IV/General/Miscellaneous	Miscellaneous	General/Marine Construction (Excluding Bridges)/Survey Operations From: 2026-08-24 To: 2026-10-01 Location: 41-49-59.988N/070-15-00.000W Sedna Robotics plans to conduct small autonomous surface vessel testing and water-quality profiling in Cape Cod Bay, Massachusetts, from August 24 through September 30, 2026. The work will support the Massachusetts Lobstermen's Association and will involve dissolved oxygen, temperature, and salinity data collection near the approximate center point of 41°50'00"N, 70°15'00"W, on Chart 13246. Operations are scheduled to occur 24 hours a day, seven days a week. The vessel, named "Warden," is a 7-foot autonomous surface vessel with a yellow hull and "Uncrewed / Research Vessel" markings. It will transmit as "Uncrewed" on AIS and will display a flashing amber beacon at night. The vessel may remain stationary for sampling or move at approximately 2 knots between sampling locations during the day. It is not fishing gear and is not intended to interfere with traps, buoys, or lines. Mariners are advised not to approach closely, as the vessel may begin moving without warning. Sedna Robotics can be contacted at any time at 617-506-9177, which is also written on the vessel. If needed to avoid impeding navigation, the vessel can be repositioned within 30 minutes of a phone call to Sedna operations.	

Navesink River

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Shrewsbury River - Navesink River/General/Bridges/Maintenance	Bridges	General/Bridges/Maintenance From: 2026-04-17 To: 2026-11-24 Location: 40-19-30.072N/074-05-56.004W Garden State Parkway Structures (109.3SO, 109.3NO, 109.3NI) Southbound Outer and Northbound Outer and Inner Structures On April 20, 2026 through November 23, 2026, between 6:00 a.m. and 3:00p.m. Monday through Friday, temporary walkways attached to the GSP structures and a hydro-platform will be operated from the Garden State Pkwy Structures under the Swimming River, located 3 miles from the confluence of the Navesink River, in Tinton Falls, Monmouth County, New Jersey. Mariners requiring full vertical and horizontal clearances can contact the contractor via marine radio VHF-FM Ch. 13/16 or call (646) 267-5285 or (908) 421-9718. Mariners are requested to exercise caution when transiting the area.	Lat: 40° 19' 30" Lon: -074° 05' 56"
Shrewsbury River - Navesink River/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2024-09-13 To: 2039-12-21 Location: 40.38611° N / 73.97916° W 40.38543° N / 73.97826° W 40.38141° N / 73.98251° W 40.38052° N / 73.99044° W 40.38219° N / 73.99542° W 40.38186° N / 74.01186° W 40.37971° N / 74.01675° W 40.3665° N / 74.05477° W 40.36499° N / 74.05658° W 40.35643° N / 74.06363° W 40.35664° N / 74.06423° W 40.36625° N / 74.05638° W 40.37948° N / 74.02366° W 40.38026° N / 74.01688° W 40.38229° N / 74.01242° W 40.38291° N / 73.99401° W 40.38131° N / 73.98972° W 40.38229° N / 73.98293° W 40.38611° N / 73.97916° W NJ- NAVESINK RIVER Recent surveys have shown significant shoaling in the Navesink River. Shoaling exists across the entire reach beginning at the entrance to the Navesink River to Navesink River Buoy 24. Least depths of 2.3 feet to 5.8 feet extending into channel and throughout the waterway. Navigation of the area requires extreme caution due to the encroaching nature of the shoal.	
Shrewsbury River - Navesink River/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2026-04-02 To: 2027-08-15 THE COAST GUARD HAS RECIEVED REPORT OF A SHIFT IN SHOALING IN THE NAVESINK RIVER. SHOALING HAS BEEN REPORTED AS 1-2 FEET AT LOW TIDE BETWEEN NAVESINK RIVER BUOY 8 AND 14 PRESENTING HAZARDOUS CONDITIONS IN THE AREA . MARINERS ARE ADVISED TO USE CAUTION WHILE TRANSITING THE AREA.	

New Bedford Harbor Channel

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
New Bedford Channel - New Bedford Harbor Channel/General/Hazards To Navigation/Wrecks	Hazards To Navigation	An uncharted wreck has been identified during recent survey work with the following details: length: @13m, Width:@10m Height off seafloor:@4.9m Least Depth:@4.9m in position 41-38-37.41N, 070-55-08.07W	Lat: 41° 38' 35" Lon: -070° 55' 07"
New Bedford Channel - New Bedford Harbor Channel/General/Marine Construction (Excluding Bridges)/Dredging	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Dredging From: 2026-09-14 To: 2026-10-03 Location: 41-37-27.336N/070-54-52.092W Mariners are advised that DW White Construction Inc. will conduct marine construction and dredging operations in the Acushnet River, New Bedford, MA, from September 14, 2026, through October 2, 2026. Work will include driving support piles and installing a turbidity curtain in CAD Cell No. 3, as well as dredging at Shuster Wharf with scow transits from the Tug Channel to the Federal Channel and CAD Cell No. 3 for disposal. Operations are scheduled Monday through Friday, from 6:00 a.m. to 11:00 p.m. Equipment on scene will include the CATERPILLAR 390, push boats SHEELAGH M and ERIN ASHLEY, spud barges KS1502 and POSEIDON SECTIONAL, and barges LITTLE JEFF and 61B. Work at Shuster Wharf will be conducted without a silt curtain to avoid impeding navigation; work in CAD Cell No. 3 will occur inside a silt curtain. Mariners should use caution when transiting the area, operate at a safe speed, and contact vessels on VHF-FM channels 13, 16, or 71 to make passing arrangements. The project location is in approximate position 41°37'27.37"N, 070°54'52.10"W.	Lat: 41° 37' 27" Lon: -070° 54' 52"

New Bedford Southeast Approach

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
New Bedford Southeast Approach Bell Buoy 2SE	16960	OFF STATION	FD

New Brunswick Grand Manan Channel Northern Part

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector Northern New England, Submerged Lands Act (SLA) - New Brunswick Grand Manan Channel Northern Part/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-06-15 To: 2027-06-02 Location: 44-54-55.728N/066-59-04.344W Fuller Marine Services, Inc. submitted a Local Notice to Mariners (LNM) Information Form to the U.S. Coast Guard First District regarding the planned replacement of the Clark Ledge Daybeacon (LLNR 925) in the St. Croix River, Maine. The project involves replacing the aid in its entirety, with operations scheduled to begin on June 15, 2026, and continue until completion. Work will be conducted daily from 7:00 AM to 6:00 PM, utilizing the vessels Enzo Charles and Mary Louisa II. Vessels on-site will monitor VHF-FM Channels 16 and 13 for navigational safety and passing arrangements, with secondary contact available on Channel 09 or USCG working channel 22A. The crew will maintain a clear fairway for all traffic and will reposition within 30 minutes if additional channel breadth is required, subject to weather and safety conditions.	Lat: 44° 54' 56" Lon: -066° 59' 04"

New Haven Harbor

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Long Island Sound Eastern Part - New Haven Harbor/General/Marine Construction (Excluding Bridges)/Dredging	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Dredging From: 2026-09-17 To: 2027-03-31 Great Lakes Dredge and Dock Co. LLC will conduct improvement dredging for the New Haven Harbor Federal Navigation Project in New Haven Harbor, New Haven, CT, from October 2026 through March 2027. Work will occur 24 hours per day, 7 days per week, in the New Haven Harbor Main Ship Channel and Turning Basin, with dredged material placement at the Shellfish Habitat Disposal Area, Morris Cove Borrow Pit Disposal Area, West River Borrow Pit Disposal Area, and Long Island Sound Disposal Site. Equipment on scene will include Dredge 54, Dredge 58, Tug SMITH PRIVATEER, Tug SMITH PREDATOR, Tug LARRY J HEBERT, multiple scows, support vessels, and associated equipment. Mariners are requested to contact the dredges and support vessels on VHF-FM channels 13 or 16 to make passing arrangements. Mariners are urged to transit at their slowest safe speed to minimize wake and proceed with caution after passing arrangements have been made. For additional information, contact Johan VanBladel at 630-235-9612 or JVanBladel@glidd.com.	

New Inlet

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Georges Bank And Nantucket Shoals - New Inlet/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	MA-MARSHFIELD-NEW INLET Shoaling has been reported from the North River junction buoy towards the #2 buoy South River. This area is reported as approx. 3.0 feet during the low tide. Mariners should use caution while transiting the area, especially during astronomical low tides.	

New Jersey Pierhead

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
New Jersey Pierhead South Entrance Lighted Buoy 2	37015	MISSING	FD
New Jersey Pierhead South Channel Lighted Buoy P	37038	LT EXT	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Main Channel - New Jersey Pierhead/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2025-02-13 To: 2027-02-28 Claremont Terminal Channel Shoaling – The Harbor Safety, Operations and Navigation Committee of the Port of NY and NJ – Deep Draft Working Group: The need to immediately restrict the deep draft of vessels transiting Claremont Terminal Channel has come to our attention. Based on the latest available surveys conducted by the Army Corps of Engineers, November 4, 2024, shoaling has occurred in the channel. The shoaling has minimized the available depth of water to 15 feet near the centerline of the channel. Based on this data, vessels will be restricted to a draft of 13 feet, plus the rise in tide, with a maximum draft of 18 feet. On 11/04/2024, the shoal area was bound by the following approximate coordinates: 40° 41'11"N, 074° 04' 41"W; thence to 40° 41' 17"N, 074° 04' 33"W; thence to 40° 40' 14"N, 074° 03' 06"W; thence to 40° 40' 10"N, 074° 03' 13"W.	

New London Harbor

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Frank Ledge Buoy F	21840	OFF STATION/SINKING	FD
New London Harbor Buoy 16	21943	MISSING	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION

Long Island Sound Eastern Part - New London Harbor/General/Marine Construction (Excluding Bridges)/Dredging	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Dredging From: 2026-11-01To: 2030-06-30 Marine construction and dredging operations are scheduled to occur on or about November 1, 2026, through June 9, 2030, in New London Harbor on the Thames River adjacent to the General Dynamics Electric Boat Facility in Groton, CT, between Graving Dock #2 and Graving Dock #3. Operations will include wet berth pier construction, dredging, and associated marine support activities, with barges, dredging equipment, tugboats, survey vessels, and other support equipment operating in the area. A mooring may be established in New London Harbor Anchorage A and/or Anchorage B for staging barges. Mariners are advised to transit the area at the slowest safe speed, minimize wake, and proceed with caution. Project vessels will monitor VHF-FM Channels 16 and 13, with a designated working channel to be established. Passing arrangements should be coordinated via VHF radio, or in advance by telephone when necessary, and approximately 30 minutes may be required to clear the navigation area for vessel passage depending on operational and environmental conditions.	
---	---	--	--

Newark Bay

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Kill Van Kull - Newark Bay/General/Bridges/Construction	Bridges	Construction will commence on June 1, 2026, to replace NJ Turnpike Authority’s Newark Bay Bridge over Newark Bay at mile 3.8 between Newark and Bayonne NJ. From June 1, 2026, to April 1, 2027, contractors will be constructing a work trestle from the Bayonne shore of Newark Bay to the navigable channel. This work will not impede the navigable channel. Work hours will be 6:00 a.m. to 4:00 p.m. Monday through Friday. For construction details please contact Jed Fritz at 267-907-5932 or on-scene work vessels via marine radio VHF-FM 13/16. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 41' 43" Lon: -074° 07' 04"
Kill Van Kull - Newark Bay/General/Bridges/Inspection	Bridges	Kill Van Kull - Newark Bay/General/Bridges/Inspection From: 2026-07-13T00:00:00.000Z To: 2026-09-25T00:00:00.000Z Location: 40.69898, -74.11964 Bridge Name: Lehigh Valley Drawbridge Starting July 14th through September 25, 2026, between 6:00 a.m. and 4 p.m. Monday through Friday, barges and work boats will be positioned outside the navigable channel at or near CONRAIL’s Lehigh Valley Railroad Bridge over the Upper Newark Bay at milepost 4.3 between Newark and Bayonne, New Jersey to perform an inspection For bridge related matters contact (215) 495-2140 and secondary contact (856) 220-8948. Mariners are advised to exercise caution when transiting the area. Contractor will monitor VHF-FM marine radio channels 13/16 during hours of operation.	Lat: 40° 41' 56" Lon: -074° 07' 11"
Kill Van Kull - Newark Bay/General/Bridges/Construction	Bridges	Construction has commenced to replace NJ Turnpike Authority’s Newark Bay Bridge over Newark Bay at mile 3.8 between Newark and Bayonne NJ. From August 17, 2026, through November 30, 2027, contractors will be constructing a work trestle from the Newark shore of Newark Bay to the navigable channel. This work will not impede the navigable channel. Work hours will be 5:00 a.m. to 6:00 p.m. Monday through Saturday. For construction details please contact the project superintendent at 731-614-7153 or on-scene work vessels via marine radio VHF-FM 13/16. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 41' 43" Lon: -074° 07' 04"

Newport Harbor

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
East Passage - Newport Harbor/General/Marine Events/Regatta (Race)	Marine Events	RI – NARRAGANSETT BAY– JAMESTOWN YACHT CLUB FALL RACE SERIES – RACE/REGATTA Mariners are advised that the Jamestown Yacht Club Fall Race Series is scheduled to be held in the vicinity of Southern Narragansett Bay and Brenton Reef, RI. The event will take place multiple days (September 6, 13, 20, 27 and October 4, 2026) from 12:30 a.m. to 5:00 p.m. each day Expect up to 40 sailing vessels, 20-66 ft in length. Mariners are advised to transit the area with extreme caution. Mariners may contact the person in charge by phone at (401) 782-7271. or by Channel 72 VHF.	
East Passage - Newport Harbor/General/Marine Events/Regatta (Race)	Marine Events	RI – NARRAGANSETT BAY– ILYC SHIELDS CLASS WEDNESDAY NIGHT SERIES – RACE/REGATTA Mariners are advised that the 2026 ILYC Shields Class Wednesday Night Series is scheduled to be held in the vicinity of Newport Bridge, Narragansett Bay, RI. The event will take place on Wednesdays from May 13 through October 7, 2026, from 5:30 p.m. to 8:00 p.m. Expect up to 50 vessels, 30 ft in length. Mariners are advised to transit the area with extreme caution. Mariners may contact the person in charge by phone at (401) 486-5318.	
East Passage - Newport Harbor/General/Marine Events/Regatta (Race)	Marine Events	RI – NARRAGANSETT BAY– ILYC SHIELDS CLASS WEDNESDAY NIGHT SERIES – RACE/REGATTA Mariners are advised that the 2026 ILYC Shields Class Wednesday Night Series is scheduled to be held in the vicinity of Newport Bridge, Narragansett Bay, RI. The event will take place on Wednesdays from May 13 through October 7, 2026, from 5:30 p.m. to 8:00 p.m. Expect up to 50 vessels, 30 ft in length. Mariners are advised to transit the area with extreme caution. Mariners may contact the person in charge by phone at (401) 486-5318.	
East Passage - Newport Harbor/General/Marine Events/Regatta (Race)	Marine Events	RI – NARRAGANSETT BAY– MITCHELL REGATTA SPRING EDITION – RACE/REGATTA Mariners are advised that the Mitchell Regatta Spring Edition is scheduled to be held from west of Goat Island and south of Rose Island, RI to New Harbor, Block Island, RI. The event will take place on Saturday May 23, 2026, from 9:00 a.m. to 6:00 p.m. Expect up to 20 sailing vessels, 20-60 ft in length. Mariners are advised to transit the area with extreme caution. Mariners may contact the person in charge on VHF channel 72 or by phone at (401) 529-5699.	

North Channel

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
North Channel Light 24	33800	LT EXT	PA

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Beach Channel - North Channel/General/Bridges/Inspection	Bridges	General/Bridges/Inspection From: 2026-07-16 To: 2026-12-01 Location: 40-38-31.474N/073-50-04.254W Bridge Name: Cross Bay Blvd Bridge NEW YORK – JAMAICA BAY - Bridge Inspections – From July 28, 2026 to November 30, 2026, a barge will be performing underdeck bridge inspections at the Cross Bay Blvd Bridge across Jamaica Bay at mile 10.0. Mariners requiring full vertical and horizontal clearance can contact the contractor via marine radio VHF-FM Ch 13/16 or call Luis Monroe at (646) 460-3880 or Minas Lyrstis at (863) 326-3750. Mariners are advised to exercise caution and reduce wake when transiting the area.	Lat: 40° 38' 31" Lon: -073° 50' 04"
Beach Channel - North Channel/General/Bridges/Inspection	Bridges	General/Bridges/Inspection From: 2026-08-24 To: 2027-01-01 Location: 40-37-19.859N/073-53-47.479W Bridge Name: Belt Pkwy Bridge From August 24, 2026, to December 30, 2026, between 9:00 am to 3:00 pm, a barge with manlift and tug boat #NY8360GY will be utilized to inspect the Belt Parkway Bridge across Paerdegat Basin at mile 0.2, in Brooklyn, NY. Mariners requiring full horizontal clearance can contact the contractor via marine radio VHF-FM Ch 13/16 or by calling (917) 306-0152. Mariners are advised to exercise caution and reduce wake when transiting the area.	Lat: 40° 37' 20" Lon: -073° 53' 47"

North Channel Saybrook To New Haven

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Chimney Corner Reef Buoy 20	21600	OFF STATION/SINKING	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Long Island Sound Eastern Part - North Channel Saybrook To New Haven/General/Marine Construction (Excluding Bridges)/Dredging	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Dredging From: 2026-10-01 To: 2026-12-31 Location: 41-15-52.668N/072-45-57.276W Mariners are advised that, in compliance with Department of the Army Permit No. NAE-2021-03025, Tilcon Connecticut, Inc. plans to conduct maintenance dredging at 1 Forest Road, Branford, Connecticut, within Long Island Sound. The work is expected to commence and be completed in October 2026, within the regulatory dredging window of October 1 through December 31. Operations will involve mechanical maintenance dredging of approximately 65,600 cubic yards of material over an area of approximately 21 acres. Dredging will be conducted to a depth of minus 15.5 feet mean low water, with 1 foot of allowable overdepth, in the Barge Basin, and to a depth of minus 17 feet mean low water, with 1 foot of allowable overdepth, in the Access Channel. Dredged material will be disposed of at the Central Long Island Sound Disposal Site. The approximate central coordinates of the work are 41.264630°N, 72.765910°W. The activity is not located in the vicinity of a federal navigation channel, and no temporary buoys, lights, ranges, or markers are proposed to be established, moved, or discontinued in association with the project. Mariners transiting the area are requested to exercise caution and avoid interfering with dredging operations. For questions or additional information, contact William Heiple at wheiple@tritonenvironmental.com or 203-631-7563.	Lat: 41° 15' 53" Lon: -072° 45' 57"

North Side

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Great South Bay - North Side/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2024-09-13 To: 2039-11-12 NY-SAYVILLE-BROWNS CREEK Mariners be advised, dangerous shoaling conditions exist east of Browns Creek and vicinity which cause dangerous conditions when transiting the channel. Mariners should exercise extreme caution when navigating the channel.	

Norwalk Channel

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Norwalk East Approach - Norwalk Channel/General/Bridges/Construction	Bridges	General/Bridges/Construction From: 2026-04-29 To: 2031-01-01 Location: 41-06-01.548N/073-24-55.512W Bridge Name: Walk Bridge CONNECTICUT – NORWALK RIVER - General Construction – Connecticut Department of Transportation will continue work of the new Walk Bridge over the Norwalk River at mile 0.1 beginning May 1, 2026 through December 31, 2030. The contractor will utilize work boats & barges in one channel (either East or West) at a time leaving the unoccupied side available for mariners to transit with assistance of Norwalk Marine Police. Message signs will be installed along the North Side or South Side of Walk Bridge to direct marine traffic accordingly to the open channel. Contractors will be transiting barges to and from Manresa Island frequently throughout the project. Mariners are advised to exercise caution and reduce wake when transiting the area as barges may move between the channels at times throughout the day. Mariners with questions or concerns can contact the contractor via marine radio VHF-FM Ch 13/16 or call Matthew Damore (978)-621-7937 or Jason Rourke (860) 250-1020.	Lat: 41° 06' 02" Lon: -073° 24' 56"
Norwalk East Approach - Norwalk Channel/General/Bridges/Closure (Scheduled Or Emergency)	Bridges	The Coast Guard has issued a temporary deviation from the regulation governing the operation of the Walk Bridge across the Norwalk River at mile 0.1. Under this temporary deviation the Walk Bridge may remain closed to mariners during the following time frames: 10:00 pm Friday, September 11, 2026, until 6:00 am Monday, September 14, 2026 10:00 pm Friday, September 18, 2026, until 6:00 am Monday, September 21, 2026 10:00 pm Friday, September 25, 2026, until 6:00 am Monday, September 28, 2026 Back-up Dates: 10:00 pm Friday, October 2, 2026, until 6:00 am Monday, October 5, 2026 10:00 pm Friday, October 9, 2026, until 6:00 am Monday, October 12, 2026 10:00 pm Friday, October 16, 2026, until 6:00 am Monday, October 19, 2026 Back-up Dates: 10:00 pm Friday, October 23, 2026, until 6:00 am Monday, October 26, 2026 & 10:00 pm Friday, October 30, 2026, until 6:00 am Monday, November 2, 2026 Vessels able to pass under the bridge in the closed position will be allowed to do so. Questions may be directed to Joe Phinney at (508) 726-5474. Mariners are advised to exercise caution when transiting the area.	Lat: 41° 06' 02" Lon: -073° 24' 56"

Owls Head Bay.

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Emery Island Daybeacon 1	4680	STRUCT DEST	FD

Oyster Bay.

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Oyster Bay Lighted Buoy 5	26885	BUOY DMGD	FD

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Oyster Bay Harbor Channel Junction Lighted Buoy B	26895	LT EXT	PA
Oyster Bay Harbor Alternate Channel Buoy 4A	27045	BUOY DMGD	PA
Oyster Bay Harbor Inner Channel Lighted Buoy 4B	27000	OFF STATION	PA

Passaic River

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Hackensack River - Passaic River/General/Bridges/Rehabilitation	Bridges	General/Bridges/Rehabilitation From: 2025-05-01 To: 2027-12-31 Location: 40.742075° N / 74.12271111° W Bridge Name: NJ Tpke Bridges Rehabilitation at the New Jersey Turnpike (Laderman) Bridge across Passaic River at mile 2.7 will commence on May 1, 2025. A safe span will be installed under the bridge across the entire span which will reduce the vertical clearance by approximate 3ft. Please contact Frank Duba of Ferreira Construction at 908-331-4630 or via marine radio VHF-FM CH 13/16 for bridge construction. This project will be completed by December 31, 2027. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 44' 31" Lon: -074° 07' 22"
Hackensack River - Passaic River/General/Bridges/Maintenance	Bridges	General/Bridges/Maintenance From: 2026-03-02 To: 2026-11-27 Location: 40-43-56.590N/074-07-03.850W Bridge Name: Route 1 and 9 -Lincoln Hwy Bridge Repairs to the Route 1 and 9 Lincoln Highway Bridge across the Passaic River at mile 1.8 will commence on March 2, 2026, through November 27, 2026. Hours of operation are from 7 a.m. to 3:30 p.m. EST Monday through Friday. A barge may perform work on the bridge piers from within the navigable channel adjacent to the fender. However, at no time will the work area constitute more than 50% of the channel width. Should a vessel need to transit an area of the channel where work is occurring the barge will be moved out of the channel with proper notification (four hours). Channels 13/16 will be monitored on VHF-FM radios. Mariners requiring full vertical clearance and can contact Sean Milachouski – Project Manager 201-675-1553 or Conor Teesdale – Director of Operations 609-694-5938. This project will be completed by November 27, 2026. Mariners are advised to use caution and reduce wake when transiting the area.	Lat: 40° 43' 57" Lon: -074° 07' 04"
Hackensack River - Passaic River/General/Bridges/Modification	Bridges	General/Bridges From: 2026-05-29 To: 2028-11-08 Location: 40-44-09.528N/074-09-41.148W Bridge Name: Amtrak Dock Bridges From May 29, 2026 – November 8, 2028 Monday-Friday, between 7:00 a.m. and 3:30 p.m., the rehabilitation and decommissioning work will be performed on the Dock Bridges across the Passaic River at mile 5.0 between Newark and Harrison, NJ. Vertical clearance will not be reduced. The bridge remains in the closed position at 24 feet above Mean High Water. At no time will the navigational channel width be reduced from 120 linear feet. Mariners can contact the VTS for scheduled barge placements and mooring arrangements before planning to transit under the bridge via marine radio VHF-FM Ch. 13/16 or by calling the resident engineer at (917) 656-6820. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 44' 10" Lon: -074° 09' 41"
Hackensack River - Passaic River/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2026-05-26 To: 2031-04-30 Shoaling has been reported, 5 to 10 ft water depths (MLLW), within the area of the old center pier fender system of the Point-No-Point Bridge (mile 2.6) over the Passaic River, within the area bound by the following approx. coordinates: 40°44'29.34"N, 074°7'13.42"W 40°44'29.24"N, 074°7'13.92"W 40°44'29.93"N, 074°7'15.95"W 40°44'30.32"N, 074°7'15.66"W 40°44'29.59"N, 074°7'13.65"W.	

Patchogue Bay

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Sandspit Buoy 1	29766	OFF STATION	PA

Pawcatuck River

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Pawcatuck River Channel Daybeacon 22	20365	STRUCT MISSING	PA
Pawcatuck River Channel Daybeacon 22	20365	STRUCT MISSING	PA

Phinneys Harbor

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Phinneys Harbor Light 7	16670	DAYMK MISSING	FD

Plum Island Sound

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Plum Island Sound Entrance Buoy 8A	9328	SINKING	FD
Bass Rock Daybeacon BR	9340	DAYMK MISSING	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Portsmouth To Cape Ann - Plum Island Sound/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	Shoaling exists in Plum Island Sound between Plum Island Sound Entrance buoy 4 (LLNR 9310) and Plum Island Sound Entrance buoy 6 (LLNR 9320), aids are not properly marking best water. Mariners are advised to use caution while navigating this area. All of Plum Island is particularly susceptible to shoaling, the area between 4 and 6 being the worst at the mouth of the channel. Last year the unit partnered with the harbor Master moving the aids to mark the best water. Even though the aids are in the best possible locations that water is still shallow at low tide and mariners should use caution while navigating in this area	
Portsmouth To Cape Ann - Plum Island Sound/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	Newburyport Harbor and Plum Island Sound – Plum Island Sound Entrance has experienced an increase in shoaling between Plum Island Sound Entrance Buoy 6 and 8. The shoaling was observed in approx. position 42-41.365N /070-45.169W and extends 100 yards west following the channel. Mariners are advised that at MLLW depths of 3’ could be seen. Mariners without local knowledge are advised to transit with extreme caution and monitor tidal stations prior to transiting.	

Sector Boston, Submerged Land Act (SLA) - Plum Island Sound/General/Marine Events/Regatta (Race)	Marine Events	MA – IPSWICH BAY – IPSWICH RIVER – LABOR IN VAIN CHALLENGE, IPSWICH ILLUMINATION FESTIVAL PADDLE – PADDLE RACE – The Town of Ipswich MA is hosting the 2026 Ipswich illuminations Festival and the Labor in Vain Challenge Paddle Race on October 18, 2026, from 3:00 PM to 6:00 PM from the Ipswich Town Wharf to Pavilion Beach on the Ipswich River. The event will consist of a paddle race with approximately 20 kayaks, canoes and Stand Up Paddle Boards ranging from 5’-14’ feet in length. The person responsible for on scene safety can be reached at 978-356-4343. For more information, please contact LT Jon Hubbard at 978-356-4343.	
--	---------------	---	--

Plymouth Bay

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
ARII Plymouth Bay Wave Research Lighted Buoy	12550	MISSING	PA

Plymouth Harbor

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Plymouth Beach Jetty Daybeacon	12935	MISSING	FD

Pocasset Harbor

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Pocasset Harbor Buoy 8	16640	OFF STATION	FD

Point Judith Harbor Of Refuge

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Point Judith Harbor of Refuge East Entrance Light 3	19490	STRUCT DEST/STRUCT MISSING	FD
Point Judith Harbor of Refuge East Entrance Lighted Buoy 3	19491	LT EXT/OFF STATION	FD
Point Judith Harbor of Refuge East Entrance Lighted Buoy 5	19492	LT EXT	FD
Point Judith Harbor of Refuge West Entrance Lighted Buoy 2	19501	STRUCT DEST/STRUCT MISSING	FD
Point Judith Harbor of Refuge West Entrance Light 3	19505	DAYMK DMGD	FD

Point Judith Pond

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Point Judith Harbor Of Refuge - Point Judith Pond/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2024-09-12 To: 2039-10-11 RI-BLOCK ISLAND SOUND AND APPROACHES (CHART 13205)-POINT JUDITH POND Shoaling has been observed within the channel to a least depth of 4.0 feet MLW in approximate position 41 22'48"N, 071 33'55"W between Point Judith Pond Channel Buoy 2 (LLNR 19555) and Point Judith Pond Channel Buoy 4 (LLNR 19560). Shoal is encroaching from the East side of the channel and protruding west. Shoaling has also been identified in several other areas north of buoy 2, below charted depth, extending into the upper pond. Mariners without local knowledge are advised to transit with extreme caution, paying particular attention to tidal range. Mariners are urged to use caution while transiting the area.	

Port Chester Harbor

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Port Chester Light 4	25545	STRUCT DMGD	FD

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Tide Mill Yacht Basin Channel Buoy 1	25556.100000000002	HAZ NAV/SINKING	PA

Port Jefferson Harbor

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Port Jefferson Harbor Buoy 4	26165	MISSING/TRUB	FD

Port Jersey Channel

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Port Jersey Channel Range Rear Light	null	LT IMCH	PA

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Main Channel - Port Jersey Channel/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-01-29 To: 2027-03-01 Location: 40-00-08.892N/074-04-30.288W Trevcon Construction Company, LLC. Will be conducting installation of Steel Pile Piles & Steel Beams / Structural Concrete Work / Concrete Pile Repair Work & Underdeck Concrete Repairs at the Port Liberty Container Terminal, in position 40-40-8.900N, 074-4-30.313W, from March 1, 2026, to February 28, 2027, between 5:00am to 7:00pm. Equipment on scene will be Two Barge (180' x 60'), Two Barges (140' x 50'), One Barge (90' x 30'), All moving of vessels to occur by tugboat; vessels will be moved at all times of day and night.	Lat: 40° 39' 55" Lon: -074° 04' 04"

Port Newark Pierhead Channel

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Newark Bay - Port Newark Pierhead Channel/General/Marine Construction (Excluding Bridges)/Dredging	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Dredging From: 2026-08-04 To: 2026-10-31 Location: 40-40-50.808N/074-08-32.172W Jay Cashman, Inc. submitted a Local Notice to Mariners information form for maintenance dredging work at the Port Newark and Elizabeth Port Authority Marine Terminal in New Jersey. The work will support NY and NJ marine terminal maintenance dredging under Port Authority work orders and is scheduled to occur from August 3, 2026, through October 31, 2026. Operations are planned for Berths 8, 23, 25, 68, 70, 72, 96, and 98, near position 40°40'50.81"N, 74°8'32.18"W. Work hours are expected to be 6:00 a.m. to 6:00 p.m., Monday through Saturday, with Sunday operations as required. Equipment on scene will include the Clamshell Dredge Icarus, Tender Tug Ava Jude, Towing Tug Jay Michael, Crew Boat Capt. Joe Casey 2, and Survey 2. Vessels may be contacted on VHF channels 13 and 16. Passing arrangements indicate approximately 15 minutes may be needed to move vessels so as not to impede navigation.	Lat: 40° 40' 51" Lon: -074° 08' 32"

Portland Harbor

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Portland Harbor Approach - Portland Harbor/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2024-08-30 To: 2030-02-26 Shoaling has been reported in the inner harbor of Casco Bay's federal channel. Shoaling could impede the approach to the Gulf Oil Terminal in South Portland, and significantly reduces the available channel where large passenger ships regularly maneuver on and off berths in Portland. Deep draft vessels are advised to use caution when transiting the area.	
Portland Harbor Approach - Portland Harbor/General/Marine Events/Regatta (Race)	Marine Events	ME – CASCO BAY – PORTLAND – Boat Race Mariners are advised that the Wednesday Night Race Series is scheduled to be held in Casco Bay in the vicinity of Portland, ME. The event will be held every Wednesday from May 18, 2026 through October 2, 2026 from 5:00 p.m. to 9:00 p.m. 40 sailboats 18'- 44' in length will be participating. All mariners are requested to exercise caution when transiting the area. Chart number: 13290. For event information contact: Justin Henderson, (207) 267-5810.	
Portland Harbor Approach - Portland Harbor/General/Marine Events/Regatta (Race)	Marine Events	ME – CASCO BAY/GULF OF MAINE – FALMOUTH – Sailboat Race Mariners are advised that the Monhegan Island Race and Seguin Sprint is scheduled to start South of Clapboard Island and finish outside Portland Headlight. The longer Monhegan Course (150 nm) will start Friday at 3:00 pm and the shorter Seguin Island Race (55 nm) will start on Saturday at 1:00 pm. Both fleets are estimated to finish between Saturday night 8:00 pm and Sunday 10:00 pm. Approximately thirty-five 24'-60' sailboats participating. The event will take place in Casco Bay, Maine. Chart number: 13288. For event information: Greg Carville, (207) 272-2300.	

Portland Harbor Approach

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Broad Cove Rock Buoy 5	7525	OFF STATION	FD

Portland To Yarmouth

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Portland To Merepoint - Portland To Yarmouth/General/Marine Events/Regatta (Race)	Marine Events	ME –PYC Pilot Regatta – Falmouth – Regatta Mariners are advised that the PYC Regatta is scheduled to be held around Casco bay and Clapboard Island near the vicinity of Falmouth, ME. The event will be held from 12:00 p.m. to 06:00 p.m. on July 11-12, 2026. Chart number: 13260. For event information contact: Bill Conners (207)841-8534.	
Portland To Merepoint - Portland To Yarmouth/General/Marine Events/Regatta (Race)	Marine Events	General/Marine Events/Regatta (Race) From: 2026-09-18 To: 2026-10-10 Location: 43-44-09.060N/070-11-28.896W 43-43-12.144N/070-09-27.180W 43-42-10.260N/070-12-00.108W 43-42-17.640N/070-12-31.932W 43-43-09.012N/070-12-51.084W 43-44-09.060N/070-11-28.896W ME – CASCO BAY – Boat Race Mariners are advised that Portland Yacht Club Fall Series is scheduled to be held in Casco Bay in the vicinity of Clapboard Island. The event will be held every Saturday from September 19, 2026 through October 10, 2026 from 1:00 p.m. to 6:00 p.m. Approximately 25, 15'-50' sailboats will be participating. Chart number: 13260. For event information contact: 207-841-8534.	

Portsmouth Harbor

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
South Beacon Shoal Lighted Buoy 11	8385	OFF STATION	FD

President Roads

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
New England Aquarium Intake Buoy	10950	MISSING	PA

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Boston North Channel - President Roads/General/Bridges/Repairs, Painting, Or Fender Replacement	Bridges	General/Bridges/Repairs, Painting, Or Fender Replacement From: 2026-05-11 To: 2026-12-01 Location: 42-22-06.276N/071-04-25.680W MASSACHUSETTS – BOSTON INNER HARBOR – LOWER CHARLES RIVER –BROAD CANAL DRAWBRIDGE – Bridge Repairs Mariners are advised that SPS New England Inc will be conducting bridge repairs and structural steel replacement on the Broad Canal Bridge in the Lower Charles River basin. Bridge repair operations will commence on May 11, 2026, and continue through December 1, 2026. Work Hours will be Monday through Friday for 8 hours per day varying between day and night shifts subject to Mass DOT approval. On scene equipment will consist of a push boat and a 20' x 50' Barge. The equipment will be staged in the navigable channel during work hours, reducing the horizontal clearance of the channel to 20 feet. Vessels requiring the entire 40-foot navigable channel are asked to provide 24-hour advanced notification to the on-scene contractor. All support vessels and work barges will be staged outside the navigable channel during non-working hours. For more information, mariners may contact SPS New England Marine Manager Mr. Greg Bashaw at (978) 360-0262 or the project manager Mr. Andrew Chamberland at (508) 328-8828. On-scene support vessel will be monitoring VHF-FM Ch 13. Mariners are advised to use caution and transit at slow speed to minimize wake when transiting the area.	Lat: 42° 22' 06" Lon: -071° 04' 26"
Boston North Channel - President Roads/General/Bridges/Maintenance	Bridges	General/Bridges/Maintenance From: 2026-09-13 To: 2026-10-31 Location: 42-22-48.288N/071-03-06.620W Bridge Name: Chelsea St Bridge MA - BOSTON INNER HARBOR – LITTLE MYSTIC – CHELSEA STREET BRIDGE- Bridge Painting and Repairs Mariners are advised that SPS New England will be conducting Bridge painting and maintenance to the Chelsea Street Bridge mile 0.2 across thew Little Mystic channel. Work will commence on Monday September 21, 2026, and continue through Saturday October 31, 2026. Work hours will be from 7:00 a.m. to 7:00 p.m. Monday through Saturday. All work will be conducted from a suspended work platform beneath the bridge which will remain in place outside of working hours reducing the advertised vertical and horizontal clearances. Half of the navigational channel will be maintained for vessel passage. On-scene safety vessel will be monitoring VHF-FM Ch 13. POC Mr. Rick Williams (978) 417-9806 Questions may be directed to the City of Boston Public Works at (617) 635-2220 or Mr. Spencer Kresge (508) 932-7254. Mariners are advised to use caution and plan their transits accordingly.	Lat: 42° 22' 48" Lon: -071° 03' 07"
Boston North Channel - President Roads/General/Bridges/Temp Deviation	Bridges	General/Bridges/Temp Deviation From: 2026-09-20 To: 2026-10-03 Location: 42-22-08.256N/071-03-55.188W Bridge Name: MBTA Railroad Bridge MASSACHUSETTS – BOSTON INNER HARBOR – LOWER CHARLES RIVER – Temporary Deviation Mariners are advised a temporary Deviation has been issued for the opening schedule of the MBTA Draw One bridge over the Charles River. Under this temporary deviation, the bridge operator need not open for marine traffic from 6:00 p.m. to 5:00 a.m. from September 20, 2026, through October 3, 2026. Furthermore, the bridge needs only open for marine traffic on the hour from 5:00 a.m. to 6:00 p.m. from September 20, 2026, through October 3, 2026. Vessels able to transit without a bridge opening are free to do so. For more information contact Mr. Karl Eckstrom at (857) 329-8231. Mariners are advised to use caution and transit at slow speed to minimize wake.	Lat: 42° 22' 08" Lon: -071° 03' 55"
Boston North Channel - President Roads/General/Marine Construction (Excluding Bridges)/Boring and Core Samples	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Boring and Core Samples From: 2026-08-10 To: 2026-09-30 Location: 42-22-09.516N/071-03-55.008W 42-22-07.284N/071-03-52.452W 42-22-06.564N/071-03-53.820W 42-22-09.480N/071-03-57.348W 42-22-09.516N/071-03-55.008W MASSACHUSETTS – BOSTON INNER HARBOR – CHARLES RIVER – Boring Operations Mariners are advised that Skanska Civil Northeast/Koch JV (Skanska) will be conducting boring operations in the vicinity of the MBTA Draw One Bridge over the Charles River. Operations will commence on August 10, 2026, and continue through September 25, 2026. Work will be conducted between 7:00 a.m. and 4:00 p.m. daily for the duration of the project. On-scene equipment will consist of a 22' x 40' steel pontoon barge and one assist vessel. All boring operations will occur outside the navigational channel. For additional information, mariners may contact Skanska representative Mr. Edward Breed at (617) 981-0215. The on-scene support vessel will monitor VHF-FM Channels 13 and 16. Mariners are advised to exercise caution and proceed at a slow speed to minimize wake while transiting the area.	
Boston North Channel - President Roads/General/Marine Events/Regatta (Race)	Marine Events	MA – BOSTON HARBOR ISLANDS – SAVIN HILL YACHT CLUB BOSTON LIGHT RACE – REGATTA – The Savin Hill Yacht Club and Constitution Yacht Club are hosting the Boston Light Race on September 26th, 2026, from 12:00 PM to 6:00 PM in the vicinity of the Boston Harbor Islands, Boston, MA. The event will consist of approximately 30 - 45 vessels, 22' to 47' in length. The vessel responsible for on scene safety can be reached at 508-479-1338. For more information please contact Sean Kane at 508-479-1338. Chart 13270	
Boston North Channel - President Roads/General/Marine Events/Regatta (Race)	Marine Events	MA – CHARLESTOWN – BOSTON INNER HARBOR – COURAGEOUS SAILING YOUTH FALL PROGRAM – REGATTA – The Courageous Sailing Center is hosting the Courageous Sailing Youth Fall Program every Monday through Thursday, 3:30 PM to 6:30 PM from August 10, 2026, to October 30, 2026, in and around the vicinity of Pier 4 Charlestown, Boston Inner Harbor. The event will consist of approximately 15 sailing vessels varying in length from 14'-26' with 3 support craft. The person responsible for on scene safety can be reached at 917-282-7464. For more information, please contact Dave DiLorenzo at 917-282-7464. Chart 13272	
Boston North Channel - President Roads/General/Marine Events/Regatta (Race)	Marine Events	MA – BOSTON - CHARLES RIVER – MASS AVE BRIDGE TO NORTHEASTERN BOATHOUSE – HEAD OF THE CHARLES – ROWING RACE – The Cambridge Boat Club is hosting the Head of the Charles Rowing Race from October 16th. 2026 to October 18th, 2026, from 7:30 AM to 4:30 PM on the Charles River from the Mass Ave Bridge to the Northeastern University Boathouse.. The event will consist of over 500 rowing craft varying in length. The person responsible for on scene safety can be reached at 617-799-6980. For more information, please contact Steven Hines at 617-799-6980. Chart 13267	

Boston North Channel - President Roads/General/Marine Events/Regatta (Race)	Marine Events	MA – BOSTON – BOSTON INNER HARBOR – PIERS PARK SAILING SUNDAY FALL RACING – REGATTA – The Piers Park Sailing Center is hosting the Sunday Fall Racing Series every Sunday from September 27, 2026, to October 25, 2026, from 11:00 AM to 1:00 PM. The event will take place in Boston Inner Harbor at the Piers Park Mooring Field. The event will consist of approximately 6 sailing vessels, all 23’ in length. The person responsible for on scene safety can be reached on VHF Ch. 78. For more information, please contact Alex DeFronzo at 617-894-5868. Chart 13727	
Boston North Channel - President Roads/General/Marine Events/Regatta (Race)	Marine Events	MA – BOSTON – BOSTON INNER HARBOR – PIERS PARK SAILING HALLOWEEN HOWL REGATTA – REGATTA – The Piers Park Sailing Center is hosting the Halloween Howl Regatta on Saturday October 31, 2026, from 11:00 AM to 2:30 PM. The event will take place in Boston Inner Harbor from Piers Park out and around Spectacle Island and back. The event will consist of approximately 6 sailing vessels, all 23’ in length. The person responsible for on scene safety can be reached on VHF Ch. 78. For more information, please contact Alex DeFronzo at 617-894-5868. Chart 13727	
Boston North Channel - President Roads/General/Marine Events/Regatta (Race)	Marine Events	MA – BOSTON – BOSTON INNER HARBOR – PIERS PARK SAILING HALLOWEEN HOWL REGATTA – REGATTA – The Piers Park Sailing Center is hosting the Halloween Howl Regatta on Saturday October 31, 2026, from 11:00 AM to 2:30 PM. The event will take place in Boston Inner Harbor from Piers Park out and around Spectacle Island and back. The event will consist of approximately 6 sailing vessels, all 23’ in length. The person responsible for on scene safety can be reached on VHF Ch. 78. For more information, please contact Alex DeFronzo at 617-894-5868. Chart 13727	
Boston North Channel - President Roads/General/Marine Events/Regatta (Race)	Marine Events	MA – BOSTON – BOSTON INNER HARBOR – BOSTON SAILING CENTER SATURDAY FALL RACING SERIES – REGATTA – The Boston Sailing Center is hosting the Boston Sailing Center Saturday Fall Racing Series every Saturday, from 10:00 AM to 1:00 PM from September 12, 2026, to October 17, 2026, in and around the vicinity of Fan Pier, Boston Inner Harbor. The event will consist of approximately 8 sailing vessels 27’ in length with 1 support craft. The person responsible for on-scene safety can be reached on VHF CH 13 by hailing the BSC Race Committee Boat. For more information, please contact Dave Bryan at 617-227-4198. Chart 13272	
Boston North Channel - President Roads/General/Marine Events/Fireworks	Marine Events	MA – BOSTON – CHARLES RIVER – HARVARD UNIVERSITY ATHLETICS – FIREWORKS – Pyrotecnico is hosting the Harvard University Athletics Fireworks on October 3, 2026, from 8:15 PM to 8:45 PM in the area of the Newell Boathouse Charles River, Boston, MA in approximate position 42°22.267’ N, 071°07.532’ W. The event will consist of approximately 2 barges and tug, and 1 pontoon vessel. Please maintain a 700’ distance from the fireworks barges. The person responsible for on-scene safety can be reached at 603-235-4656. For more information, please contact Tara Hughgill at 603-532-8324.	

Providence River

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Providence River Channel Buoy 17	18320	OFF STATION	FD
Bullock Point Light BP	18345	LT EXT	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Providence River Approach - Providence River/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-08-31 To: 2026-09-30 Location: 41-45-43.416N/071-22-27.264W AGM Marine Contractors, Inc. is scheduled to perform an ATON (Aid to Navigation) removal operation for the U.S). Coast Guard, specifically removing Sabin Point Daybeacon SP (LLNR 18455) in position 41-45-43.389N 071-22-27.250W in Providence River, Rhode Island. The project is planned for August 31 to September 30, 2026, with work conducted Monday through Friday 12 hours per day, weather permitting. The operation will utilize the barge "ZARENAI" and will be monitoring radio frequencies 13/16 and working on 68.	Lat: 41° 45' 43" Lon: -071° 22' 27"
Providence River Approach - Providence River/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-09-16 To: 2026-10-01 Location: 41-45-43.380N/071-22-27.228W Mariners are advised that AGM Marine Contractors, Inc. will be conducting removal operations for Sabin Point Daybeacon in the Providence River, RI, in approximate position 41°45'43.389"N, 071°22'27.250"W. Operations are scheduled to take place from approximately August 31, 2026 through September 30, 2026, Monday through Friday, during daylight hours from 6:00 a.m. to 6:00 p.m., weather permitting. Work will be conducted from the barge Zarenai, which will monitor VHF-FM channels 13 and 16 and work on channel 68. Mariners are requested to transit the area with caution and reduce wake when operating near the work site.	Lat: 41° 45' 43" Lon: -071° 22' 27"
Providence River Approach - Providence River/General/Marine Events/Regatta (Race)	Marine Events	RI – PROVIDENCE RIVER – RIYC 2026 GASPEE REGATTA – RACE/REGATTA Mariners are advised that the RIYC 2026 Gaspee Regatta is scheduled to be held in multiple areas to include Providence River, Rhode Island Yacht Club, Rumstick Neck Reach, Rumstick Point. The event will take place on Sunday June 14, 2026 from 1:00 p.m. to 4:00 p.m. Expect up to 15 sailing vessels, 25-42 ft in length. Mariners are advised to transit the area with extreme caution. Mariners may contact the person in charge by phone at (401) 474-4769.	

Providence River Approach

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Providence River Approach Channel Lighted Buoy 13	18295	MISSING	FD
Providence River Approach Channel Lighted Buoy 13	18295	MISSING/TRLB	FD

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Prudence Island Monitoring Lighted Buoy	18241	REDUCED INT	PA

Quicks Hole

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE

Quicks Hole Entrance Lighted Bell Buoy 1	15910	LT EXT	FD
--	-------	--------	----

Quonset Channel

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Davisville Turning Basin Buoy 18	19250	OFF STATION	PA

Raritan Bay

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Raritan Bay Light 58	36315	LT EXT	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Swash Channel - Raritan Bay/General/Marine Construction (Excluding Bridges)/Dredging	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Dredging From: 2026-08-01 To: 2026-10-01 Curtin Maritime, represented by Project Manager Robert Collaro, will conduct mechanical clamshell dredging in the New York and New Jersey Channels—specifically the Seguine, Ward, and Outerbridge reaches—from August 1, 2026, to October 1, 2026. Operations will run continuously, 24 hours per day, seven days a week. The equipment on scene will include the DB Avalon dredge, three scows (Crown Point, Rincon Point, and Stony Point), three towing tugs, and one assist tug. All vessels will monitor VHF-FM Channels 13 and 16 for communications. Mariners are advised that passing arrangements require a “Slow Bell” request and one hour’s notice to move vessels out of the channel to avoid impeding navigation. For further information, Robert Collaro can be contacted at 772-643-0784 or rcollaro@curtinmaritime.com. The Local Notice to Mariners should be submitted to the U.S. Coast Guard First District two weeks prior to the start of operations, and publication does not constitute project approval. Coordination with the appropriate Coast Guard Sector is required before publication.	
Swash Channel - Raritan Bay/General/Marine Events/Regatta (Race)	Marine Events	General/Marine Events/Regatta (Race) From: 2026-05-06 To: 2026-11-02 NY/NJ– LOWER NY BAY – RARITAN BAY – Sailing Regatta Mariners are advised that regattas are scheduled to be held on Raritan Bay. Races will take place every Wednesday, Friday, most Saturdays, some Sundays and Holidays from May 5, 2026 through January 7, 2027 at various times stipulated in the table below. Approximately 30 sailboats 12-45 feet in length will participate in short-distance courses. Interested mariners may contact the Principal Race Officer on marine band radio channel 9 or 71 VHF-FM or via telephone at 203-509-1469.	
Swash Channel - Raritan Bay/General/Marine Events/Regatta (Race)	Marine Events	General/Marine Events/Regatta (Race) 1. NARRATIVE: THE RARITAN YACHT CLUB WILL HOLD REGATTAS IN THE RARITAN BAY FROM MAY 6, 2026 AND CONTINUING UNTIL JANUARY 7, 2026. THESE REGATTAS WILL INCLUDE APPROXIMATELY 30 SAILBOATS 15-45 FEET IN LENGTH. 2. NEW JERSEY - RARITAN BAY - A REGATTA WILL TAKE PLACE EVERY WEDNESDAY, FRIDAY, MOST SATURDAYS, SOME SUNDAYS AND HOLIDAYS FROM JUNE 10, 2026 THROUGH DECEMBER 26, 2026 APPROXIMATELY 30 SAILING VESSELS 15-45 FEET IN LENGTH WILL PARTICIPATE IN RACES THROUGHOUT THE RARITAN BAY. VARIOUS MOTORIZED VESSELS WILL BE ASSISTING WITH THE EVENT. INTERESTED MARINERS MAY CONTACT THE PRINCIPAL RACE OFFICER ON CHANNEL 9 OR 71 VHF-FM OR VIA TELEPHONE AT 203-509-1469. 3. SECNY BROADCAST WITH REGULARLY SCHEDULE BROADCAST DURING THE DATES OF EVENT: A. 10 - JUNE - 26 FROM 6:15 P.M. TO 7:30 P.M. B. 12 - JUNE - 26 FROM 6:00 P.M. TO SUNSET C. 14 - JUNE - 26 FROM 6:15 P.M. TO 7:30 P.M. D. 17 - JUNE - 26 FROM 6:00 P.M. TO SUNSET E. 19 - JUNE - 26 FROM 2:30 P.M. TO 4:30 P.M. F. 20 - JUNE - 26 FROM 6:15 P.M. TO 7:30 P.M. G. 20 - JUNE - 26 FROM 6:00 P.M. TO SUNSET H. 24 - JUNE - 26 FROM 3:00 P.M. TO 5:00 P.M. I. 26 - JUNE - 26 FROM 3:00 P.M. TO 5:00 P.M. J. 28 - JUNE - 26 FROM 6:15 P.M. TO 7:30 P.M. K. 01 - JULY - 26 FROM 6:00 P.M. TO SUNSET L. 03 - JULY - 26 FROM 2:00 P.M. TO 4:00 P.M. M. 04 - JULY - 26 FROM 1:00 P.M. TO 3:00 P.M. N. 08 - JULY - 26 FROM 6:00 P.M. TO SUNSET O. 10 - JULY - 26 FROM 6:15 P.M. TO 7:30 P.M. P. 11 - JULY - 26 FROM 10:00 A.M. TO 12:00 P.M. Q. 12 - JULY - 26 FROM 6:00 P.M. TO SUNSET R. 15 - JULY - 26 FROM 11:00 A.M. TO 5:00 P.M. T. 17 - JULY - 26 FROM 11:00 A.M. TO 5:00 P.M. U. 18 - JULY - 26 FROM 6:15 P.M. TO 7:30 P.M. V. 19 - JULY - 26 FROM 6:00 P.M. TO SUNSET W. 19 - JULY - 26 FROM 3:00 P.M. TO 5:00 P.M. X. 22 - JULY - 26 FROM 3:00 P.M. TO 5:00 P.M. Y. 24 - JULY - 26 FROM 6:15 P.M. TO 7:30 P.M. Z. 25 - JULY - 26 FROM 6:00 P.M. TO SUNSET AA. 29 - JULY - 26 FROM 2:00 P.M. TO 4:00 P.M. BB. 31 - JULY - 26 FROM 6:15 P.M. TO 7:30 P.M. CC. 01 - AUGUST - 26 FROM 6:00 P.M. TO SUNSET DD. 02 - AUGUST - 26 FROM 6:15 P.M. TO 7:30 P.M. EE. 05 - AUGUST - 26 FROM 6:00 P.M. TO SUNSET FF. 07 - AUGUST - 26 FROM 6:15 P.M. TO 7:30 P.M. GG. 12 - AUGUST - 26 FROM 6:00 P.M. TO SUNSET HH. 14 - AUGUST - 26 FROM 6:15 P.M. TO 7:30 P.M. II. 19 - AUGUST - 26 FROM 6:00 P.M. TO SUNSET JJ. 21 - AUGUST - 26 FROM 3:00 P.M. TO 5:00 P.M. KK. 22 - AUGUST - 26 FROM 3:00 P.M. TO 5:00 P.M. LL. 22 - AUGUST - 26 FROM 6:15 P.M. TO 7:30 P.M. MM. 26 - AUGUST - 26 FROM 6:00 P.M. TO SUNSET NN. 28 - AUGUST - 26 FROM 10:00 A.M. TO 12:00 P.M. OO. 29 - AUGUST - 26 FROM 1:00 P.M. TO 3:00 P.M. PP. 30 - AUGUST - 26 FROM 6:15 P.M. TO 7:30 P.M. QQ. 02 - SEPTEMBER - 26 FROM 6:15 P.M. TO 7:30 P.M. RR. 07 - SEPTEMBER - 26 FROM 11:00 A.M. TO 5:00 P.M. SS. 09 - SEPTEMBER - 26 FROM 11:00 P.M. TO 5:00 P.M. TT. 16 - SEPTEMBER - 26 FROM 6:15 P.M. TO 7:30 P.M. UU. 19 - SEPTEMBER - 26 FROM 6:15 P.M. TO 7:30 P.M. VV. 20 - SEPTEMBER - 26 FROM 6:15 P.M. TO 7:30 P.M. WW. 23 - SEPTEMBER - 26 FROM 6:15 P.M. TO 7:30 P.M. XX. 27 - SEPTEMBER - 26 FROM 10:00 A.M. TO 12:00 P.M. YY. 30 - SEPTEMBER - 26 FROM 6:15 P.M. TO 7:30 P.M. ZZ. 03 - OCTOBER - 26 FROM 6:15 P.M. TO 7:30 P.M. AAA. 07 - NOVEMBER - 26 FROM 11:00 A.M. TO 1:00 P.M. BBB. 14 - NOVEMBER - 26 FROM 11:00 A.M. TO 1:00 P.M. CCC. 21 - NOVEMBER - 26 FROM 11:00 A.M. TO 1:00 P.M. DDD. 28 - NOVEMBER - 26 FROM 11:00 A.M. TO 1:00 P.M. EEE. 05 - DECEMBER - 26 FROM 11:00 A.M. TO 1:00 P.M. FFF. 12 - DECEMBER - 26 FROM 11:00 A.M. TO 1:00 P.M. GGG. 19 - DECEMBER - 26 FROM 11:00 A.M. TO 1:00 P.M. HHH. 26 - DECEMBER - 26 FROM 11:00 A.M. TO 1:00 P.M.	

Raritan River

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION

Raritan River Cutoff Channel - Raritan River/General/Bridges/Construction	Bridges	Raritan River Cutoff Channel - Raritan River/General/Bridges/Construction From: 2026-03-10T00:00:00.000Z To: 2030-01-18T23:59:59.000Z Location: 40.49632, -74.28037 Bridge Name: Raritan River Railroad Bridge Raritan River Cutoff Channel - Raritan River/General/Bridges/Construction From: 2026-03-10T00:00:00.000Z To: 2030-01-18T23:59:59.000Z Location: 40.49632, -74.28037 Bridge Name: Raritan River Railroad Bridge Construction and demolition operations to replace the Raritan River Railroad Bridge commenced on April 1, 2026, and will continue through January 18, 2030. Operations through August 2026 include Perth Amboy Pier Concrete Operations followed by counterweight Installation at the South Amboy Pier. A number of barges and support vessels will be moored outside the navigational channel. Due to ongoing construction activities, mariners will be unable to use the south navigational channel. Work hours for this project are 7:00a.m. to 3:30 p.m. Monday -Friday. Mariners are advised to exercise caution and reduce wake when transiting the area. For more detailed information about the positioning of marine equipment, marker buoys and temporary works contact Project Engineer at 718 702-7238. A one-day channel closure is A one-day channel closure is tentatively scheduled the weeks of October 26 and November 16, 2026. The actual closure date will be weather dependent and communicated with local mariners as the operation gets closer.	Lat: 40° 29' 47" Lon: -074° 16' 49"
Raritan River Cutoff Channel - Raritan River/General/Bridges/Public Notice	Bridges	The TIR published in the Federal Register at https://www.govinfo.gov/content/pkg/FR-2026-05-05/pdf/2026-08733.pdf . Comments and related material must be received by the Coast Guard on or before August 3, 2026. This establishes a RNA from 12:01 a.m. on April 15, 2026, until 11:59 p.m. on June 30, 2030. ADDRESSES: You may submit comments at https://www.regulations.gov . See the "Public Participation and Request for Comments" portion of the SUPPLEMENTARY INFORMATION section for further instructions on submitting comments. To view available documents go to https://www.regulations.gov and search for USCG-2026-0149. --165.T01-0149 Regulated Navigation Area (RNA); (a)Location. See MSI LNM Layer. (c) In addition to the general RNA regs in § 165.13, the following regs apply to the RNA. (1) Nothing in this regulation relieves any vessel, owner, operator, charterer, master, or person directing the movement of a vessel, from the consequences of any neglect to comply with this part or any other applicable law or regulation (i.e. the International Regulations for Prevention of Collisions at Sea, 1972 (72 COLREGS) or 33 CFR part 84-Subchapter E, Inland Navigation Rules) or of the neglect of any precaution which may be required by the ordinary practice of seamen, or by the special circumstances of the case. (2) Entry and movement within the RNA is subject to a "Slow-No Wake" speed limit. All vessels may not produce a wake and may not attain speeds greater than five (5) knots unless a higher minimum speed is necessary to maintain bare steerageway. (3) No vessel is permitted to transit through the south span navigational channel of the bridge(s) at any given time. (4) Any vessel transiting through the RNA must make a direct passage. No vessel may stop, fish, moor, anchor, or loiter within the RNA at any time. (5) Vessels may not pass (overtake) another vessel within the RNA. (6) Only one vessel is permitted to pass through the north span navigational channel of the bridge(s) at any given time. (7) Except when transiting through the north span navigation channel, no vessel or craft may operate within 20 feet of the bridge(s). (8) The operator of any vessel transiting in the RNA must comply with all lawful directions given to them by the COTP or the COTP's on-scene representative. (9) When a full enforcement period of the regulated area is activated, only vessel authorized by COTP may enter or remain within the RNA. (d) Enforcement. The following enforcement periods and requirements apply to this RNA. (1) This section enforced from 12:01 a.m. on 15Apr2026, to 11:59 p.m. on 30Jun2030. (2) The "Slow-No Wake" speed limit, south channel closure, and other restrictions-except for the limited full enforcement period prohibiting vessels from entering the regulated area-will be enforced throughout the entire enforcement period. (3) Full enforcement periods of the regulated area, prohibiting all vessel entry, will be enforced only during hazardous construction operations involving multiple tugs and large barges maneuvering in and obstructing the navigable channel for heavy lift, construction, or demolition activities. The USCG will issue information on full enforcement periods through LNM's, the CG Navigation Center at https://www.navcen.uscg.gov/msi , and BNMs via VHF CH 16 as soon as practicable. (4) Persons or vessels seeking to deviate from the restrictions described in section (c) of this section or to enter the regulated area during a full enforcement period must request authorization from the COTP or COTP's on-scene designated representative on VHF-16 or via (718) 354-4353. Enforcement periods prohibiting vessels from entering the RNA planned during the following approx. dates (subject to change): Jul-Aug2026, two separate 1-day full-chnl closures Jul2027-Jun2028, three, 7-day full chnl closures Jan-Sep2028, one 30-day full chnl closure Jul-Sep2029, one 14-day full chnl closure Dates/times provided when available.	

Raritan River Cutoff Channel

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Perth Amboy Port Authority No Wake Lighted Buoy A	36585	MISSING	PA
Perth Amboy Port Authority No Wake Lighted Buoy B	36586	MISSING	PA
Perth Amboy Port Authority No Wake Lighted Buoy C	36587	MISSING	PA
Perth Amboy Port Authority No Wake Lighted Buoy D	36588	MISSING	PA

Red Brook Harbor

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Bassetts Island Shoal South Buoy 1	16540	MISSING	FD

Reynolds Channel

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Reynolds Channel/General/Bridges/Maintenance	Bridges	General/Bridges/Maintenance NEW YORK – HENDRIX CREEK - Bridge Maintenance – From July 10, 2026 to July 25, 2027, NYSDOT will be performing bridge maintenance and repairs at the Belt Parkway across Hendrix Creek at mile 0.1. During this time work platforms will be installed decreasing the vertical clearance to 20'-7". Mariners with any questions or concerns may contact Antonio Donato at (646) 703-2644.	Lat: 40° 38' 48" Lon: -073° 52' 25"

Reynolds Channel/General/Bridges	Bridges	Reynolds Channel/General/Bridges From: 2026-09-01 To: 2027-01-01 Location: 40.59395, -73.58721 Bridge Name: Loop Pkwy Bridge From September 15, 2026 to December 31, 2026, between 6:00 a.m. and 4:00 p.m., (with occasional night work) a barge will be operated under Loop Parkway Bridge over Reynolds Channel at mile 8.2 to perform bridge painting. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or call Dylan Thompson 516-402-4339 or David Ofsharick 516-580-1269. The barge will be moved out of the navigable channel after work hours or when not in use. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 35' 38" Lon: -073° 35' 14"
----------------------------------	---------	---	--

Robinsons Hole

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Robinsons Hole Buoy 10	15900	MISSING	FD

Rockland Harbor Bypass Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Rockland Harbor Bypass Channel Buoy 12	4205	SINKING	FD

Saco River

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector Northern New England, Submerged Lands Act (SLA) - Saco River/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-06-03 To: 2027-08-31 Location: 43-27-36.000N/070-22-25.608W North Jetty Spur Construction project by Mohawk Northeast, scheduled to take place in Saco, Maine in position 43.464725° N, 70.373789° W, from June 2026 through August 2027. The project involves construction activities at Saco Bay and Saco River, with a haul route extending to Portland Harbor. Operations will occur Monday through Friday, with ten-hour workdays. The onsite equipment will include two tug boats, one push boat, one work skiff, two work barges, and two material barges. Vessel communications will be managed via VHF channels 13 and 16, with security calls made prior to vessel movements to ensure safe navigation and coordination with passing vessels.	Lat: 43° 27' 36" Lon: -070° 22' 26"
Sector Northern New England, Submerged Lands Act (SLA) - Saco River/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-09-03 To: 2027-08-31 Location: 43-27-46.800N/070-22-26.400W Mariners are advised that Mohawk Northeast, Inc. will conduct North Jetty Spur construction work in Saco, Maine, from June 2026 through August 2027. Work will take place in the Saco Bay and Saco River area, primarily on the north side of the North Jetty, near 43.463° N, 70.374° W. Marine construction equipment will be operating in and around the work area, including tugboats, a push boat, a work skiff, work barges, and material barges. Equipment and materials may also transit between the project site and Portland Harbor using designated haul routes through Saco Bay and nearby coastal waters. The haul routes are expected to be approximately 100 feet wide, but may vary depending on weather and operating conditions. Work is expected to occur Monday through Friday, during 10-hour workdays. Mariners should use caution when transiting near the construction area, reduce speed as appropriate, and remain alert for slow-moving or restricted-maneuverability vessels and barges. Project vessels will monitor VHF-FM channels 13 and 16. Vessel masters will make security calls before vessel movements and will coordinate passing arrangements with approaching traffic as needed. Mariners are requested to contact project vessels on VHF channels 13 or 16 before passing or operating near the work area.	Lat: 43° 27' 47" Lon: -070° 22' 26"

Sakonnet River

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Elisha Ledge Buoy EL	17555	OFF STATION	FD
Sakonnet River Buoy 8	17620	OFF STATION	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector Southeastern New England, Submerged Lands Act (SLA) - Sakonnet River/General/Autonomous Vessel Operations	Autonomous Vessel Operations	General/Autonomous Vessel Operations From: 2026-08-11 To: 2026-11-11 Location: 41-26-17.160N/071-13-20.028W 41-20-21.084N/071-13-13.836W 41-20-15.540N/071-19-22.152W 41-26-10.680N/071-19-23.376W 41-26-17.160N/071-13-20.028W M/V ATLANTIC ENDURANCE will be conducting autonomous testing between the hours of 0800-2000 Monday through Friday and can be contacted on channel 13/16.	
Sector Southeastern New England, Submerged Lands Act (SLA) - Sakonnet River/General/Marine Events/Fireworks	Marine Events	RI – SAKONETT RIVER – TOWN OF GOSNOLD FIREWORKS DISPLAY – FIREWORKS Mariners are advised that the Town of Tiverton Fireworks Display is scheduled to be held from a barge in the vicinity of Sakonett River and Grinnell Beach, Tiverton, RI. The event will take place on Saturday May 23, 2026 from 8:45 p.m. to 9:30 p.m. Mariners are requested to maintain a minimum distance of 190 yards from the fireworks launching platform. Mariners may contact the person in charge by phone at (603) 235-4656. (Rain Date: May 26)	
Sector Southeastern New England, Submerged Lands Act (SLA) - Sakonnet River/General/Miscellaneous	Miscellaneous	General/Survey Operations From: 2026-02-03 To: 2027-01-01 VATN Systems will be conducting AUV testing in the Sakonnet River, from Island Park to Third Beach, from February 2, 2026, to December 31, 2026, between 8:00am to 5:00pm. Equipment on scene will be a support vessel, AUV with a boat in tow, monitoring VHF-FM CH 16.	

Salem Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE

Bowditch Ledge Daybeacon	10025	STRUCT DEST	FD
--------------------------	-------	-------------	----

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector Boston, Submerged Land Act (SLA) - Salem Channel/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-28-21 To: 2026-11-16 Location: 42-31-49.764N/070-51-43.164W Marine construction operations will be conducted in Salem Harbor, MA, in the vicinity of Abbott Rock Daybeacon from approximately September 28, 2026, through November 15, 2026. AGM Marine Contractors, Inc. will remove the Abbott Rock Daybeacon for the U.S. Coast Guard using the dredge PRONCKAI, deck barge THING, and tug SITKA. Work is expected to occur during a single daylight shift, approximately 6:00 a.m. to 8:00 p.m., seven days per week, weather permitting. Mariners are advised to transit the area with caution, reduce wake as necessary, and remain alert for construction vessels and equipment operating on scene. The dredge and tug will monitor VHF-FM Channels 13 and 16 and will use Channel 68 as the working channel.	Lat: 42° 31' 50" Lon: -070° 51' 43"
Sector Boston, Submerged Land Act (SLA) - Salem Channel/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-09-28 To: 2026-11-16 Location: 42-32-25.152N/070-48-42.624W Marine construction operations will be conducted in Salem Sound, MA, in the vicinity of Bowditch Ledge Daybeacon from approximately September 28, 2026, through November 15, 2026. AGM Marine Contractors, Inc. will remove the Bowditch Ledge Daybeacon for the U.S. Coast Guard using the dredge PRONCKAI, deck barge THING, and tug SITKA. Work is expected to occur during a single daylight shift, approximately 6:00 a.m. to 8:00 p.m., seven days per week, weather permitting. Mariners are advised to transit the area with caution, reduce wake as necessary, and remain alert for construction vessels and equipment operating on scene. The dredge and tug will monitor VHF-FM Channels 13 and 16 and will use Channel 68 as the working channel.	Lat: 42° 32' 25" Lon: -070° 48' 43"
Sector Boston, Submerged Land Act (SLA) - Salem Channel/General/Marine Events/Regatta (Race)	Marine Events	MA – BEVERLY – SALEM SOUND – JUBILEE YACHT CLUB THURSDAY NIGHT RACING – REGATTA – The Jubilee Yacht Club is hosting the JYC Thursday Night Races every Thursday night, from May 21, 2026, to October 1, 2026, from 6:00 PM to 9:00 PM in and around the vicinity of Salem Sound. The event will consist of approximately 30 sailing vessels varying in length from 24'-40'. The person responsible for on-scene safety can be reached at 617-957-0073 or VHF CH 72. For more information, please contact Tyler Jupp at 617-957-0073. Chart 13275	

Salem South Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Endeavors Rock Daybeacon	10152	DAYMK MISSING	FD

Sandy Bay

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Dodge Rock Daybeacon 2	9840	MISSING/HAZ NAV	FD
Dodge Rock Buoy 2A	9841	SINKING	FD

Sandy Hook Bay

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Anchorage Buoy E	35525	MISSING	FD

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Atlantic Highlands Light 4	35596.4	SINKING	PA

Sandy Hook Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Sandy Hook Channel Lighted Buoy 5	35110	OFF STATION	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector New York, Submerged Lands Act (SLA) - Sandy Hook Channel/General/Marine Construction (Excluding Bridges)/Dredging	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Dredging From: 2026-09-22 To: 2026-11-21 Mariners are advised that Great Lakes Dredge and Dock Company, LLC will conduct channel maintenance dredging in New York Harbor, Sandy Hook Channel, Monmouth County, New Jersey, under USACE Contract W912DS-26-C-0022, from early October 2026 through mid-November 2026. Operations will occur 24 hours per day, 7 days per week. Equipment on scene will include GLDD Mechanical Dredge 54, two tugboats, two scow barges, and one survey/crew boat. Dredged material will be transported approximately 5 nautical miles for placement at the Sandy Hook Sea Bright Offshore Borrow Area. Mariners are requested to transit the area with caution, proceed at minimum safe speed to reduce wake, and avoid interfering with dredging, towing, and placement operations. Vessels may contact the dredge and support vessels on VHF-FM Channels 13 and 16 for passing arrangements.	

Saquatucket Harbor

Temporary Changes

NAME	LLNR	STATUS	AID TYPE
Saquatucket Harbor Buoy 8	14055	DISCONTINUED FOR DREDGING	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector Southeastern New England, Submerged Lands Act (SLA) - Saquatucket Harbor/ATON/Advanced Notice of Change	Advanced Notice of Change	ATON/Advanced Notice of Change From: 2026-09-02 To: 2027-03-01 Location: 41-39-23.976N/070-03-35.712W Aid Name: Saquatucket Harbor Buoy 1 LLNR: 14030 Action: CHANGE Action Type Change Light System Primary The U.S. Coast Guard will be making the following change to Aids to Navigation: CHANGE Saquatucket Harbor Buoy 1 (LLNR 14030) from an unlighted buoy to Saquatucket Harbor Lighted Buoy 1 (LLNR 14030) Quick Flashing Green Add to the remarks section of Light List Vol 1 Aid removed when endangered by ice. Light removed from Nov 15 to May 1.	Lat: 41° 39' 24" Lon: -070° 03' 36"

Sasanoa River

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Sasanoa River Buoy 39	5990	OFF STATION	FD

Saugatuck River

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Saugatuck River/General/Bridges	Bridges	Saugatuck River/General/Bridges From: 2026-09-16 To: 2026-09-26 Location: 41.122714, -73.369155 Bridge Name: Bridge St Bridge From September 24, 2026 to September 25, 2026 between 8:00 a.m. to 4:00p.m., a raft will be utilized to inspect the Bridge Street (Rte 136) Bridge across Saugatuck River at mile 1.3, in Westport, Connecticut. This bridge inspection will not affect the navigational channel. Mariners with any questions may contact the contractor via marine radio VHF-FM Ch 13/16 or call Nate Crane at 9203) 213-4254. Mariners are advised to exercise caution and reduce wake when transiting the area.	Lat: 41° 07' 22" Lon: -073° 22' 09"

Saugus River Approach Channel

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Nahant Harbor - Saugus River Approach Channel/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	MA-SALEM AND LYNN HARBORS (Chart 13275)-SAUGUS RIVER APPROACH CHANNEL Severe shoaling has been reported in the Saugus River in the vicinity of Saugus River Approach Channel Lighted Buoy 5 (LLNR 10655). Mariners should proceed with caution while transiting the area.	
Nahant Harbor - Saugus River Approach Channel/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-09-15 To: 2026-10-16 Location: 42-26-40.488N/070-57-43.956W Mariners are advised that Semper Diving & Marine Corp will conduct commercial diving operations in Lynn Harbor, Lynn, MA, in the vicinity of 42°26'40.50"N, 70°57'43.97"W, from September 21 through October 15, 2026. Operations will take place daily from 6:00 a.m. to 3:00 p.m. A spud barge will be on scene and may be contacted on VHF-FM channel 16. Mariners transiting the area are requested to use caution, pass on the offshore side of the vessel, and maintain a closest point of approach of at least 100 yards.	Lat: 42° 26' 40" Lon: -070° 57' 44"
Nahant Harbor - Saugus River Approach Channel/General/Marine Construction (Excluding Bridges)/Boring and Core Samples	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Boring and Core Samples From: 2026-08-24 To: 2026-10-24 Location: 42-26-43.764N/070-57-57.240W 42-26-43.368N/070-57-54.504W 42-26-32.568N/070-57-58.716W 42-26-32.964N/070-58-00.732W 42-26-43.764N/070-57-57.240W MASSACHUSETTS – LYNN/REVERE - SAUGUS RIVER – GENERAL EDWARDS BRIDGE – Boring Operations Mariners are advised that New England Boring Contractors will be conducting boring operations in the vicinity of the General Edwards Bridge Rt 1A Lynn/Revere. Operations will commence on Monday August 24, 2026, and continue through Friday October 23, 2026. Hours of operations are 7:00 a.m. to 3:00 p.m. for the duration of the operations. On scene equipment will consist of the 18'x35' jack-up barge Seismic Princess #7. All proposed boring locations are located outside of the navigable channel. For more information mariners may contact New England Boring Representative at (603) 828-6115 or (774) 259-2978. On scene vessel will be monitoring VHF-FM Ch 13/16. Mariners are advised to use caution and transit at slow speed to minimize wake when transiting the area.	

Scituate Harbor Approach

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector Boston, Submerged Land Act (SLA) - Scituate Harbor Approach/General/Marine Events/Regatta (Race)	Marine Events	MA – SCITUATE – SCITUATE SAILING SUNDAY FALL SERIES – REGATTA – The Satuit Boat Club is hosting the Scituate Sailing Sunday Fall Series every Wednesday from September 06, 2026, to October 04, 2026 in and around Scituate Harbor from 1:00 PM until 5:00 PM. The event will consist of a weekly regatta, consisting of approximately 15 vessels, all 24' – 50' in length. The vessel responsible for on scene safety can be reached at 781-635-6589. For more information, please contact James Plassman at 781-635-6589. Chart 13269	

Sector Boston, Exclusive Economic Zone (EEZ)

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE

WHOI Traffic Separation Scheme Research Lighted Buoy AB-2	466	MISSING	PA
WHOI Traffic Separation Scheme Research Lighted Buoy AB-3	467	MISSING	PA
WHOI Traffic Separation Scheme Research Lighted Buoy AB-4	468	MISSING	PA
WHOI Traffic Separation Scheme Research Lighted Buoy AB-5	471	MISSING	PA
WHOI Traffic Separation Scheme Research Lighted Buoy AB-6	472	MISSING	PA
WHOI Traffic Separation Scheme Research Lighted Buoy AB-7	473	MISSING	PA
WHOI Traffic Separation Scheme Research Lighted Buoy AB-8	496	MISSING	PA
WHOI Traffic Separation Scheme Research Lighted Buoy AB-9	497	Status Unreported	PA
WHOI Traffic Separation Scheme Research Lighted Buoy AB-10	498	MISSING	PA
WHOI Traffic Separation Scheme Research Lighted Buoy AB-1	415	MISSING	PA

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector Boston, Exclusive Economic Zone (EEZ)/General/Hazards To Navigation/Obstructions	Hazards To Navigation	The uncrewed maritime system (UMS) Saildrone SD-2044 has been reported disabled and adrift in approximate position 42° 3.35'N, 067° 14.71'W in Closed Area II. The vessel is transmitting AIS. Vessels are requested to keep a sharp lookout and avoid the UMS.	
Sector Boston, Exclusive Economic Zone (EEZ)/General/Marine Construction (Excluding Bridges)/Survey Operations	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Survey Operations From: 2026-04-01 To: 2026-12-31 SAILDRONE INC. intends to conduct operations with up to ten Uncrewed Surface Vehicles (USVs), contracted by the United States Coast Guard District Northeast from 01 April through 31 December 2026. The SAILDRONE VOYAGER is 33 feet in length, 19 feet tall, gray in color with an orange wing, and has a tricolor light on the top wing and is marked "SAILDRONE." These vehicles will be operating in waters predominantly offshore of Maine in the New England Grey Zone area, down to 300NM off the coast of Connecticut and New York. Mariners are requested to maintain 500m CPA from the vehicle. The plan for Saildrone USVs is to transit from Portland, Maine	
General/Marine Construction (Excluding Bridges)/Survey Operations	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Survey Operations From: 2026-04-01 To: 2026-12-31 SAILDRONE INC. intends to conduct operations with up to ten Uncrewed Surface Vehicles (USVs), contracted by the United States Coast Guard District Northeast from 01 April through 31 December 2026. The SAILDRONE VOYAGER is 33 feet in length, 19 feet tall, gray in color with an orange wing, and has a tricolor light on the top wing and is marked "SAILDRONE." These vehicles will be operating in waters predominantly offshore of Maine in the New England Grey Zone area, down to 300NM off the coast of Connecticut and New York. Mariners are requested to maintain 500m CPA from the vehicle. The plan for Saildrone USVs is to transit from Portland, Maine	
Sector Boston, Exclusive Economic Zone (EEZ)/General/Marine Construction (Excluding Bridges)/Survey Operations	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Survey Operations From: 2026-09-09 To: 2026-09-30 Location: 42-18-22.572N/070-37-27.264W 42-17-51.504N/070-30-20.880W 42-14-23.892N/070-29-58.632W 42-14-46.752N/070-34-57.720W 42-18-22.572N/070-37-27.264W MASSACHUSETTS – MASS BAY – Autonomous Underwater Vehicle Operations o Mariners are advised that Anduril Maritime intends to deploy an Autonomous Underwater Vehicle (UAV) for sensor testing in a grid pattern five NM East of Minots Ledge Light bound by the following positions. 42°.304335N / 070°.616692W 42.304335N 070 .551359W/ 42 .252982N / 070 .551359W / 42 .269020N /070 .616692W. The vehicle will be deployed daily from September 9, 2026, through September 30, 2026. The UAV will be deployed, recovered daily, and monitored via the on-scene support vessels M/V Encourager, and Quincy Harbor Master. Mariners may contact the on-scene support vessels via VHF-FM CH 13/16. For more information, mariners may contact Mr. Steve Torpey at (949) 486-1263 or Ms. Kami Bucholz at (949) 392-9216. Mariners are advised to use caution when transiting the area.	

Sector Boston, Submerged Land Act (SLA)

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Boston Approach Lighted Buoy BG	385	OFF STATION	FD
The Graves Light	390	REDUCED INT	FD
Chatham Light	525	LT IMCH	FD
NOAA Data Lighted Buoy 44018	560	LT EXT	FD

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
WHOI Cape Ann Lighted Research Buoy DMON	366	OFF STATION	PA
Neptune LNG Deepwater Port Lighted Hazard Buoy	369.5	MISSING	PA
Northeast Gateway Support Vessel Mooring Buoy	374.1	MISSING	PA
ARII Lighted Research Buoy NI	12324	MISSING	PA

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector Boston, Submerged Land Act (SLA)/ATON/ATON Changes	ATON Changes	ATON/ATON Changes From: 2026-09-15 To: 2026-11-14 Location: 42-09-54.216N/070-43-23.808W Aid Name: North River Buoy 14 LLNR: 12407 Action: RELOCATE	Lat: 42° 09' 54" Lon: -070° 43' 24"
Sector Boston, Submerged Land Act (SLA)/ATON/ATON Changes	ATON Changes	ATON/ATON Changes From: 2026-09-15 To: 2026-11-14 Location: 42-09-52.308N/070-43-41.772W Aid Name: North River Buoy 16 LLNR: 12412 Action: RELOCATE	Lat: 42° 09' 52" Lon: -070° 43' 42"

Sector Boston, Submerged Land Act (SLA)/ATON/ATON Changes	ATON Changes	ATON/ATON Changes From: 2026-09-15 To: 2026-11-14 Location: 42-09-51.336N/070-43-40.764W Aid Name: North River Buoy 17 LLNR: 12415 Action: RELOCATE	Lat: 42° 09' 51" Lon: -070° 43' 41"
Sector Boston, Submerged Land Act (SLA)/ATON/ATON Changes	ATON Changes	ATON/ATON Changes From: 2026-09-15 To: 2026-11-14 Location: 42-09-49.140N/070-43-47.244W Aid Name: North River Buoy 18 LLNR: 12418 Action: RELOCATE	Lat: 42° 09' 49" Lon: -070° 43' 47"
Sector Boston, Submerged Land Act (SLA)/ATON/ATON Changes	ATON Changes	ATON/ATON Changes From: 2026-09-15 To: 2026-11-14 Location: 42-09-45.612N/070-43-52.896W Aid Name: North River Buoy 20 LLNR: 12424 Action: RELOCATE	Lat: 42° 09' 46" Lon: -070° 43' 53"
Sector Boston, Submerged Land Act (SLA)/General/MSIB	MSIB	General/MSIB From: 2026-05-05 To: 2026-11-01 Boston Harbor Approaches to Approaches to Scituate, Boston Harbor and Weymouth Fore River AIS assigned to all Aids to Navigation in the greater Boston marine area from Boston Harbor Approaches to Scituate Approaches landward to Boston Harbor and Weymouth Fore River are non-operational until further notice.	
Sector Boston MSI/Sector Boston, Submerged Land Act (SLA)/General/MSIB	MSIB	Potential Heavy Weather Impacts September 23 - 28, 2026 SUMMARY: Due to the approach of forecasted gale-force winds, the Captain of the Port, Coast Guard Sector Boston is urging the public to exercise extreme caution and strongly advising boaters against operating in adverse weather conditions. During this time, the Coast Guard's ability to respond to emergencies may be degraded. Maritime stakeholders should review continuity of operations and communication procedures, as well as methods of minimizing storm damage and environmental risk, such as riding out the storm at sea, doubling up mooring lines, securing transfers, ballasting down storage tanks and draining transfer lines. SITUATION: The National Weather Service has issued a Gale Warning for Boston Harbor, and the coastal waters of Massachusetts. Sustained northeast winds between 35-40 knots with gust exceeding 55 knots are expected. Hazardous marine conditions are expected for a sustained period from late Wednesday night to early Monday morning due to strong winds and 15–20-foot seas potentially building to 25 feet offshore. Conditions will include significant rainfall, potential for minor coastal flooding, and moderate coastal erosion due to storm surge during periods of high tide. Mariners should consider altering plans to avoid possible hazardous conditions. Remain in port, seek safe harbor, alter course, and/or secure the vessel for severe wind and waves. Marinas, Yacht Clubs, and private residents are encouraged to secure all paddle craft and small boats to prevent unintentional drifting out to sea. Due to the high winds, regional draw bridge operations may be impacted. MONITORING: Vessels at facilities shall carefully monitor their moorings and cargo operations. Vessels at anchor shall prepare for heavy winds. Additional anchor(s) should be made ready to let go and preparations shall be made to have a continuous anchor watch. Engine(s) should be made immediately available for maneuvering. Mariners should maintain a continuous listening watch on VHF Channel 16 and are advised to monitor the latest forecasts from the National Weather Service or other weather media outlets as conditions and forecasts may change. COMMUNICATIONS: For urgent safety of life issues, please contact the Sector Boston Command Center on VHF-FM Channel 16 or call (833) 449-0539. Additionally, please check USCG Navigation Center often for updates to the public from the US Coast Guard. Questions regarding this bulletin may be address to Lieutenant Commander Jessica Hull, Chief of Waterways Management Division at (617) 512-9615 or Mr. Timothy Chase, Deputy Chief of Waterways Management Division at (617) 447-1620 or email at SECBOSSWaterways@uscg.mil.	

Sector New York, Submerged Lands Act (SLA)

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Highlands Light	35025	LT IMCH	PA
Empire Offshore Wind WTG C12	604.45	LT EXT	PA

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector New York, Submerged Lands Act (SLA)/General/LAA/RNA/COTP Restriction	LAA/RNA	General/LAA/RNA/COTP Restriction From: 2026-09-16 To: 2026-09-24 A 500-meter Safety Zone will be enforced around Empire Wind operations from 8:00am, September 16, 2026, to 8:00am, September 23, 2026, Mariners are to avoid transiting within 500-meters of the following positions: C09: 40°20'25.307N, 073°26'50.160W; E08: 40°18'57.671N, 73°27'43.888W; D10: 40°19'34.629N, 73°25'59.594W; B05: 40°21'45.973N, 73°30'15.333W; D03: 40°20'50.352N, 73°32'00.051W; H15: 40°16'19.659N, 73°21'45.664W; B06: 40°21'35.981N, 73°29'23.800W; D02: 40°21'12.870N, 73°32'51.312W; B08: 40°21'15.978N, 73°27'40.747W; E07: 40°19'20.220N, 73°28'35.102W; B16: 40°19'55.714N, 73°20'48.712W; B17: 40°19'45.652N, 73°19'57.228W; F11: 40°17'49.988N, 73°25'10.306W; B04: 40°21'55.959N, 73°31'06.870W. D18: 40°18'14.268N, 73°19'07.766W; D17: 40°18'24.335N, 73°19'59.229W; C21: 40°18'24.687N, 73°16'32.370W; C20: 40°18'34.773N, 73°17'23.828W; C19: 40°18'44.853N, 73°18'15.290W; C18: 40°18'54.926N, 73°19'06.757W; C11: 40°20'05.266N, 73°25'07.150W; C10: 40°20'15.289N, 73°25'58.653W; C15: 40°19'25.110N, 73°21'41.185W; E11: 40°18'43.946N, 73°25'09.048W; D04: 40°20'27.828N, 73°31'08.799W; C01: 40°21'35.382N, 73°33'42.583W; D05: 40°20'05.299N; 73°30'17.557W; E10: 40°18'53.969N, 73°26'00.534W E06: 40°19'42.762N, 73°29'26.325W; D11: 40°19'24.606N, 73°25'08.100W; D14: 40°18'54.499N, 73°22'33.644W; D19: 40°18'04.195N, 73°18'16.307W; D20: 40°17'54.115N, 73°17'24.853W; F09: 40°18'35.116N, 73°26'52.685W. Offshore vessels include: ECO LIBERTY, C PIONEER, CROSSWAY EAGLE, PERSISTENCE LAB, ACADIA and PATRIOT LEADER. Local fishing vessels will also support this work to promote communication and safety on the waterway. Potential vessels include: PAMELA ANN, GABRIELLE ELIZABETH, TRIUNFO, BARBARA ANN, ITALIAN PRINCESS, REDEMPTION, ENFORCER, FLEET KING, FLEET QUEEN, OCEAN QUEEN, NEW HORIZON, OCEAN PRIDE, MISTER MARCO, MADISON KATE and JO ANN V.	
Sector New York, Submerged Lands Act (SLA)/General/LAA/RNA/COTP Restriction	LAA/RNA	General/LAA/RNA/COTP Restriction From: 2026-09-23 To: 2026-10-01 A 500-meter Safety Zone will be enforced around Empire Wind operations from 8:00am, September 23, 2026, to 8:00am, September 30, 2026, Mariners are to avoid transiting within 500-meters of the following positions: C09: 40°20'25.307N, 073°26'50.160W; E08: 40°18'57.671N, 73°27'43.888W; D10: 40°19'34.629N, 73°25'59.594W; B05: 40°21'45.973N, 73°30'15.333W; B16: 40°19'55.714N, 73°20'48.712W; B17: 40°19'45.652N, 73°19'57.228W; D18: 40°18'14.268N, 73°19'07.766W; D17: 40°18'24.335N, 73°19'59.229W; C19: 40°18'44.853N, 73°18'15.290W; C18: 40°18'54.926N, 73°19'06.757W. Offshore vessels include: ECO LIBERTY, C PIONEER, CROSSWAY EAGLE, PERSISTENCE LAB, ACADIA and PATRIOT LEADER. Local fishing vessels will also support this work to promote communication and safety on the waterway. Potential vessels include: PAMELA ANN, GABRIELLE ELIZABETH, TRIUNFO, BARBARA ANN, ITALIAN PRINCESS, REDEMPTION, ENFORCER, FLEET KING, FLEET QUEEN, OCEAN QUEEN, NEW HORIZON, OCEAN PRIDE, MISTER MARCO, MADISON KATE and JO ANN V.	

Sector New York, Submerged Lands Act (SLA)/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-05-01 To: 2027-04-30 Location: 40-18-11.592N/073-58-33.384W J.T. Cleary Inc. will be conducting pile driving operations in Long Branch, NJ, in position 40-18-11.6N, 073-58-33.4W, from May 1, 2026, to April 30, 2027, Monday through Friday, between 5:00am to 6:00pm. Equipment on scene will be an offshore trestle extending 200 feet from shore, monitoring VHF-FM CH 16.	Lat: 40° 18' 12" Lon: -073° 58' 33"
General/Marine Construction (Excluding Bridges)/Dredging	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Dredging From: 2025-12-10 To: 2030-09-30 North American Aggregates, LLC, will be conducting maintenance dredging for the purpose of sand mining At the eastern end of Ambrose Federal Navigation Channel, bounded by the following positions: Southeast Corner: 40o28'38.09N, 073o53'40.95W; Northeast Corner: 40o28.56.01N, 073o53'29.99W; Northwest Corner: 40o30'03.63N, 073o56'23.56W; Southwest Corner: 40o29'53.98N, 073o56'55.75W. Work Start & Stop dates and Hours of Operation: 24/7 365-days per year (weather dependent) Equipment of scene: Dredge Eleanor & Associated Notched Tug the vessel is able to move on demand for traffic And will be monitoring VHF Radio Channel Monitored: 13, 14, 65. Disposal Site/Alternative Use Determination North American Aggregates, LLC, 1250 State Street, Perth Amboy, New Jersey 08861.	

Sector Northern New England, Submerged Lands Act (SLA).

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Cape Ann Light	295	SS INOP	FD
Fir Point Ledge Lighted Buoy 3	2490	LT EXT	FD
Penobscot Bay Lighted Buoy WP	3302	MISSING	FD
Three Fathom Ledge Isolated Danger Lighted Buoy DTF	3307	MISSING	FD
The Breakers Sunken Ledge Buoy 2	3750	OFF STATION	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector Northern New England, Submerged Lands Act (SLA)/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-06-24 To: 2026-10-18 Location: 42-59-44.628N/070-43-44.328W The U.S. Coast Guard District Northeast received a Local Notice to Mariners regarding an oceanographic research project funded by the Office of Naval Research (ONR). The project, led by Jenna Hare from the University of New Hampshire, involves the deployment of a small instrumented lander measuring 3 meters on each side and 3 meters tall. The lander will be placed on the seafloor offshore from Rye Harbor State Park, New Hampshire, at coordinates 42° 59' 44.64" N, 070° 43' 44.34" W, in approximately 18 meters of water depth. The operation will run continuously, 24 hours a day, seven days a week, from June 24, 2026, through October 18, 2026. No radio frequency or passing arrangements are required, as the equipment is stationary and does not impede navigation. Mariners are advised to be aware of the presence of this research equipment in the area during the specified period.	Lat: 42° 59' 45" Lon: -070° 43' 44"
Sector Northern New England, Submerged Lands Act (SLA)/General/Marine Construction (Excluding Bridges)/Survey Operations	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Survey Operations From: 2026-04-01 To: 2026-12-31 SAILDRONE INC. intends to conduct operations with up to ten Uncrewed Surface Vehicles (USVs), contracted by the United States Coast Guard District Northeast from 01 April through 31 December 2026. The SAILDRONE VOYAGER is 33 feet in length, 19 feet tall, gray in color with an orange wing, and has a tricolor light on the top wing and is marked "SAILDRONE." These vehicles will be operating in waters predominantly offshore of Maine in the New England Grey Zone area, down to 300NM off the coast of Connecticut and New York. Mariners are requested to maintain 500m CPA from the vehicle. The plan for Saildrone USVs is to transit from Portland, Maine	
Sector Northern New England, Submerged Lands Act (SLA)/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-07-20 To: 2027-07-07 The attached Local Notice to Mariners (LNM) Information Form announces upcoming maintenance on Emms Rock Light 9 (LLNR 1305) in Englishman Bay, Maine, located at latitude 44.52899°N and longitude -67.56581°W. Fuller Marine Services Inc., represented by Chuck and Sam Fuller, will replace the steel structure and concrete cap, stabilize the stone foundation, and remove the lights. The project is scheduled to begin on July 20, 2026, and will continue until completion, with daily operations from 7:00 AM to 6:00 PM. The vessel Enzo Charles will be on site, monitoring VHF-FM Channels 16 and 13 for navigational safety, with additional contact available on Channels 09 and 22A. The Enzo Charles will ensure a clear fairway for marine traffic and will reposition as needed within 30 minutes of notification, weather and safety permitting. Mariners should coordinate passing arrangements via VHF Channel 13.	

Sector Southeastern New England, Exclusive Economic Zone (EEZ).

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
USACE Data Lighted Buoy Station 154/NDBC 44097	635	BUOY DMGD	FD

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Block Island Wind Farm WTG-3 Fog Horn	654.5	SS INOP	PA
Vineyard Wind 1 WTG AU39	600.01	LT EXT	PA
Vineyard Wind 1 WTG AS42	600.19	LT EXT	PA
Vineyard Wind 1 WTG AQ40	600.28	LT EXT	PA
Revolution Wind WTG AP11	602.65	LT EXT	PA
Vineyard Wind 1 WTG AQ39	600.16	LT EXT	PA
Vineyard Wind WTG AW38	600.0500000000001	LT EXT	PA
Vineyard Wind 1 WTG AP35	600.4300000000001	LT IMCH	PA
Vineyard Wind 1 WTG AP38	600.02	LT EXT	PA
Vineyard Wind 1 WTG AR38	600.1800000000001	LT EXT	PA
Vineyard Wind 1 WTG AN39	600.3100000000001	LT EXT	PA

Vineyard Wind Lighted Research Buoy C	589.8000000000001	ADRIFT	PA
Vineyard Wind 1 WTG AU40	600.24	LT EXT	PA
Vineyard Wind 1 WTG AR39	600.04	LT EXT	PA
Vineyard Wind 1 WTG AS41	600.13	LT EXT	PA
Revolution Wind WTG AE11	602.02	SS INOP	PA
Revolution Wind WTG AJ10	602.16	SS INOP	PA
Revolution Wind WTG AL21	602.1	SS INOP	PA
Revolution Wind WTG AP11	602.65	SS INOP	PA
Sunrise Wind WTG AU11	603.12	LT EXT	PA
Vineyard Wind 1 WTG AS40	600.17	LT EXT	PA
South Fork Wind Wave Lighted Buoy B	657.7	LT EXT	PA
Sunrise Wind WTG AU12	603.13	LT EXT	PA
Vineyard Wind 1 WTG AN38	600.21	LT EXT	PA
Revolution Wind WTG AM14	602.45	SS INOP	PA
Vineyard Wind 1 WTG AN39	600.3100000000001	LT EXT	PA

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector Southeastern New England, Exclusive Economic Zone (EEZ)/ATON/ATON Changes	ATON Changes	ATON/ATON Changes From: 2026-09-23 To: 2026-11-22 Location: 40-59-26.988N/071-15-11.088W Aid Name: Sunrise Wind WTG AU02 LLNR: 603.18 Action: CHANGE Action Type Change Light Flash Characteristic from QY to FI Y 6s.	Lat: 40° 59' 27" Lon: -071° 15' 11"
Sector Southeastern New England, Exclusive Economic Zone (EEZ)/ATON/ATON Changes	ATON Changes	ATON/ATON Changes From: 2026-09-23 To: 2026-11-22 Location: 40-59-36.276N/071-07-16.968W Aid Name: Sunrise Wind WTG AU08 LLNR: 603.44 Action: CHANGE Action Type Change Light Flash Characteristic from QY to FI Y 6s.	Lat: 40° 59' 36" Lon: -071° 07' 17"
Sector Southeastern New England, Exclusive Economic Zone (EEZ)/General/Hazards To Navigation/Hazards	Hazards To Navigation	General/Hazards To Navigation/Hazards From: 2026-08-20 To: 2026-12-31 Location: 40-58-08.472N/071-07-25.284W	Lat: 40° 58' 08" Lon: -071° 07' 25"
Approaches To New York Nantucket Shoals To Five Fathom Bank/General/Hazards To Navigation/Hazards	Hazards To Navigation	NY-NJ-ATLANTIC OCEAN-NEW YORK BIGHT-Updated 3/4/2024 Two unexploded ordnances have been located via survey approximately 25 miles east of Sandy Hook, NJ in positions, 40-22-15.667N, 073-33-49.519W and 40-20-37.821N, 073-31-11.674W in approximately depth of 26 meters (see chartlet). Mariners are urged to avoid the ordnance and transit the area with caution.	
Sector Southeastern New England, Exclusive Economic Zone (EEZ)/General/LAA/RNA/COTP Restriction	LAA/RNA	General/LAA/RNA/COTP Restriction From: 2026-09-15 To: 2026-09-24 A 500-meter Safety Zone may be enforced around Ørsted Northeast Program operations from 8:00am, September 16, 2026, to 8:00am, September 23, 2026, Mariners are to avoid transiting within 500-meters of the following positions: Revolution Wind Lease Area 486 Offshore Substations (OSS): AF08: 41-12-36.00N, 071-07-42.120W, AL11: 41-07-41.15N, 071-03-32.6W. Sunrise Wind Lease Area 487 Offshore Converter Station (OCS): AU08: 40-59-36.262N, 071-07-16.954W. Revolution Wind Lease Area 486 Wind Turbine Generator (WTG) AF09: 41-12-37.698N, 071-06-22.504W Sunrise Wind Lease Area 487 Wind Turbine Generator (WTG) AU01: 40-59-25.215N, 071-16-30.568W, AU02: 40-59-26.987N, 071-15-11.101W, AU04: 40-59-30.044N, 071-12-33.249W, AU03: 40-59-28.468N, 071-13-57.285W Northeast Program SCYLLA and supporting vessels are installing wind turbine generators (WTGs). Components are stored in New London, CT. Barge 455-8 and tugs SAM and OCEAN SUN transport one complete WTG per roundtrip. LEVIATHAN is stationed at AU08 for offshore converter station commissioning. BOKA OCEAN is installing these cables. NDEAVOR is trenching behind BOKA OCEAN. There may be areas of exposed cable. Please contact Safety Vessels on scene before conducting bottom-contacting activities. Block Island Wind Farm: R/V JIM COLE will be conducting routine surveys in and around Block Island Wind Farm this week.	
General/Marine Construction (Excluding Bridges)/Survey Operations	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Survey Operations From: 2026-04-01 To: 2026-12-31 SAILDRONE INC. intends to conduct operations with up to ten Uncrewed Surface Vehicles (USVs), contracted by the United States Coast Guard District Northeast from 01 April through 31 December 2026. The SAILDRONE VOYAGER is 33 feet in length, 19 feet tall, gray in color with an orange wing, and has a tricolor light on the top wing and is marked "SAILDRONE." These vehicles will be operating in waters predominantly offshore of Maine in the New England Grey Zone area, down to 300NM off the coast of Connecticut and New York. Mariners are requested to maintain 500m CPA from the vehicle. The plan for Saildrone USVs is to transit from Portland, Maine	

Sector Southeastern New England, Submerged Lands Act (SLA)

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Sankaty Head Light	555	Status Unreported	FD
Pollock Rip Channel Buoy 5	13540	MISSING	FD
Pollock Rip Channel Lighted Buoy 8	13550	MISSING	FD
L'Hommedieu Shoal Buoy 13	14810	Status Unreported	FD
Nantucket Harbor Range Rear Light	15165	LT IMCH	FD
Muskeget Channel Buoy 3	15365	SINKING	FD

Temporary Changes

NAME	LLNR	STATUS	AID TYPE

Oak Bluffs North Breakwater Light 2	15460	TRLB	FD
-------------------------------------	-------	------	----

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector Southeastern New England, Territorial Sea - Sector Southeastern New England, Submerged Lands Act (SLA)/ATON/ATON Changes	ATON Changes	ATON/ATON Changes From: 2026-09-15 To: 2026-11-14 Location: 41-39-14.112N/069-58-33.780W Aid Name: Southway Mid-Channel Buoy F LLNR: 13306.5 Action: RELOCATE	Lat: 41° 39' 14" Lon: -069° 58' 34"
Sector Southeastern New England, Territorial Sea - Sector Southeastern New England, Submerged Lands Act (SLA)/ATON/ATON Changes	ATON Changes	ATON/ATON Changes From: 2026-09-15 To: 2026-11-14 Location: 41-39-04.212N/069-58-23.412W Aid Name: Southway Mid-Channel Buoy G LLNR: 13306.6 Action: RELOCATE	Lat: 41° 39' 04" Lon: -069° 58' 23"
Sector Southeastern New England, Territorial Sea - Sector Southeastern New England, Submerged Lands Act (SLA)/ATON/ATON Changes	ATON Changes	ATON/ATON Changes From: 2026-09-15 To: 2026-11-14 Location: 41-39-02.412N/069-57-56.520W Aid Name: Southway Mid-Channel Buoy J LLNR: 13306.9 Action: RELOCATE	Lat: 41° 39' 02" Lon: -069° 57' 57"
Sector Southeastern New England, Territorial Sea - Sector Southeastern New England, Submerged Lands Act (SLA)/ATON/ATON Changes	ATON Changes	ATON/ATON Changes From: 2026-09-15 To: 2026-11-14 Location: 41-39-17.748N/069-57-34.740W Aid Name: Outermost Harbor Mid Channel Buoy A LLNR: 13308.95 Action: RELOCATE	Lat: 41° 39' 18" Lon: -069° 57' 35"
Georges Bank And Nantucket Shoals - Chatham Harbor Approach/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2024-08-30 To: 2039-12-31 Location: Shoaling has been reported in Old Harbor between buoys 6 and 8. Mariners are advised to use extreme caution while transiting the area.	
Georges Bank And Nantucket Shoals - Pollock Rip Channel/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	MA-NANTUCKET SOUND AND APPROACHES (Chart 13237)-POLLOCK RIP CHANNEL The entrance to Pollock Rip Channel from the East continues to have SEVERE shoaling East of Pollock Rip Lighted Buoy 4 (LLNR 13535). Mariners should not attempt to transit the area without local knowledge of the shoals and use the channel at their own risk. If transiting the channel, Mariners are urged to transit at their slowest safe speed and proceed with extreme caution.	
Sector Southeastern New England, Territorial Sea - Sector Southeastern New England, Submerged Lands Act (SLA)/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2026-05-18 To: 2027-09-30 Location: 41-39-18.108N/070-06-56.808W 41-39-18.036N/070-06-56.124W 41-39-14.508N/070-06-57.096W 41-39-14.616N/070-06-57.816W 41-39-18.108N/070-06-56.808W Shoaling has been report in Allen Harbor. The Allen Harbor entrance channel is less than 30 feet wide due to severe shoaling in the vicinity of the west jetty. Water depths have been reported less than 3 feet in the across the channel.	
Sector Southeastern New England, Territorial Sea - Sector Southeastern New England, Submerged Lands Act (SLA)/General/Marine Construction (Excluding Bridges)/Dredging	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Dredging From: 2026-05-19 To: 2027-05-18 AGM Marine Contractors, Inc. is currently working on the removal of Collier Ledge and Southwest Rock rock pile rubble in Nantucket Sound, Massachusetts, in position 41° 35' 44." N, 70°21' 08.2" W and 41°36' 26.6" N, 70° 19' 10.8" W, for the U.S. Coast Guard. The operation is scheduled to take place between June 16, 2026 and May 2027, utilizing the dredge "PRONCKAI," deck barge "THING 2," and tug "SITKA." Work will occur daily from 6 AM to 8 PM, weather permitting. The rock pile rubble will be deposited in the Yarmouth Offshore Reef Site in position 41-36-24.4N, 70-11-7.46W. All vessels will be monitoring VHF channels 13/16 and operating on channel 68. No passing arrangements are required.	

Sector Southeastern New England, Territorial Sea

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Nantucket Sound Channel Lighted Buoy 21A	13717	LT EXT	FD
West Chop Light	13775	LT EXT	FD

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Revolution Wind WTG AJ15	602.64	SS INOP	PA

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector Southeastern New England, Exclusive Economic Zone (EEZ) - Sector Southeastern New England, Territorial Sea/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-04-20 To: 2029-04-19 Location: 41.07463/-71.5385 RIDEM is deploying acoustic monitoring units with fixed structures on the seafloor. The fixed structures will remain in place on the seafloor and are roughly 40 inches wide by 14 inches in height. All mariners are advised to exercise caution if trawling or fishing along the seafloor in this area.	Lat: 41° 04' 44" Lon: -071° 32' 08"
Sector Southeastern New England, Exclusive Economic Zone (EEZ) - Sector Southeastern New England, Territorial Sea/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-04-20 To: 2029-04-19 Location: 41.13795/-71.3519 RIDEM is deploying acoustic monitoring units with fixed structures on the seafloor. The fixed structures will remain in place on the seafloor and are roughly 40 inches wide by 14 inches in height. All mariners are advised to exercise caution if trawling or fishing along the seafloor in this area.	Lat: 41° 09' 01" Lon: -071° 23' 18"
Approaches To New York Nantucket Shoals To Five Fathom Bank - Block Island/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	RI-BLOCK ISLAND-OLD HARBOR Shoaling has been reported in the entrance to Old Harbor, Block Island. Mariners are advised to proceed with caution while transiting the area.	

Sector Southeastern New England, Exclusive Economic Zone (EEZ) - Sector Southeastern New England, Territorial Sea/General/LAA/RNA/COTP Restriction	LAA/RNA	General/LAA/RNA/COTP Restriction From: 2026-09-16 To: 2026-09-24 Active work ongoing within and outside of the Wind Farm Project area. Mariners are encouraged to avoid transiting within 500-meters of the following positions while work is being performed: AQ34: 41-04-08.95267N, 070-33-02.00372W; Mariners also are strongly encouraged to operate with extreme caution and to maintain a safe distance from construction vessels and associated activities even when not located within one of the above-mentioned safety zone locations. Construction works are being conducted by the vessel SEACOR HAWK with construction and Operations and Maintenance (O&M) activities being supported by vessels ROSS CANDIES, WINDEA ENTERPRISE, WINDEA INTREPID, WINDEA FRONTIER, ROGER WILLIAMS, REBECCA H, and F/V SAINTS AND ANGELS. There also will be ongoing environmental and other survey activities within the Vineyard Wind Project Area. Vessels supporting these activities include, but are not limited to R/V CATAPULT, F/V FRUM UNDA, and F/V MISS MOLLY. There may also be safety and scout vessels from the local fishing fleet operating in the area, all monitoring VHF FM CH 13 and 16 for any concerned traffic. All Mariners are requested to give a 0.5 NM wide berth to the construction vessel and their equipment as they are extremely limited in their ability to maneuver. Passing arrangements can be made via VHF with any construction vessels. To view mariner notices and project mapping, please visit: https://www.vineyardwind.com/offshore-wind-mariner-updates .	
Sector Southeastern New England, Exclusive Economic Zone (EEZ) - Sector Southeastern New England, Territorial Sea/General/LAA/RNA/COTP Restriction	LAA/RNA	General/LAA/RNA/COTP Restriction From: 2026-09-23 To: 2026-10-01 A 500-meter Safety Zone may be enforced around Ørsted Northeast Program operations from 8:00am, September 23, 2026, to 8:00am, September 30, 2026, Mariners are to avoid transiting within 500-meters of the following positions: Revolution Wind Lease Area 486 Offshore Substations (OSS): AF08: 41-12-36.00N, 071-07-42.120W, AL11: 41-07-41.15N, 071-03-32.6W. Sunrise Wind Lease Area 487 Offshore Converter Station (OCS): AU08: 40-59-36.262N, 071-07-16.954W. Sunrise Wind Lease Area 487 Wind Turbine Generator (WTG) AU02: 40-59-26.987N, 071-15-11.101W, AU04: 40-59-30.044N, 071-12-33.249W, AU03: 40-59-28.468N, 071-13-57.285W, AU05: 40-59-31.738N, 071-11-14.283W, AW01: 40-57-25.672N, 071-16-26.852W, AT18: 41-00-49.851N, 070-54-05.926W Northeast Program SCYLLA and supporting vessels are installing wind turbine generators (WTGs). Components are stored in New London, CT. Barge 455-8 and tugs SAM and OCEAN SUN transport one complete WTG per roundtrip. LEVIATHAN is stationed at AU08 for offshore converter station commissioning. BOKA OCEAN is installing these cables. NDEAVOR is trenching behind BOKA OCEAN. There may be areas of exposed cable. Please contact Safety Vessels on scene before conducting bottom-contacting activities.	

Seekonk River

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Providence River - Seekonk River/General/Bridges/Construction	Bridges	RHODE ISLAND- WASHINGTON BRIDGE (RIDOT BRIDGE NO. 700) – SEEKONK RIVER- General Construction – Rhode Island Department of Transportation (RIDOT) will begin preliminary construction work for the new Washington Bridge. From May 18, 2026, to June 29, 2029, there will be ongoing bridge construction operations Monday-Friday from 7:00 a.m.-4:30 p.m. Construction equipment and barges will be positioned outside of the navigation channel. For the next three months, there will be no reduction to the bridge horizontal or vertical clearances and no closures to the navigation channel. Mariners are advised to exercise caution and reduce wake when transiting the area. Mariners with questions or concerns can contact the contractor via marine radio VHF-FM Ch 16 or call Andy Kerr, General Superintendent at (860) 912-7299.	Lat: 41° 49' 09" Lon: -071° 23' 13"

Shaw Cove Entrance

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
New London Harbor - Shaw Cove Entrance/General/LAA/RNA/Safety Zone	LAA/RNA	General/LAA/RNA/Safety Zone From: 2026-09-11 To: 2027-03-13 Location: 41-21-00.972N/072-05-42.000W The Coast Guard is establishing a temporary safety zone on September 12, 2026 from 8:15 p.m. through 9:30 p.m. The safety zone will cover all navigable waters of the Thames River encompassing a 600-foot radius at approximate position 41° 21' 01" N, 72° 05' 42" W, in the vicinity of New London Waterfront Park in New London, CT. No vessel or person will be permitted to enter the safety zone without obtaining permission from the COTP or a designated representative. Mariners can contact the person in charge of the Drone Show Jeff Ward during the event at (516) 369-2107	Lat: 41° 21' 01" Lon: -072° 05' 42"

Sheepscot River

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Clough Point Buoy 25	5810	OFF STATION	FD

Sheepshead Bay

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Rockaway Inlet - Sheepshead Bay/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2024-09-13 To: 2039-12-21 Location: 40.57808° N / 73.93027° W 40.57799° N / 73.92774° W 40.57476° N / 73.92804° W 40.57502° N / 73.9307° W 40.57808° N / 73.93027° W	
Rockaway Inlet - Sheepshead Bay/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2026-05-21 To: 2027-10-03 Location: 40-34-38.064N/073-55-39.936W 40-34-30.756N/073-55-38.424W 40-34-30.036N/073-55-42.672W 40-34-37.416N/073-55-44.868W 40-34-38.064N/073-55-39.936W Shoaling has been reported in Sheepshead Bay. Mariners report that only two feet of water at low tide and five feet of water at high tide when transiting around the buoys 6 and 7 buoys at the southern entrance to Sheepshead Bay NY. Mariners are advice to transit the area with extreme caution.	

Shelter Island Sound North Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Shelter Island Sound North Channel Lighted Whistle Buoy N	27960	OFF STATION	FD
Long Beach Bar Light	27975	LT EXT	FD

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Dering Harbor Buoy 7	28100	OFF STATION	PA
Stirling Basin Buoy 7	28063	OFF STATION	PA

Shelter Island Sound South Channel

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Gardiners Bay South Entrance - Shelter Island Sound South Channel/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-05-28 To: 2027-05-01 Location: 40-53-31.488N/072-17-10.608W Sound and the Sea, LLC will conduct scientific research focused on marine mammal detection and monitoring in the Atlantic Ocean south of Long Island, New York, off Mecox Bay. Four bottom-mounted passive acoustic monitoring devices will be deployed at specified coordinates: Sensor 1 (40°53'31.499" N, 72°17'10.612" W), Sensor 2 (40°52'33.985" N, 72°18'8.856" W), Sensor 3 (40°52'34.698" N, 72°19'44.666" W), and Sensor 4 (40°51'37.181" N, 72°20'42.911" W). Each device will be moored to the seafloor with a footprint of approximately one square foot and a line floating up to eight feet above the seafloor, at depths between 50 and 60 feet. The monitoring will be continuous, operating 24/7 from June 7, 2026, to May 1, 2027.	Lat: 40° 53' 31" Lon: -072° 17' 11"

Shinnecock Bay

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Shinnecock Inlet - Shinnecock Bay/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-05-28 To: 2027-05-01 Location: 40-52-33.960N/072-18-08.856W Sound and the Sea, LLC will conduct scientific research focused on marine mammal detection and monitoring in the Atlantic Ocean south of Long Island, New York, off Mecox Bay. Four bottom-mounted passive acoustic monitoring devices will be deployed at specified coordinates: Sensor 1 (40°53'31.499" N, 72°17'10.612" W), Sensor 2 (40°52'33.985" N, 72°18'8.856" W), Sensor 3 (40°52'34.698" N, 72°19'44.666" W), and Sensor 4 (40°51'37.181" N, 72°20'42.911" W). Each device will be moored to the seafloor with a footprint of approximately one square foot and a line floating up to eight feet above the seafloor, at depths between 50 and 60 feet. The monitoring will be continuous, operating 24/7 from June 7, 2026, to May 1, 2027.	Lat: 40° 52' 34" Lon: -072° 18' 09"
Shinnecock Inlet - Shinnecock Bay/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-05-28 To: 2027-05-01 Location: 40-52-34.680N/072-19-44.652W Sound and the Sea, LLC will conduct scientific research focused on marine mammal detection and monitoring in the Atlantic Ocean south of Long Island, New York, off Mecox Bay. Four bottom-mounted passive acoustic monitoring devices will be deployed at specified coordinates: Sensor 1 (40°53'31.499" N, 72°17'10.612" W), Sensor 2 (40°52'33.985" N, 72°18'8.856" W), Sensor 3 (40°52'34.698" N, 72°19'44.666" W), and Sensor 4 (40°51'37.181" N, 72°20'42.911" W). Each device will be moored to the seafloor with a footprint of approximately one square foot and a line floating up to eight feet above the seafloor, at depths between 50 and 60 feet. The monitoring will be continuous, operating 24/7 from June 7, 2026, to May 1, 2027.	Lat: 40° 52' 35" Lon: -072° 19' 45"
Shinnecock Inlet - Shinnecock Bay/General/Hazards To Navigation/Obstructions	Hazards To Navigation	General/Hazards To Navigation/Obstructions From: 2026-05-28 To: 2027-05-01 Location: 40-51-37.152N/072-20-42.900W Sound and the Sea, LLC will conduct scientific research focused on marine mammal detection and monitoring in the Atlantic Ocean south of Long Island, New York, off Mecox Bay. Four bottom-mounted passive acoustic monitoring devices will be deployed at specified coordinates: Sensor 1 (40°53'31.499" N, 72°17'10.612" W), Sensor 2 (40°52'33.985" N, 72°18'8.856" W), Sensor 3 (40°52'34.698" N, 72°19'44.666" W), and Sensor 4 (40°51'37.181" N, 72°20'42.911" W). Each device will be moored to the seafloor with a footprint of approximately one square foot and a line floating up to eight feet above the seafloor, at depths between 50 and 60 feet. The monitoring will be continuous, operating 24/7 from June 7, 2026, to May 1, 2027.	Lat: 40° 51' 37" Lon: -072° 20' 43"
Shinnecock Inlet - Shinnecock Bay/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2024-09-13 To: 2039-12-29 NY-SHINNECOCK BAY TO EAST ROCKAWAY INLET-SLOOP CHANNEL Shoaling has been reported in the vicinity of Sloop Channel Beacon 21 (LLNR - 31100). All mariners are requested to use caution when transiting the area.	

Shinnecock Inlet

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Shinnecock Inlet Breakwater Light 2	29042	REDUCED INT/STRUCT DMGD	FD

Shooters Island Channel

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Shooters Island South Channel Wreck Lighted Buoy WR1	37374	MISSING/HAZ NAV	PA

Shrewsbury River

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION

Raritan Bay - Shrewsbury River/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2024-09-13 To: 2039-12-27 Location: 40.41466° N / 74.00177° W 40.41347° N / 74.00134° W 40.41321° N / 74.0027° W 40.41428° N / 74.00315° W 40.41466° N / 74.00177° W NJ-SHREWSBURY RIVER Shoaling has been reported in the vicinity of Shrewsbury River Channel Lighted Buoy 5 (LLNR - 35755). All mariners are requested to use caution when transiting the area.	
--	-----------------------	--	--

Sloop Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Sloop Channel Light 4	31010	BUOY DMGD/TRUB	FD
Sloop Channel Buoy 19	31090	MISSING	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Jones Inlet - Sloop Channel/General/Bridges/Maintenance	Bridges	General/Bridges/Maintenance From: 2026-09-08 To: 2026-09-26 Location: 40-35-57.156N/073-32-35.592W Bridge Name: Meadowbrook State Parkway Bridge From September 8-25, 2026, Monday-Friday, 9:00 a.m.-3:00 p.m., NYCDOT will be performing bridge washing on the following bridges: - Meadowbrook State Parkway Bridge over False Channel at mile 0.7 - Meadowbrook State Parkway Bridge over Fundy Channel at mile 2.7 - Meadowbrook State Parkway Bridge over Sloop Channel at mile 12.8 - Loop Parkway Bridge over Swift Creek at mile 11.9 - Loop Parkway Bridge over Long Creek at mile 0.7 - Wantagh State Parkway Bridge over Seamans Island Creek at mile 0.5 - Wantagh State Parkway Bridge over Goose Creek at mile 16.1 - Wantagh Parkway Bridge over Sloop Channel at mile 15.4 - Robert Moses Causeway over Fire Island Inlet at mile 4 A Snooper Truck with a safety boat in the water will be utilized. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or call 631-339-4810. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 35' 57" Lon: -073° 32' 36"
Jones Inlet - Sloop Channel/General/Bridges/Maintenance	Bridges	General/Bridges/Maintenance From: 2026-09-08 To: 2026-09-26 Location: 40-36-32.000N/073-33-10.500W Bridge Name: Loop Pkwy Bridge From September 8-25, 2026, Monday-Friday, 9:00 a.m.-3:00 p.m., NYCDOT will be performing bridge washing on the following bridges: - Meadowbrook State Parkway Bridge over False Channel at mile 0.7 - Meadowbrook State Parkway Bridge over Fundy Channel at mile 2.7 - Meadowbrook State Parkway Bridge over Sloop Channel at mile 12.8 - Loop Parkway Bridge over Swift Creek at mile 11.9 - Loop Parkway Bridge over Long Creek at mile 0.7 - Wantagh State Parkway Bridge over Seamans Island Creek at mile 0.5 - Wantagh State Parkway Bridge over Goose Creek at mile 16.1 - Wantagh Parkway Bridge over Sloop Channel at mile 15.4 - Robert Moses Causeway over Fire Island Inlet at mile 4 A Snooper Truck with a safety boat in the water will be utilized. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or call 631-339-4810. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 36' 32" Lon: -073° 33' 11"
Jones Inlet - Sloop Channel/General/Bridges/Closure (Scheduled Or Emergency)	Bridges	General/Bridges/Closure (Scheduled Or Emergency) From: 2026-07-22 To: 2027-01-18 Location: 40-35-57.156N/073-32-35.592W Bridge Name: Meadowbrook State Parkway Bridge Due to a mechanical failure, the south leaves of the Meadowbrook State Parkway Bridge across Sloop Channel at mile 12.8 are inoperable until further notice. The bridge can still open in accordance with its operating schedule but can only open the north leaves of the bridge, providing open vertical clearance of 37.5' at the North side of the channel. Updates regarding the status of repairs will be provided when available. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 35' 57" Lon: -073° 32' 36"
Sloop Channel/General/Bridges	Bridges	Sloop Channel/General/Bridges From: 2026-09-01 To: 2027-01-01 Location: 40.61433, -73.50073 Bridge Name: Wantagh State Parkway Bridge From September 15, 2026 to December 31, 2026, between 6:00 a.m. and 4:00 p.m., (with occasional night work) a barge will be operated under Wantagh Parkway Bridge over Sloop Channel at mile 15.4 to perform bridge painting. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or call Dylan Thompson 516-402-4339 or David Ofsharick 516-580-1269. The barge will be moved out of the navigable channel after work hours or when not in use. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 36' 52" Lon: -073° 30' 03"
Sloop Channel/General/Bridges	Bridges	Sloop Channel/General/Bridges From: 2026-09-01 To: 2027-01-01 Location: 40.59921, -73.54322 Bridge Name: Meadowbrook State Parkway Bridge From September 15, 2026 to December 31, 2026, between 6:00 a.m. and 4:00 p.m., (with occasional night work) a barge will be operated under Meadowbrook State Parkway Bridge over Sloop Channel at mile 12.8 to perform bridge painting. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or call Dylan Thompson 516-402-4339 or David Ofsharick 516-580-1269. The barge will be moved out of the navigable channel after work hours or when not in use. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 35' 57" Lon: -073° 32' 36"

Somes Sound

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Gilpatrick Cove Daybeacon 4	2190	DAYMK MISSING	FD
Middle Rock Lighted Buoy 5	2195	LT EXT	FD
Myrtle Ledge Buoy 6	2200	MISSING	FD
Sargents Point Buoy 2SP	2205	MISSING	FD

South River

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
South River Buoy 6	12365	OFF STATION	PA

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION

New Inlet - South River/ATON/ATON Changes	ATON Changes	ATON/ATON Changes From: 2026-09-15 To: 2026-11-14 Location: 42-08-53.988N/070-42-06.696W Aid Name: South River Buoy 10 LLNR: 12375 Action: RELOCATE	Lat: 42° 08' 54" Lon: -070° 42' 07"
---	--------------	---	--

Southport Harbor

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Southport Harbor Light 7	24785	LT EXT	FD

Southwest Approach

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Pemaquid Ledge Buoy PL	5135	OFF STATION	FD
Southwest Approach Buoy 10	16780	MISSING	FD

Stage Harbor

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector Southeastern New England, Submerged Lands Act (SLA) - Stage Harbor/ATON/ATON Changes	ATON Changes	ATON/ATON Changes From: 2026-09-15 To: 2026-11-14 Location: 41-39-20.412N/069-59-04.812W Aid Name: Southway Mid-Channel Buoy A LLNR: 13306 Action: RELOCATE	Lat: 41° 39' 20" Lon: -069° 59' 05"

State Boat Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
State Boat Channel Daybeacon 3	31120	DAYMK MISSING	FD
State Boat Channel Buoy 86	31470	OFF STATION	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Fire Island Inlet - State Boat Channel/General/Bridges/Maintenance	Bridges	General/Bridges/Maintenance From: 2026-09-08 To: 2026-09-26 Location: 40-37-24.960N/073-30-05.562W Bridge Name: Wantagh State Pkwy Bridge From September 8-25, 2026, Monday-Friday, 9:00 a.m.-3:00 p.m., NYCDOT will be performing bridge washing on the following bridges: - Meadowbrook State Parkway Bridge over False Channel at mile 0.7 - Meadowbrook State Parkway Bridge over Fundy Channel at mile 2.7 - Meadowbrook State Parkway Bridge over Sloop Channel at mile 12.8 - Loop Parkway Bridge over Swift Creek at mile 11.9 - Loop Parkway Bridge over Long Creek at mile 0.7 - Wantagh State Parkway Bridge over Seamans Island Creek at mile 0.5 - Wantagh State Parkway Bridge over Goose Creek at mile 16.1 - Wantagh Parkway Bridge over Sloop Channel at mile 15.4 - Robert Moses Causeway over Fire Island Inlet at mile 4 A Snooper Truck with a safety boat in the water will be utilized. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or call 631-339-4810. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 37' 25" Lon: -073° 30' 06"
Fire Island Inlet - State Boat Channel/General/Bridges/Maintenance	Bridges	General/Bridges/Maintenance From: 2026-09-08 To: 2026-09-26 Location: 40-36-51.588N/073-30-02.628W Bridge Name: Wantagh State Parkway Bridge From September 8-25, 2026, Monday-Friday, 9:00 a.m.-3:00 p.m., NYCDOT will be performing bridge washing on the following bridges: - Meadowbrook State Parkway Bridge over False Channel at mile 0.7 - Meadowbrook State Parkway Bridge over Fundy Channel at mile 2.7 - Meadowbrook State Parkway Bridge over Sloop Channel at mile 12.8 - Loop Parkway Bridge over Swift Creek at mile 11.9 - Loop Parkway Bridge over Long Creek at mile 0.7 - Wantagh State Parkway Bridge over Seamans Island Creek at mile 0.5 - Wantagh State Parkway Bridge over Goose Creek at mile 16.1 - Wantagh Parkway Bridge over Sloop Channel at mile 15.4 - Robert Moses Causeway over Fire Island Inlet at mile 4 A Snooper Truck with a safety boat in the water will be utilized. Mariners requiring full vertical clearance can contact the contractor via marine radio VHF-FM Ch. 13/16 or call 631-339-4810. Mariners are advised to exercise caution when transiting the area.	Lat: 40° 36' 52" Lon: -073° 30' 03"
State Boat Channel/General/Bridges	Bridges	State Boat Channel/General/Bridges From: 2026-09-10 To: 2026-09-26 Location: 40.64322, -73.26357 Bridge Name: Captree State Pkwy Bridge From September 21, 2026 to September 25, 2026, an Under Bridge Inspection Unit (UBIU) will be operating at the Robert Moses Causeway Bridge across the State Boat Channel at mile 30.7 for bridge inspection. Mariners requiring full horizontal clearance can contact the contractor via marine radio VHF-FM CH. 13/16 or call George Koss at (646) 568-0004. Mariners are advised to exercise caution and reduce wake when transiting the area.	Lat: 40° 38' 36" Lon: -073° 15' 49"
Fire Island Inlet - State Boat Channel/General/LAA/RNA/Safety Zone	LAA/RNA	General/LAA/RNA/Safety Zone From: 2026-09-25 To: 2027-03-27 Mariners are advised that a safety zone will be enforced for the Ironman 70.3 at Jones Beach state Park, scheduled to be held on Zach's Bay in Wantagh, NY on September 25, 2026 through September 26, 2026 from 7 a.m. to 4 p.m. The safety zone will cover all navigable waters of Zach's Bay south of a line connecting a point near the western entrance to Zach's Bay in position at 40°36'28.47" N, 073°29'21.01" W and 40°36'26.78" N, 073°28'52.06" W, and south of a line connecting a point near the eastern entrance of the bay in position at 40°36'32.18" N, 073°28'37.45" W and 40°36'32.65" N, 073°28'21.00" W. Vessels may not enter, remain in, or transit through the Safety Zone during the enforcement period unless authorized by the Coast Guard Captain of the Port. Mariners may contact the Coast Guard on-scene commander by VHF radio channel 16.	

Stave Island To Mallets Bay Channel

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Allen Point Railroad South Light 2	39490	LT EXT	PA

Terminal Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Naval Weapon Station Earle Security Zone Lighted Buoy 1	35660	LT EXT	FD
Naval Weapon Station Earle Security Zone Lighted Buoy 6	35685	OFF STATION	FD

Thames River

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
New London Harbor - Thames River/General/Marine Construction (Excluding Bridges)/Dredging	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Dredging From: 2026-10-01 To: 2027-01-31 Location: 41-24-01.692N/072-05-47.040W Cashman Dredging and Marine Contracting Co., LLC plans to begin dredging operations on or about October 1, 2026, for the Naval Submarine Base New London Pier 31 Extension project in Groton, Connecticut. Work will occur in the Thames River adjacent to Naval Submarine Base New London/Pier 31in position 41°24'01.720"N, 72°05'47.050"W and is expected to continue through January 31, 2027, operating 24 hours per day, seven days per week. The project is authorized under U.S. Army Corps of Engineers Permit No. NAE-2023-00668. Equipment may include the dredge Icarus, split-hull dump scows Joe V and Eddie C, a survey boat, tugboats, and other support equipment. Project vessels will monitor VHF Channels 16 and 13, with a working channel to be determined. Mariners transiting the area should proceed with caution, maintain a safe distance from dredging equipment, and coordinate passing arrangements by VHF radio. Dredged material will be transported to the U.S. Navy Confined Aquatic Disposal Cell Center. Mariners requiring passage through the work area are encouraged to provide advance notice when practicable, as clearing the navigation area may take approximately 30 minutes depending on conditions.	Lat: 41° 24' 02" Lon: -072° 05' 47"

The Nummet Channel

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Kingston Channel Buoy 42	12895	MISSING	PA
Kingston Channel Buoy 40	12890	MISSING	PA

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Plymouth Bay - The Nummet Channel/ATON/ATON Changes	ATON Changes	ATON/ATON Changes From: 2026-09-16 To: 2026-11-15 Location: 41-59-17.016N/070-39-55.800W Aid Name: USGS Lighted Research Buoy A LLNR: 12582 Action: RELOCATE	Lat: 41° 59' 17" Lon: -070° 39' 56"
Plymouth Bay - The Nummet Channel/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	MA-NUMMET CHANNEL (REVISED) The Coast Guard has received a report of shoaling in the vicinity of The Nummet Channel Buoy 7 (LLNR 12760). Mariners are advised to proceed with caution when transiting the area.	

The Raunt Channel

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
North Channel - The Raunt Channel/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2024-09-13 To: 2039-10-20 Location: 40.60215° N / 73.83815° W 40.60189° N / 73.8372° W 40.60065° N / 73.83424° W 40.59977° N / 73.83497° W 40.60104° N / 73.83772° W 40.60147° N / 73.8387° W 40.60215° N / 73.83815° W NY-RAUNT CHANNEL (Booklet Chart 12350 JAMAICA BAY Recent surveys have shown significant shoaling in the Raunt Channel. Shoaling exists in the vicinity of Buoy 6, in approximate position 40-36.17N 073-50.47W. Depths of less than 5 feet in the middle of the channel. Navigation of the area requires extreme caution due to the encroaching nature of the shoal.	

The Reach

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
The Reach Rock Lighted Buoy 2	3765	OFF STATION	FD

Threemile Harbor

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Threemile Harbor East Breakwater Light	27790	DAYMK MISSING	PA

Tiverton Upper Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Tiverton Upper Channel Buoy 2	18815	OFF STATION	FD

Troy Dam

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Hudson River - Troy Dam/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-05-11 To: 2026-11-30 Location: 42-42-03.996N/073-41-09.996W Carteret Marine Services will be conducting marine construction operations at the Troy Locks, Hudson River, in position 42-45-04N, 073-41-10W, from May 11, 2026, to November 30, 2026, between 7:00am to 5:00pm. Equipment on scene will be a barge and vessel, monitoring VHF-FM CH 8 & 16.	Lat: 42° 42' 04" Lon: -073° 41' 10"

Union River Channel

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Union River Channel Buoy 2	2445	MISSING	FD
Union River Channel Lighted Buoy 6	2455	MISSING	FD
Union River Channel Lighted Buoy 6	2455	MISSING	FD
Union River Channel Buoy 7	2460	MISSING	FD
Union River Channel Buoy 9	2465	MISSING	FD
Union River Channel Buoy 11	2470	MISSING	FD

Upper Kennebec River

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Kennebec River - Upper Kennebec River/General/Marine Events/Fireworks	Marine Events	ME –Old Hallowell Day – Hallowell – Fireworks Mariners are advised that the Old Hallowell Day Fireworks are scheduled to be held around the Kennebec River near the vicinity of Hallowell, ME. The event will be held from 09:00 p.m. to 09:30 p.m. on July 18, 2026. Chart number: 13260. For event information contact: Steven Marson, (207)242-9013.	Lat: 44° 17' 17" Lon: -069° 47' 16"

Upper Thames River

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Thames River Buoy 23	22110	OFF STATION	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Thames River - Upper Thames River/ATON/ATON Changes	ATON Changes	ATON/ATON Changes From: 2026-09-23 To: 2026-10-23 Location: 41-26-28.572N/072-05-11.364W Aid Name: Thames River Buoy 21 LLNR: 22090 Action: ESTABLISH This aid will be established in the next two weeks.	Lat: 41° 26' 29" Lon: -072° 05' 11"
Thames River - Upper Thames River/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2024-10-23 To: 2027-05-31 Location: 41-26-39.480N/072-05-03.984W CT-THAMES RIVER-GALES FERRY Sterling Equipment, Inc, will be storing rental fleet barges in position 41-26-39.5N 072-05-04.0W, until May 2027. Equipment on scene will be Spud Barges, Hopper Barge and Deck Barges, which will be outside the navigable channel and will not impede navigation. Point of contact for this operation is Mark Quinn, who can be reached at (617) 984-0022 or at mark@sterlingequipment.com. Mariners are requested to give adequate clearance to the equipment and transit at their slowest safe speed to minimize wake.	Lat: 41° 26' 39" Lon: -072° 05' 04"

Warwick Cove

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Greenwich Bay - Warwick Cove/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	RI-NARRAGANSETT BAY (CHART 13221)-GREENWICH BAY-WARWICK COVE Shoaling has been observed within the federal navigation channel to a least depth of 3 FT MLW. Shoaling is encroaching from the west and has impacted the western part of the channel, reducing the authorized project width from 150 feet to approx. 90 feet between Warwick Cove Buoy 3 (LLNR 19360) and Warwick Cove Buoy 7 (LLNR 19375).	

Waterway Name Not Found

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Massapequa Cove Daybeacon 4	34200	DAYMK DMGD	PA
Carman Creek Daybeacon D8	34155	DAYMK MISSING	PA
Carman Creek Daybeacon D10	34160	DAYMK MISSING	PA
Carman Creek Daybeacon D6	34150	DAYMK MISSING	PA
Amity Channel Light 94	34075	LT EXT	PA

Wellfleet Harbor

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Billingsgate Shoal Lighted Bell Buoy 1	13160	OFF STATION	FD
James Longstreet Isolated Danger Lighted Buoy DJ	13174	OFF STATION/TRLB	FD
Billingsgate Flat Lighted Buoy 3	13180	MISSING	FD
Billingsgate Lighted Buoy 5	13185	SINKING	FD
Wellfleet Harbor Channel Buoy 12	13210	OFF STATION	FD

Wells Harbor

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Wells Harbor Daybeacon 3	8220	DBD DMGD	FD

West Passage

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Approaches To New York Nantucket Shoals To Five Fathom Bank - West Passage/General/Hazards To Navigation/Hazards	Hazards To Navigation	RI- NARRAGANSETT BAY - WEST PASSAGE – UNEXPLODED ORDNANCE-UPDATE 9/2/2022 Sixteen (16) unexploded ordnances have been located via survey in Narragansett Bay – West Passage in positions: (1.) 41-27-7.68N 071-24-35.64W; (2.) 41-27-25.74N 071-24-38.94W; (3.) 41-27-33.60N 071-24-38.34W (4.) 41-24-49.80N 071-22-58.14W (5.) 41-26-40.32N 071-24-42.54W (6.) 41-26-34.44N 071-24-8.22W; (7.) 41-26-00.18N 071-24-30.48W;(8.) 41-28-00.96N 071-24-28.68W; (9.) 41-24-43.74N 071-4.26.40W; (10.) 41-24-56.52N 071-21-59.64W; (11.) 41-24-52.62N 071-23-43.62W; (12.) 41-27-38.88N 071-24-6.978W; (13.) 41-26-4.324N 071-24-30.591W; (14.) 41-27-36.236N 071-24-37.026N; (15.) 41-26-44.709N 071-24-38.97W; (16.) 41-24-45.927N 071-21-39.508W. Mariners are urged to avoid the ordnances and transit the area with caution.	
Sector Southeastern New England, Submerged Lands Act (SLA) - West Passage/General/Hazards To Navigation/Hazards	Hazards To Navigation	General/Hazards To Navigation/Hazards From: 2026-05-04 To: 2026-10-31 Location: 41-28-15.024N/071-25-25.500W 41-28-07.860N/071-25-25.500W 41-28-06.060N/071-25-34.932W 41-28-13.296N/071-25-35.400W 41-28-15.024N/071-25-25.500W A load of concrete pilings were reported on the seafloor. It is unclear how the pilings are oriented at this time. All mariners are advised to exercise extreme caution and to avoid the area given the uncertain depth of the obstructions.	
Sector Southeastern New England, Submerged Lands Act (SLA) - West Passage/General/Marine Construction (Excluding Bridges)/Survey Operations	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Survey Operations From: 2026-08-27 To: 2026-10-01 Anduril Industries will be conducting autonomous underwater vehicle testing in Rhode Island Sound, Rhode Island. The work is scheduled to occur from September 2 through September 30, 2026, during daily operating hours of 0600 to 1800. The testing area is defined by four latitude/longitude points in Rhode Island Sound and is associated with chart number US3RI1AA. The operation will involve a 19-foot autonomous underwater vehicle and the support vessel F/V Voyager. Vessels on scene may be contacted on VHF Channels 16 and 13. The form notes that once the AUV is submerged and conducting its mission, it will have restricted ability to maneuver until it reaches its pre-set destination.	
Sector Southeastern New England, Submerged Lands Act (SLA) - West Passage/General/Marine Construction (Excluding Bridges)/Survey Operations	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Survey Operations From: 2026-08-31 To: 2026-10-02 From August 31 to October 1, 2026, sunrise to sunset, manned and unmanned wing-in-ground effect vehicles will conduct surface and ground-effect testing in the West Passage of Narragansett Bay. The vehicles will launch from the Port of Davisville and may operate at speeds up to 60 knots. Mariners should transit the area with extreme caution. REGENT support vessel SEABEE will monitor VHF Channel 16 for concerned traffic. Additional testing dates will be announced.	
Sector Southeastern New England, Submerged Lands Act (SLA) - West Passage/General/Miscellaneous	Miscellaneous	General/MISC From: 2026-06-16 To: 2026-06-19 Sunrise to sunset And further testing dates to be announced. Unmanned remote controlled vehicles will be conducting surface and aerial ground effect testing in the West Passage, Narragansett Bay, with speeds up to 50 knots. The unmanned vehicles will launch from the Port of Davisville. Mariners are advised to transit the area with extreme caution. "REGENT support boat Nautaplane will be standing by on Ch 13/16.	
Sector Southeastern New England, Submerged Lands Act (SLA) - West Passage/General/Miscellaneous	Miscellaneous	General/Marine Construction (Excluding Bridges)/Survey Operations From: 2026-08-27 To: 2026-10-01 Anduril Industries will be conducting autonomous underwater vehicle testing in Rhode Island Sound, Rhode Island. The work is scheduled to occur from September 2 through September 30, 2026, during daily operating hours of 0600 to 1800. The testing area is defined by four latitude/longitude points in Rhode Island Sound and is associated with chart number US3RI1AA. The operation will involve a 19-foot autonomous underwater vehicle and the support vessel F/V Voyager. Vessels on scene may be contacted on VHF Channels 16 and 13. The form notes that once the AUV is submerged and conducting its mission, it will have restricted ability to maneuver until it reaches its pre-set destination.	

West Penobscot Bay

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Porterfield Ledge Daybeacon	4270	DAYMK DMGD	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Sector Northern New England, Submerged Lands Act (SLA) - West Penobscot Bay/General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Facilities, Barriers, Manmade Reefs, Riprap, Jetties/Dikes From: 2026-08-20 To: 2027-07-07 The attached Local Notice to Mariners (LNM) Information Form outlines upcoming maintenance work on the Porterfield Ledge Daybeacon (LLNR 4270), located in Rockport Harbor, Maine at latitude 44°09'14.6"N and longitude 69°03'41.3"W. Fuller Marine Services Inc., led by Sam and Chuck Fuller, will conduct activities to replace the steel structure, cap the granite superstructure, and stabilize the stone base. The project is scheduled to begin August 20, 2026, and will continue until completion, with daily operations from 7:00 AM to 6:00 PM. The vessel Enzo Charles will be present, monitoring VHF-FM Channels 16 and 13 for navigational safety, with secondary contact available on Channels 09 and 22A. To ensure safe passage, the Enzo Charles will maintain a clear fairway and reposition as needed within 30 minutes of notification, weather and safety permitting. Mariners should coordinate passing arrangements via VHF Channel 13	

Western Way.

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Spectacle Island Lighted Hazard Buoy C	11587	MISSING	PA

Westport Harbor

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Westport Harbor Approach Lighted Bell Buoy 1	17445	LT EXT	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Buzzards Bay Main Channel - Westport Harbor/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	General/Hazards To Navigation/Shoaling Reported From: 2024-08-30 To: 2039-12-31 Location: Westport Channel has experienced significant shoaling, with considerable narrowing of the federal channel. Aids to navigation have been relocated outside the federal channel, to mark best water. Mariners are advised that shoaling has been identified and is unpredictable outside the federal channel, affecting both commercial and recreational vessels. Mariners without local knowledge are advised to transit with extreme caution and only during plus tides. Mariners are urged to use caution while transiting the area.	
Buzzards Bay Main Channel - Westport Harbor/General/Hazards To Navigation/Shoaling Reported	Hazards To Navigation	MA-MARTHA'S VINEYARD TO BLOCK ISLAND (Chart 13218)-WESTPORT HARBOR Shoaling exists in Westport Harbor in the vicinity of Westport Harbor Channel LB 14 (LLNR 17490) and Westport Harbor Channel Buoy 17 (LLNR 17505). There are other areas of shoaling throughout the Westport Harbor Channel reducing the available depth of water. Mariners are advised to use caution while navigating this area	

Weweantic River

Federal Discrepancies

NAME	LLNR	STATUS	AID TYPE
Wareham River Buoy 13	17250	OFF STATION	FD

Private Discrepancies

NAME	LLNR	STATUS	AID TYPE
Wareham Regulatory Buoy A	null	OFF STA	PA
Weweantic River Buoy 15	17297.5	Status Unreported	PA

Temporary Changes

NAME	LLNR	STATUS	AID TYPE
Wareham River Buoy 28	17295	DISCONTINUED FOR DREDGING	FD

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Buzzards Bay Main Channel - Weweantic River/General/Bridges/Construction	Bridges	Massachusetts Department of Transportation (MassDOT) will conduct bridge demolition and replacement operations on the Route 6 Bridges over the Weweantic River in Marion and Wareham, MA. Beginning May 1, 2026 through September 10, 2028, multiple work boats, barges, cranes, and support equipment will be operating in the vicinity of the bridges. Construction activities may occur within multiple spans and channels; however, a navigable channel will remain open at all times. Construction equipment, including barges, cofferdams, and work platforms, will be present within and adjacent to the navigable channel. Short-term channel restrictions may occur during active construction operations, including pile driving, sheeting, and erection activities, and will be limited to periods when such operations are in progress. Mariners are advised to exercise caution and reduce wake when transiting the area. Mariners with questions or concerns may contact the contractor via VHF-FM Channels 13/16 or call Don Smith (413) 262-3687 or Jay Krutiak (413) 770-1723.	Lat: 41° 44' 17" Lon: -070° 44' 48"

Buzzards Bay Main Channel - Weweantic River/General/Marine Construction (Excluding Bridges)/Dredging	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Dredging From: 2026-06-17 To: 2026-10-01 Location: 41-44-57.768N/070-42-18.216W AGM Marine Contractors, will be conducting dredging operations in the Wareham River, Wareham, Massachusetts, in position 41-44-57.75N, 070-42-18.21W. The project is scheduled to run from July 1, 2026, through September 31, 2026, and will operate continuously, seven days a week, 24 hours per day. The equipment involved includes the Dredge Triton, crane, scow, and tugs. To ensure safe navigation, vessels in the area can contact the operation on radio frequency 66 and are advised to provide a 15-minute notice for passing arrangements, with the dredging vessel remaining out of the channel when necessary.	Lat: 41° 44' 58" Lon: -070° 42' 18"
--	---	---	--

Weymouth Fore River

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Nantasket Roads Southern Approach - Weymouth Fore River/General/Bridges/Inspection	Bridges	General/Bridges/Inspection From: 2026-10-01 To: 2026-10-08 Location: 42-14-40.776N/070-58-01.236W Bridge Name: Fore River Bridge MASSACHUSETTS – WEYMOUTH FORE RIVER – Bridge Inspection Mariners are advised that ATANE Engineers will be conducting an inspection of the Weymouth Fore River Bridge commencing October 1st, 2026, through October 8th, 2026. Work hours will be from 8:00 a.m. to 3:00 p.m. for the duration of the project. All work will be conducted from a road level snooper truck suspended below the bridge deck up to 50 feet. The Bridge will open for vessels requiring a lift with 30 minutes advanced notice. The bridge tender will remain on scene for the duration of the inspection and may be contacted at (617) 774-0143. Questions may be directed to ATANE Mr. Bryan Slater at (203) 525-9992. The on-scene safety vessel may be reached via VHF-FM CH 13/16 Mariners are advised to plan transits accordingly.	Lat: 42° 14' 41" Lon: -070° 58' 01"

Wollaston Channel

Additional MSI Categories

TITLE	SUBCATEGORY	DESCRIPTION	LOCATION
Western Way - Wollaston Channel/General/Marine Construction (Excluding Bridges)/Survey Operations	Marine Construction (Excluding Bridges)	General/Marine Construction (Excluding Bridges)/Survey Operations From: 2026-06-03 To: 2026-09-30 Location: 42-16-50.988N/070-59-08.988W • Autonomous surface vessel (ASV) by Sedna Robotics in Quincy Bay, Massachusetts, from June 8 to September 30, 2026. The ASV, named "Warden," is a 7-foot vessel with a yellow hull, marked "Uncrewed / Research Vessel," and transmits as "Uncrewed" on AIS. Operations are scheduled to run 24 hours a day, seven days a week at coordinates 42° 16' 51"N, 70° 59' 9"W. It will operate within a 50-foot radius, station-keeping, and may transit at 2 knots during daytime hours. The vessel will display a flashing amber beacon at night and can be repositioned within 30 minutes upon request via the Sedna operations line, which is available 24/7 and displayed on the vessel. Launch and recovery will occur at Perry Beach, Quincy, MA. Operations are scheduled to run 24 hours a day, seven days a week at coordinates 42° 16' 51"N, 70° 59' 9"W autonomous surface vessel (ASV) by Sedna Robotics in Quincy Bay, Massachusetts, from June 8 to September 30, 2026. The ASV, named "Warden," is a 7-foot vessel with a yellow hull, marked "Uncrewed / Research Vessel," and transmits as "Uncrewed" on AIS. It will operate within a 50-foot radius, station-keeping, and may transit at 2 knots during daytime hours. The vessel will display a flashing amber beacon at night and can be repositioned within 30 minutes upon request via the Sedna operations line, which is available 24/7 and displayed on the vessel. Launch and recovery will occur at Perry Beach, Quincy, MA.	Lat: 42° 16' 51" Lon: -070° 59' 09"